CDOT

CONSTRUCTION MANUAL

COLORADO
DEPARTMENT
OF TRANSPORTATION

2002

[Page Intentionally Blank]

NOTICE

Registration Form and Notice of Needed Corrections

Complete and return this registration form to receive revisions to this *Manual*. CDOT employees are not required to submit this form as updates will be posted under Public Announcements or by e-mail to Resident Engineers. Mail or fax this form to:

Colorado Department of Transportation
Project Development Branch
4201 East Arkansas Avenue, Suite 290
Denver, CO 80222-3400
Fax: (303) 757-9820

Company/Organization Name:_____
Contact Person:_____
Street Address:_____
City:_____
State:_____ Zip Code:_____
Telephone Number: (_____)_____

NOTES:_____
_____
_____
_____
_____
_____
_____

NOTES:

FOREWORD

The *CDOT Construction Manual* is an operational manual of the Colorado Department of Transportation (CDOT). It defines the criteria and procedures to be used by engineering personnel in the administration of construction contracts.

The *Manual* was prepared and is maintained by the Project Development Branch under the authority of, and at the direction of, the Chief Engineer.

Although the *Manual* follows the general outline of the *Standard Specifications*, it is not a specification and should not be interpreted as such. Any section references are specific to this *Manual* unless otherwise noted.

Suggestions and/or comments for improvement, clarification, correction, and/or inclusion of material in the *Manual* are welcome. Please forward your comments to the Project Development Branch using the Registration Form and Notice of Needed Corrections in the front of this *Manual*.

The instructions and procedures in this *Manual* are written and intended for use by Project Engineers and Project Inspectors. The *Manual* is available for purchase from CDOT.

REVISIONS

The *Manual* will be revised as methods, materials, policies, procedures, specifications, and the industry change. CDOT will make revisions to the *Manual* available at http://www.dot.state.co.us/DevelopProjects/designsupport/.

It is the *Manual* holder's responsibility to keep the *Manual* current.

ACKNOWLEDGEMENTS

With a special thanks to task force members –

- Darryl Carlson, Region 3
- Scott Ellis, Region 4
- Mark Gosselin, Region 4
- Irene Stumpf, Region 4
- Carol Hoisington, Region 6
- Jacob Koenig, Region 6
- Beth Ann Wieder, Region 6
- Hal Toland, Area Engineer
- James Zufall, Area Engineer
- Karen L. Sullivan, Assistant Area Engineer
- Sandra Wilmoth, Standards and Specifications

who agreed to participate in the rewrite of the *CDOT Construction Manual* almost two years ago, little realizing the hundreds of hours that would be required.

Also, with special thanks to Randall Burks, Project Manager, of Roy Jorgensen Associates, Inc., for his expertise in managing the preparation and development of the *CDOT Construction Manual*.

A special note of thanks to Chris Horn, FHWA; Dana Christensen, Staff Bridge Branch; Karen Gonzales, CDOT Emerging Small Business Program; Judith Lamb, CDOT Center for Equal Opportunity; and Mary Townsend, CDOT Program and Project Analysis Unit, Contracts and Market Analysis Branch for writing and rewriting material for this manual. Tim Aschenbrener of Materials and Geotechnical Branch lent considerable staff to this effort.

For the many other CDOT and FHWA staff who contributed their expertise to this update and rewrite of the *CDOT Construction Manual*, my thanks.

Larry Brinck
Standards & Specifications Engineer

Table of Contents

Section **Page**

100 GENERAL PROVISIONS 100-1
101 GENERAL GUIDELINES 100-1

101.1 – 101.100 RESERVED
101.101 SOURCE DOCUMENTS 100-1
101.102 CDOT INTERNET AND INTRANET WEB SITE 100-2
101.103 CDOT ORGANIZATION AND STAFF 100-2

101.103.1 Chief Engineer 100-2
101.103.2 Project Development Branch Manager 100-2
101.103.3 Region Transportation Director 100-3
101.103.4 Region Program Engineer 100-3
101.103.5 Resident Engineer 100-4
101.103.6 Project Engineer 100-4
101.103.7 Project Inspector (Materials Tester) 100-5
101.103.8 Staff Bridge Branch 100-5

101.103.8.1 Quality Assurance Inspectors (Fabrication Inspectors) 100-5
101.103.8.2 Bridge Construction Assistance 100-6

101.104 QUALITY CONTROL/QUALITY ASSURANCE (QC/QA) 100-6
101.105 FHWA INVOLVEMENT 100-6
101.106 AASHTO SITEMANAGER® OVERVIEW AND WORKFLOW 100-7

102 BIDDING REQUIREMENTS AND CONDITIONS 100-9

102.1 PREQUALIFICATION OF BIDDERS 100-9
102.2 – 102.4 RESERVED
102.5 EXAMINATION OF PLANS, SPECIFICATIONS, SPECIAL PROVISIONS, AND SITE OF WORK 100-9

102.5.1 Pre-Bid Conference 100-9
102.5.2 Project Showings 100-10

102.6 RESERVED
102.7 IRREGULAR PROPOSALS 100-10

103 AWARD AND EXECUTION OF CONTRACT 100-11
104 SCOPE OF WORK 100-13

104.1 INTENT OF CONTRACT 100-13
104.2 DIFFERING SITE CONDITIONS, SUSPENSIONS OF WORK, AND SIGNIFICANT CHANGES IN THE CHARACTER OF WORK 100-13
104.3 EXTRA WORK 100-14
104.4 MAINTAINING TRAFFIC 100-14
104.5 – 104.6 RESERVED
104.7 VALUE ENGINEERING CHANGE PROPOSALS BY THE CONTRACTOR 100-15

Table of Contents

Section **Page**

105 CONTROL OF WORK 100-17

105.1 AUTHORITY OF THE ENGINEER 100-17

105.1.1 Quality in Construction 100-17

105.1.1.1 CDOT Commitment 100-18
105.1.1.2 Local Support 100-18

105.1.2 Partnering 100-18

105.1.2.1 Benefits of Partnering 100-18
105.1.2.2 Partnering Process 100-19

105.2 PLANS, SHOP DRAWINGS, WORKING DRAWINGS AND CONSTRUCTION DRAWINGS 100-20

105.2.1 Working Drawing Review 100-20
105.2.2 Falsework Certification 100-21
105.2.3 Shop Drawing Review Process 100-21
105.2.4 Construction Drawings 100-22

105.3 CONFORMITY WITH PLANS AND SPECIFICATIONS 100-23

105.3.1 Use of Price Reductions 100-23
105.3.2 Price Reductions for Nonconforming Materials 100-23
105.3.3 Price Reductions for Nonconforming Work 100-24

105.3.3.1 Reasonably Acceptable Work 100-24

105.3.3.1.1 Contract Items without “F” Factors 100-24
105.3.3.1.2 Contract Items with “F” Factors 100-25

105.3.3.2 Unacceptable Work 100-26

105.3.4 Quality Control/Quality Assurance (QC/QA) Specifications 100-26

105.3.4.1 Cooperation and Communication 100-26
105.3.4.2 Quality Level 100-27
105.3.4.3 Incentive/Disincentive Payments 100-27
105.3.4.4 Acceptance Sampling 100-27

105.4 COORDINATION OF PLANS, SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, AND SPECIAL PROVISIONS 100-29
105.5 COOPERATION BY CONTRACTOR 100-29
105.6 COOPERATION WITH UTILITIES 100-29
105.7 COOPERATION BETWEEN CONTRACTORS 100-30
105.8 CONSTRUCTION STAKES, LINES, AND GRADES 100-30
105.9 AUTHORITY AND DUTIES OF THE PROJECT ENGINEER 100-31

Table of Contents

Section **Page**

105.9.1 Authority of Project Engineers 100-31
105.9.2 Commitment to Quality 100-31
105.9.3 Problem Resolution 100-31
105.9.4 Quality of Workmanship 100-32
105.9.5 Assessing Acceptability of Work 100-32

105.10 DUTIES OF THE PROJECT INSPECTOR 100-33
105.11 INSPECTION AND TESTING OF WORK 100-33
105.12 REMOVAL OF UNACCEPTABLE WORK AND UNAUTHORIZED WORK 100-34
105.13 LOAD RESTRICTIONS 100-34
105.14 MAINTENANCE DURING CONSTRUCTION 100-35
105.15 FAILURE TO MAINTAIN ROADWAY OR STRUCTURE 100-35
105.16 ACCEPTANCE 100-35

105.16.1 Partial Acceptance 100-35
105.16.2 Final Acceptance 100-35

105.17 DISPUTES AND CLAIMS FOR CONTRACT ADJUSTMENTS 100-36

105.17.1 General 100-36

105.17.1.1 Clams Evaluations 100-36
105.17.1.2 Claim Status Report 100-36
105.17.1.3 FHWA Involvement 100-37

105.17.2 Claim Processing Procedures 100-37

105.17.2.1 Claim Notification 100-37
105.17.2.2 Contractor's Claim Package 100-38
105.17.2.3 Review of Claim Package 100-39
105.17.2.4 Preparation of Official Claim Record 100-40

106 CONTROL OF MATERIAL 100-43

106.1 SOURCE OF SUPPLY 100-43
106.2 – 106.7 RESERVED
106.8 BUY AMERICA REQUIREMENTS 100-43
106.9 CERTIFICATES OF COMPLIANCE 100-44

107 LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC 100-45

107.1 LAWS TO BE OBSERVED 100-45

107.1.1 Davis-Bacon Act 100-45

107.1.1.1 FHWA Form 1273 100-45
107.1.1.2 Weekly Payrolls 100-46

107.1.2 Processing Requests for CDOT Records 100-46

Table of Contents

Section **Page**

107.1.2.1 Colorado Open Records Act 100-46
107.1.2.2 CDOT Review of Written Requests 100-46

107.1.3 Equal Employment and Civil Rights Considerations 100-46

107.1.3.1 Disadvantaged Business Enterprises 100-46
107.1.3.2 Discrimination and Sexual Harassment Complaints 100-47
107.1.3.3 Form 280 100-47
107.1.3.4 FHWA Form 1391 100-47

107.1.4 On-the-Job Training 100-48

107.1.4.1 Standard On-the-Job Training Program 100-48
107.1.4.2 Colorado On-the-Job Training Program 100-48
107.1.4.3 Projects Offering Both On-the-Job Training Programs 100-48

107.1.5 Emerging Small Business Program 100-48

107.1.5.1 First-Time Reimbursement Payment 100-48
107.1.5.2 Hourly Reimbursement 100-49
107.1.5.3 Bonding Assistance 100-50

107.1.6 Drug-Free Workplace 100-50

107.2 PERMITS, LICENSES, AND TAXES 100-50
107.3 – 107.5 RESERVED
107.6 SANITARY, HEALTH, AND SAFETY PROVISIONS 100-51

107.6.1 *CDOT Safety Manual* 100-51
107.6.2 Safety Equipment 100-51
107.6.3 Responsibilities and Authority 100-51

107.7 – 107.9 RESERVED
107.10 BARRICADES AND SIGNS 100-52
107.11 – 107.12 RESERVED
107.13 FOREST PROTECTION 100-53

107.13.1 Preservation of Wetland Areas and Plant and Animal Habitats 100-53
107.13.2 Preservation of Trees and Shrubs 100-53

107.14 RESERVED
107.15 RESPONSIBILITY FOR DAMAGE CLAIMS 100-53
107.16 OPENING SECTIONS OF PROJECT TO TRAFFIC 100-54
107.17 CONTRACTOR RESPONSIBILITY FOR WORK 100-54
107.18 – 107.22 RESERVED
107.23 ARCHAEOLOGICAL AND PALEONTOLOGICAL DISCOVERIES 100-56

107.23.1 Site Investigation 100-56
107.23.2 Discovery During Construction 100-56

Table of Contents

Section **Page**

107.24 RESERVED
107.25 WATER QUALITY CONTROL 100-56

107.25.1 General 100-56
107.25.2 Contractor Responsibility 100-57
107.25.3 Internal CDOT Coordination 100-57
107.25.4 Permit and Reporting Requirements 100-57
107.25.5 Waste Disposal Practices 100-58
107.25.6 Spill Prevention Practices 100-59

108 PROSECUTION AND PROGRESS 100-61

108.1 SUBLETTING OF CONTRACT 100-61
108.2 NOTICE TO PROCEED 100-61
108.3 SCHEDULE 100-61
108.4 LIMITATION OF OPERATIONS 100-62
108.5 CHARACTER OF WORKERS; METHODS AND EQUIPMENT 100-62

108.5.1 Personnel and Equipment Considerations 100-62
108.5.2 Removal of Project Personnel 100-63

108.6 DETERMINATION AND EXTENSION OF CONTRACT TIME 100-63

108.6.1 General 100-63
108.6.2 Methods of Determining Contract Time 100-64
108.6.3 Factors Influencing Contract Time 100-65
108.6.4 Guidelines for Preparing Form 859 100-66
108.6.5 Guidelines for Charging and Reporting Project Time 100-68

108.6.5.1 Form 262 and Form 263 100-68
108.6.5.2 Progress Schedule Considerations 100-68
108.6.5.3 Charges for Full Working Days 100-69
108.6.5.4 Charges for Less Than Full Working Days 100-70
108.6.5.5 Charges for Free Time 100-72
108.6.5.6 Challenges by the Contractor 100-72

108.6.6 Extension of Contract Time 100-72

109 MEASUREMENT AND PAYMENT 100-75

109.1 MEASUREMENT OF QUANTITIES 100-75

109.1.1 Scale Certification 100-75
109.1.2 Requirements for Federal-Aid Projects 100-75

109.1.2.1 Verification of Manual Weighing Operations 100-75
109.1.2.2 Verification of Computerized Scales 100-77

109.2 SCOPE OF PAYMENT 100-78

Table of Contents

Section **Page**

109.2.1 General 100-78
109.2.2 Incidental Work 100-78

109.3 RESERVED
109.4 COMPENSATION FOR CHANGES AND FORCE ACCOUNT WORK 100-79

109.4.1 Compensation for Extra Work 100-79
109.4.2 Force Account 100-79
109.4.3 Specialty Work 100-80

109.4.3.1 Specialty Firms 100-80
109.4.3.2 Specialty Items 100-80
109.4.3.3 Contract Administration Considerations 100-80

109.5 ELIMINATED ITEMS 100-81
109.6 PARTIAL PAYMENTS 100-81

109.6.1 Preparation and Processing of Estimates 100-81
109.6.2 Reduction of Retainage 100-82
109.6.3 Subcontractor/Supplier Liens (Claims) 100-83

109.7 PAYMENT FOR MATERIAL ON HAND (STOCKPILED MATERIAL) 100-85
109.8 RESERVED
109.9 ACCEPTANCE AND FINAL PAYMENT 100-85

109.9.1 Processing Procedures 100-85
109.9.2 Requirements for Federal-Aid Projects 100-86

109.10 COMPENSATION FOR COMPENSABLE DELAYS 100-86

110 – 119 RESERVED
120 DOCUMENTATION REQUIREMENTS 100-87

120.1 INTRODUCTION 100-87

120.1.1 Definition 100-87
120.1.2 Purpose 100-87
120.1.3 Preparation and Processing Requirements 100-87

120.1.3.1 Document Preparation 100-87
120.1.3.2 Project Number and Project Code 100-88
120.1.3.3 Original Source Document 100-88
120.1.3.4 Hard-Copy Documentation 100-88
120.1.3.5 Electronic Documentation 100-88
120.1.3.6 Photographs and Video Recordings 100-89

120.1.4 Responsibilities 100-89

120.1.4.1 Resident Engineer 100-89
120.1.4.2 Project Engineer 100-90

Table of Contents

Section **Page**

120.1.4.3 Project Inspector 100-90

120.2 RESERVED
120.3 CORRESPONDENCE 100-90

120.3.1 Letters 100-90
120.3.2 Acceptance Letters 100-90
120.3.3 Memoranda 100-91

120.4 FORM 105 – SPEED MEMO 100-91
120.5 FORM 103 – PROJECT DIARY 100-92
120.6 REPORTS 100-94

120.6.1 Weekly Time Count Reports (Form 262 and Form 263) 100-94
120.6.2 Project Status Reports (Form 110 and Form 517) 100-95
120.6.3 Project Financial Status Reports 100-95

120.6.3.1 Use of ProBE 100-95
120.6.3.2 Requests for Additional Funds 100-96
120.6.3.3 Processing of Funding Letters 100-96

120.7 CHANGE ORDERS 100-97

120.7.1 General Requirements 100-97
120.7.2 Administrative Settlements 100-97
120.7.3 Preparation of Change Orders 100-99

120.7.3.1 Requirements and Responsibilities 100-99
120.7.3.2 Required Information 100-99

120.7.4 Statewide Uniformity 100-101
120.7.5 Pre-Approval Procedures for Change Orders 100-101
120.7.6 Letter of Explanation 100-102

120.7.6.1 Content Requirements 100-102
120.7.6.2 Price Justification 100-103

120.7.6.2.1 Contractor Cost Analysis 100-104
120.7.6.2.2 Independent Cost Analysis 100-104
120.7.6.2.3 *CDOT Cost Data Book* 100-105

120.7.6.3 Budget Actions 100-106

120.7.7 Types of Change Orders 100-107

120.7.7.1 Major Design Changes 100-107
120.7.7.2 Differing Site Conditions/Significant Changes to Work 100-108
120.7.7.3 Project Termini Extensions 100-109

Table of Contents

Section **Page**

120.7.7.3.1 Type I – Routine Project Termini Extensions 100-109
120.7.7.3.2 Type II – Critical Project Termini Extensions 100-110
120.7.7.3.3 Pre-Approval Requirements for Project Extensions 100-112

120.7.7.4 Extensions of Contract Time 100-113
120.7.7.5 Settlement of Contract Claim 100-114
120.7.7.6 CDOT Field Engineering Errors 100-114
120.7.7.7 Payment of Repairs 100-115
120.7.7.8 Initiation or Extension of Utility Work 100-116

120.7.7.8.1 Initiation of Utility Work 100-116
120.7.7.8.2 Extension of Utility Work 100-117

120.7.7.9 Major Change to Traffic Control Plan 100-117
120.7.7.10 Acceptance of Non-Specification Materials 100-117
120.7.7.11 Purchase of Materials 100-118

120.7.8 Situations Not Requiring a Change Order 100-119
120.7.9 Distribution of Change Orders 100-120

120.7.9.1 General Requirements 100-120
120.7.9.2 Projects with Federal Oversight 100-121

120.8 EMERGENCY CONSTRUCTION PROJECTS 100-121

120.8.1 Definition of Emergency Conditions 100-121
120.8.2 Scope of Emergency Procedures 100-122
120.8.3 Authority to Make Emergency Procurements 100-122
120.8.4 Contracting Procedures for Emergency Projects 100-123
120.8.5 Contractor Selection for Emergency Work 100-124

120.9 DISADVANTAGED BUSINESS ENTERPRISE FORMS 100-126

120.9.1 Form 713 100-126
120.9.2 Form 714 100-127
120.9.3 Form 715 100-127
120.9.4 Form 718 100-128
120.9.5 Form 719 100-128
120.9.6 Form 863 100-129

120.10 SUBLETTING OF CONTRACT WORK 100-129

120.10.1 FHWA Form 1273 100-129
120.10.2 Form 205 100-130
120.10.3 Use of Form 205 for Leased or Rented Equipment 100-132
120.10.4 Review, Approval, and Distribution of Form 205 100-133

120.10.4.1 Project Engineer Review 100-133
120.10.4.2 Project Engineer Approval 100-134
120.10.4.3 Region EEO/Civil Rights Specialist Review 100-134

Table of Contents

Section **Page**

120.10.5 Replacement of Subcontractor 100-135

120.11 PROGRESS SCHEDULE/METHODS STATEMENT 100-135

120.11.1 Progress Schedule 100-135
120.11.2 Methods Statement 100-136

120.12 MATERIALS 100-137

120.12.1 Nuclear Gauges 100-137
120.12.2 Field Laboratory Test Results 100-137
120.12.3 Calculation for Price Reduction 100-138
120.12.4 Concrete Batch Plants and Trucks Mixer Certification 100-138

120.12.4.1 Truck Mixer Certification 100-138
120.12.4.2 Batch Plant Certification 100-138

120.13 CONFERENCES 100-139

120.13.1 Preconstruction Conference 100-139

120.13.1.1 Purpose 100-139
120.13.1.2 Notification Letter 100-139
120.13.1.3 Preconstruction Conference Agenda 100-139
120.13.1.4 Distribution of Meeting Minutes 100-140

120.13.2 Hot Bituminous Pavement Pre-Paving Conference 100-140
120.13.3 Concrete Pavement Pre-Paving Conference 100-140
120.13.4 Structural Concrete Pre-Pour Conference 100-140
120.13.5 QC/QA Conferences for Asphalt and Concrete Pavements 100-141
120.13.6 Pre-Survey Conference 100-141

120.14 PIT PAYMENTS (Royalty Fees) 100-142

120.14.1 Pit Materials Report and Receipt 100-142
120.14.2 Physical Pit Condition Certification 100-142
120.14.3 Mining Permits 100-143

120.15 INTERIM CONTRACT PAYMENTS 100-143

120.15.1 Documentation for Contract Pay Items 100-143

120.15.1.1 General 100-143
120.15.1.2 Quantity and Payment Considerations 100-144

120.15.2 Methods of Measurement 100-144
120.15.3 Force Account 100-146

120.15.3.1 Definition 100-146
120.15.3.2 Force Account 100-146

Table of Contents

Section **Page**

120.15.3.3 Importance of Converting Force Accounts to Fixed Price 100-146
120.15.3.4 Initiating Force Account Work 100-147
120.15.3.5 Form 10 100-149
120.15.3.6 Form 580 100-150
120.15.3.7 Standby Equipment Rental Rates 100-150
120.15.3.8 Reimbursement for Leased or Rented Equipment 100-151
120.15.3.9 Payment Procedures for Force Account Work 100-152

120.15.4 Stockpiled Material 100-154
120.15.5 Partial Payments 100-156

121 FINAL PROJECT RECORDS 100-159

121.1 GENERAL REQUIREMENTS AND RESPONSIBILITIES 100-159

121.1.1 General Requirements 100-159
121.1.2 Responsibilities of the Project Engineer 100-160
121.1.3 Responsibilities of the Region Finals Engineer 100-160

121.2 PROJECT FINAL PROCEDURES 100-161

121.2.1 Basis of Payment Documentation 100-161
121.2.2 Documentation for Pay Items 100-163

121.2.2.1 Excavation and Embankment (Section 203) 100-163
121.2.2.2 Structural Excavation and Backfill (Section 206) 100-164
121.2.2.3 Bases and Pavements (Sections 300 and 400) 100-164
121.2.2.4 Piling (Section 502) 100-164
121.2.2.5 Concrete Slope and Ditch Paving (Section 507) 100-165
121.2.2.6 Structural Steel (Section 509) 100-165
121.2.2.7 Structural Concrete (Section 601) 100-165
121.2.2.8 Reinforcing Steel (Section 602) 100-165
121.2.2.9 Price Reductions (Section 105) 100-166

121.2.3 As-Constructed Plans 100-166

121.2.3.1 Availability 100-166
121.2.3.2 Incorporation of Changes 100-166

121.2.3.2.1 Manual and Electronic Procedures 100-167
121.2.3.2.2 Manual Procedures 100-169
121.2.3.2.3 Electronic Procedures 100-170

121.2.4 Final Estimates 100-171
121.2.5 Rounding of Final Estimate Quantities 100-171
121.2.6 Pit Payments 100-172
121.2.7 Final Project Records 100-172
121.2.8 Contractor Reports 100-174

Table of Contents

Section **Page**

121.3 ADVERTISEMENT FOR FINAL SETTLEMENT 100-175

121.3.1 Region Records 100-175
121.3.2 Region Review Procedures 100-177
121.3.3 Distribution by Region Finals Engineer 100-179
121.3.4 Construction Phase Closure 100-181
121.3.5 Escrow of Project Funds 100-183

122 LOCAL AGENCY PROJECT ADMINISTRATION 100-187

122.1 ADMINISTRATION OF FEDERAL-AID LOCAL AGENCY PROJECTS 100-187
122.2 QUALITY ASSURANCE – CDOT FEDERAL-OVERSIGHT PROGRAM 100-187
122.3 CONTRACT ADMINISTRATION 100-187

122.3.1 Administration by the Department 100-187
122.3.2 Administration by the Local Agency 100-188

122.4 REGION RESPONSIBILITIES FOR OVERSIGHT 100-189
122.5 QUALITY CONTROL – CDOT FEDERAL-OVERSIGHT PROGRAM 100-190
122.6 PROJECT REVIEWS 100-190
122.7 FINAL PROJECT INSPECTION 100-191

200 EARTHWORK 200-1

200.1 GENERAL 200-1
200.2 PRECONSTRUCTION CONSIDERATIONS 200-1

200.2.1 Limits of Construction 200-1
200.2.2 Access to Private Property 200-2
200.2.3 Utilities and Existing Highway Facilities 200-2
200.2.4 Historical Sites and Markers 200-2
200.2.5 Wetland Areas and Animal Habitats 200-2
200.2.6 Trees and Shrubs 200-3
200.2.7 Highly Erodible Soils 200-3
200.2.8 Archaeological and Paleontological Sites 200-3
200.2.9 Hazardous Operations 200-3
200.2.10 Hazardous Material/Hazardous Waste 200-4
200.2.11 Salvable Materials 200-4
200.2.12 Stakes and Survey Monuments 200-4
200.2.13 State Noxious Weeds 200-5
200.2.14 Visual Documentation 200-5

201 CLEARING AND GRUBBING 200-7

201.1 GENERAL REQUIREMENTS 200-7

201.1.1 Excavation Areas and Borrow Pits 200-7
201.1.2 Embankment Areas 200-7

Table of Contents

Section **Page**

201.1.2.1 Fills Greater Than Four Feet 200-8
201.1.2.2 Four-Foot Fills or Less 200-8

201.2 INSPECTION GUIDELINES 200-8

201.2.1 Before Construction 200-8
201.2.2 During Construction 200-9
201.2.3 After Construction 200-9

202 REMOVAL OF STRUCTURES AND OBSTRUCTIONS 200-11

202.1 GENERAL REQUIREMENTS 200-11
202.2 INSPECTION GUIDELINES 200-11

202.2.1 Before Construction 200-11
202.2.2 During Construction 200-12
202.2.3 After Construction 200-12

203 EXCAVATION AND EMBANKMENT 200-13

203.1 GENERAL REQUIREMENTS 200-13

203.1.1 Excavation 200-13

203.1.1.1 Types of Excavation 200-13
203.1.1.2 Excavation Near Wetlands 200-14

203.1.2 Embankment Construction 200-14

203.1.2.1 Embankment Materials 200-14
203.1.2.2 Foundation Inspection 200-14
203.1.2.3 Embankment Uniformity 200-15

203.1.3 Steep Slopes and Transitions 200-15

203.2 INSPECTION GUIDELINES 200-16

203.2.1 Before Construction 200-16
203.2.2 During Construction 200-17
203.2.3 After Construction 200-19

204 – 205 RESERVED
206 EXCAVATION AND BACKFILL FOR STRUCTURES 200-21

206.1 GENERAL 200-21

206.1.1 Contractor Responsibility 200-21
206.1.2 Damage and Failure Considerations 200-21

206.2 INSPECTION GUIDELINES 200-22

Table of Contents

Section **Page**

206.2.1 Before Construction 200-22
206.2.2 During Construction 200-23

207 TOPSOIL 200-25

207.1 GENERAL 200-25
207.2 INSPECTION GUIDELINES 200-25

207.2.1 Before Construction 200-25
207.2.2 During Construction 200-25
207.2.3 After Construction 200-26

208 EROSION CONTROL 200-27

208.1 GENERAL 200-27

208.1.1 Erosion and Sedimentation Process 200-27
208.1.2 Water Quality Management Requirements 200-27

208.1.2.1 Stormwater Management Plan 200-27
208.1.2.2 Best Management Practices 200-28
208.1.2.3 Erosion Control Supervisor 200-28

208.2 INSPECTION GUIDELINES 200-29

208.2.1 Before Construction 200-29
208.2.2 During Construction 200-30
208.2.3 After Construction 200-30

209 WATERING AND DUST PALLIATIVES 200-33

209.1 GENERAL 200-33
209.2 INSPECTION GUIDELINES 200-33

209.2.1 Before Construction 200-33
209.2.2 During Construction 200-34
209.2.3 After Construction 200-54

210 RESET STRUCTURES 200-35

210.1 GENERAL 200-35
210.2 INSPECTION GUIDELINES 200-35

210.2.1 Before Construction 200-35
210.2.2 During Construction 200-36

211 RESERVED
212 SEEDING, FERTILIZER, AND SODDING 200-39

Table of Contents

Section **Page**

212.1 GENERAL....200-39

212.1.1 Landscape Applications....200-39

212.2 INSPECTION GUIDELINES....200-39

212.2.1 Before Construction....200-39
212.2.2 During Construction....200-40
212.2.3 After Construction....200-41

213 MULCHING....200-43

213.1 GENERAL....200-43

213.1.1 Material Certification....200-43

213.2 INSPECTION GUIDELINES....200-44

213.2.1 Before Construction....200-44
213.2.2 During Construction....200-44
213.2.3 After Construction....200-46

214 PLANTING....200-47

214.1 GENERAL....200-47
214.2 INSPECTION GUIDELINES....200-47

214.2.1 Before Construction....200-47
214.2.2 During Construction....200-48
214.2.3 After Construction....200-49

215 TRANSPLANTING....200-51

215.1 GENERAL....200-51
215.2 INSPECTION GUIDELINES....200-51

215.2.1 Before Construction....200-51
215.2.2 During Construction....200-52
215.2.3 After Construction....200-53

216 SOIL RETENTION COVERING....200-55

216.1 GENERAL....200-55
216.2 INSPECTION GUIDELINES....200-55

216.2.1 Before Construction....200-55
216.2.2 During Construction....200-55

217 HERBICIDE TREATMENT....200-57

Table of Contents

Section **Page**

217.1 GENERAL....200-57
217.2 INSPECTION GUIDELINES....200-57

217.2.1 Before Construction....200-57
217.2.2 During Construction....200-58

218 – 249 RESERVED

250 ENVIRONMENTAL, HEALTH, AND SAFETY MANAGEMENT....200-59

250.1 GENERAL....200-59
250.2 HAZARDOUS MATERIAL/HAZARDOUS WASTE....200-59

250.2.1 Governing Specifications and Procedural Directives....200-59
250.2.2 Site Investigation....200-59
250.2.3 Importance of Records and Documentation....200-60
250.2.4 Create Notification Form for Emergency Response....200-60
250.2.5 Discovery During Construction....200-60

250.2.5.1 Potential Discovery Situations....200-60
250.2.5.2 Stopping Work....200-63
250.2.5.3 Securing the Area....200-63
250.2.5.4 Emergency Contact Notification....200-64
250.2.5.5 Hazardous Material/Hazardous Waste Consultants....200-66
250.2.5.6 Assessment of Avoidance Alternatives....200-66
250.2.5.7 Health and Safety Plan Implementation....200-67

250.2.6 Signature Authority for Manifests....200-68

300 BASES....300-1

300.1 SUBGRADE PREPARATION....300-1
300.2 BASE COURSE CONSTRUCTION....300-2

301 PLANT-MIX BITUMINOUS BASE COURSE....300-5

301.1 GENERAL....300-5
301.2 INSPECTION GUIDELINES....300-5

301.2.1 Before Construction....300-5
301.2.2 During Construction....300-6
301.2.3 After Construction....300-7

302 – 303 RESERVED
304 AGGREGATE BASE COURSE....300-9

304.1 GENERAL....300-9
304.2 INSPECTION GUIDELINES....300-9

304.2.1 Before Construction....300-9

Table of Contents

Section **Page**

304.2.2 During Construction 300-10
304.2.3 After Construction 300-11

305 RESERVED
306 RECONDITIONING 300-13

306.1 GENERAL 300-13
306.2 INSPECTION GUIDELINES 300-13

306.2.1 Before Construction 300-13
306.2.2 During Construction 300-13
306.2.3 After Construction 300-14

307 LIME TREATED SUBGRADE 300-15

307.1 GENERAL 300-15
307.2 INSPECTION GUIDELINES 300-15

307.2.1 Before Construction 300-15
307.2.2 During Construction 300-16
307.2.3 After Construction 300-17

400 PAVEMENTS 400-1

400.1 GENERAL 400-1

400.1.1 Quality Control/Quality Assurance Provisions 400-1
400.1.2 Vertical Clearance Under Structures 400-1

401 PLANT-MIX PAVEMENTS – GENERAL 400-3

401.1 PRELIMINARY CONSIDERATIONS 400-3

401.1.1 Contract Plans and Specifications 400-3
401.1.2 Asphalt Paving Publications 400-3
401.1.3 Job-Mix Formula 400-4
401.1.4 Longitudinal Joint and Pavement Marking Plan 400-5
401.1.5 Pre-Paving Conference/Communications/Quality Control Plan 400-5
401.1.6 Weather Conditions 400-5
401.1.7 Foundation Preparation and Conditioning 400-5

401.1.7.1 Subgrade/Base 400-6
401.1.7.2 Existing Pavement 400-6

401.1.8 Application of Prime and Tack Coats 400-6
401.1.9 Project Stationing 400-6
401.1.10 Compaction Test Section 400-7
401.1.11 Mix Segregation 400-7

401.2 PRODUCTION 400-7

Table of Contents

Section **Page**

401.2.1 Plant Facilities 400-7

401.2.1.1 Laboratory Facilities 400-8
401.2.1.2 Air Quality Considerations 400-8
401.2.1.3 Plant Scales 400-8
401.2.1.4 Job-Mix Formula 400-8

401.2.2 Material Considerations 400-8

401.2.2.1 Component Materials 400-9
401.2.2.2 Aggregate Stockpiles 400-9
401.2.2.3 Aggregate Handling 400-9

401.2.3 Mix Production and Storage 400-9

401.2.3.1 Bituminous Materials 400-9
401.2.3.2 Addition of Lime 400-10
401.2.3.3 Mixing Efficiency 400-10
401.2.3.4 Mix Proportions 400-10
401.2.3.5 Mix Discharge Temperature 400-11
401.2.3.6 Surge Silo Storage 400-11

401.3 LOADING/HAULING OPERATION 400-11

401.3.1 Haul Trucks 400-11
401.3.2 Truck Loading Considerations 400-11

401.4 LAYDOWN OPERATION 400-12

401.4.1 Paving Equipment 400-12
401.4.2 Mix Delivery 400-12
401.4.3 Charging the Paver Hopper 400-12
401.4.4 Paver Operation and Adjustment 400-13

401.4.4.1 Paver Control 400-13
401.4.4.2 Paver Speed 400-13
401.4.4.3 Material Feed 400-14
401.4.4.4 Paver Hopper Wings 400-14
401.4.4.5 Augers 400-14
401.4.4.6 Screed 400-14

401.4.5 Quality Considerations 400-14

401.5 COMPACTION OPERATION 400-15

401.5.1 Rolling Procedures 400-15

401.5.1.1 Rolling Sequence 400-15
401.5.1.2 Roller Speed 400-16
401.5.1.3 Pneumatic-Tire Rollers 400-16

Table of Contents

Section **Page**

401.5.1.4 Vibratory Rollers 400-16
401.5.1.5 Manual Compaction Methods 400-17

401.5.2 Temperature Considerations 400-17
401.5.3 Joint Construction 400-17

401.5.3.1 Transverse Joints 400-17
401.5.3.2 Longitudinal Joints 400-18

402 RESERVED
403 HOT BITUMINOUS PAVEMENT 400-19

403.1 GENERAL 400-19

404 RESERVED
405 HEATING AND SCARIFYING TREATMENT 400-21

405.1 GENERAL 400-21
405.2 INSPECTION GUIDELINES 400-21

405.2.1 Before Construction 400-21
405.2.2 During Construction 400-22
405.2.3 After Construction 400-23

406 COLD BITUMINOUS PAVEMENT (RECYCLE) 400-25

406.1 GENERAL 400-25
406.2 INSPECTION GUIDELINES 400-25

406.2.1 Before Construction 400-25
406.2.2 During Construction 400-26
406.2.3 After Construction 400-27

407 PRIME COAT, TACK COAT, AND REJUVENATING AGENT 400-29

407.1 GENERAL 400-29
407.2 INSPECTION GUIDELINES 400-29

407.2.1 Before Construction 400-29
407.2.2 During Construction 400-30

408 JOINT AND CRACK SEALANT 400-31

408.1 GENERAL 400-31
408.2 INSPECTION GUIDELINES 400-31

408.2.1 Before Construction 400-31
408.2.2 During Construction 400-32
408.2.3 After Construction 400-32

Table of Contents

Section **Page**

409 SEAL COAT 400-33

409.1 GENERAL 400-33
409.2 INSPECTION GUIDELINES 400-33

409.2.1 Before Construction 400-33
409.2.2 During Construction 400-34

409.2.2.1 Application of Bituminous Material 400-34
409.2.2.2 Application of Aggregate Cover 400-36
409.2.2.3 Rolling Operation 400-37
409.2.2.4 Brooming Operation 400-38

409.2.3 After Construction 400-38

410 RESERVED

411 BITUMINOUS MATERIALS 400-39

411.1 GENERAL 400-39
411.2 INSPECTION GUIDELINES 400-39

411.2.1 Before Construction 400-39
411.2.2 During Construction 400-39
411.2.3 After Construction 400-40

412 PORTLAND CEMENT CONCRETE PAVEMENT 400-41

412.1 PRELIMINARY CONSIDERATIONS 400-41

412.1.1 Contract Plans and Specifications 400-41
412.1.2 Portland Cement Concrete Mix Design 400-41
412.1.3 Tining Plan 400-42
412.1.4 Process Control Plan 400-42
412.1.5 Pre-Paving Conference/Communications 400-42
412.1.6 Equipment Considerations 400-42
412.1.7 Utilities 400-43
412.1.8 Subgrade/Base Preparation 400-43

412.1.8.1 Fixed-Form Considerations 400-44
412.1.8.2 Slip-Form Considerations 400-44

412.2 REINFORCEMENT AND JOINT CONSIDERATIONS 400-45

412.2.1 Reinforcing Steel 400-45
412.2.2 Construction Joints 400-45
412.2.3 Weakened Plane Joints 400-46
412.2.4 Expansion Joints 400-47

Table of Contents

Section **Page**

412.3 PLACEMENT AND CONSOLIDATION OPERATION 400-47

412.3.1 Moistening of Grade 400-47
412.3.2 Hauling and Delivery Considerations 400-48
412.3.3 Spreading and Strike-Off Considerations 400-48
412.3.4 Vibration Considerations 400-48

412.4 SURFACE FINISHING OPERATION 400-49

412.4.1 Floating Considerations 400-49
412.4.2 Adding Water to Surface 400-49
412.4.3 Surface Texturing 400-50
412.4.4 Stationing 400-50
412.4.5 Rumble Strips 400-50

412.5 CONCRETE CURING OPERATION 400-51
412.6 SLAB REPAIR WORK 400-51
412.7 SURFACE SMOOTHNESS TESTING 400-51
412.8 JOINT SAWING AND SEALING 400-52

412.8.1 Sawing Operation 400-52
412.8.2 Sealing Operation 400-53

412.9 PAVEMENT THICKNESS DETERMINATION 400-53
412.10 TRAFFIC CONSIDERATIONS 400-53

413 – 419 RESERVED
420 GEOSYNTHETICS 400-55

420.1 PRELIMINARY CONSIDERATIONS 400-55
420.2 INSPECTION GUIDELINES 400-55

420.2.1 Paving Applications 400-55
420.2.2 Impervious Lining Applications 400-56
420.2.3 Erosion Control and Drainage Applications 400-56
420.2.4 Subgrade Applications 400-57
420.2.5 Landscape Applications 400-57

500 STRUCTURES 500-1
501 STEEL SHEET PILING 500-1

501.1 GENERAL 500-1
501.2 INSPECTION GUIDELINES 500-1

501.2.1 Before Construction 500-1
501.2.2 During Construction 500-2

502 PILING 500-3

502.1 GENERAL 500-3

Table of Contents

Section **Page**

502.2 INSPECTION GUIDELINES 500-4

502.2.1 Before Construction 500-4

502.2.1.1 Contract Plans and Specifications 500-4
502.2.1.2 Pile Location and Utility Considerations 500-4
502.2.1.3 Excavation 500-4
502.2.1.4 Equipment Considerations 500-4
502.2.1.5 Material Considerations 500-5
502.2.1.6 Test Piles and Pre-Drilling 500-6
502.2.1.7 Welder Certification 500-6

502.2.2 During Construction 500-6

502.2.2.1 Pile Location and Direction 500-7
502.2.2.2 Hammer Cushion/Striker Plate 500-7
502.2.2.3 Water Jetting 500-7
502.2.2.4 Pile Penetration and Bearing Elevation 500-7
502.2.2.5 Cutting of Piles 500-8
502.2.2.6 Pile Splicing 500-9
502.2.2.7 Filling and Capping of Hollow Piles 500-9
502.2.2.8 Pile Damage and Defects 500-9

502.2.3 After Construction 500-10

503 DRILLED CAISSONS 500-11

503.1 GENERAL 500-11
503.2 INSPECTION GUIDELINES 500-11

503.2.1 Before Construction 500-11
503.2.2 During Construction 500-12

503.2.2.1 Drilling Operation 500-12
503.2.2.2 Caisson Reinforcement/Steel Casing 500-13
503.2.2.3 Concrete Placement 500-13

503.2.3 After Construction 500-14

504 – 505 RESERVED

506 RIPRAP, GABIONS, AND SLOPE MATTRESS 500-15

506.1 GENERAL 500-15
506.2 INSPECTION GUIDELINES 500-15

506.2.1 Before Construction 500-15
506.2.2 During Construction 500-16

Table of Contents

Section **Page**

506.2.2.1 Riprap Treatment....500-16
506.2.2.2 Gabion Treatment....500-16
506.2.2.3 Slope Mattress Treatment....500-16

506.2.3 After Construction....500-17

507 SLOPE AND DITCH PAVING....500-19

507.1 GENERAL....500-19
507.2 INSPECTION GUIDELINES....500-19

507.2.1 Before Construction....500-19
507.2.2 During Construction....500-20

507.2.2.1 Concrete Paving....500-20
507.2.2.2 Dry-Rubble Paving....500-20
507.2.2.3 Grouted-Rubble Paving....500-21
507.2.2.4 Grouted-Riprap Paving....500-21
507.2.2.5 Bituminous Paving....500-21

507.2.3 After Construction....500-21

508 TIMBER STRUCTURES....500-23

508.1 GENERAL....500-23
508.2 INSPECTION GUIDELINES....500-23

508.2.1 Before Construction....500-23
508.2.2 During Construction....500-24
508.2.3 After Construction....500-25

509 STEEL STRUCTURES....500-27

509.1 GENERAL....500-27
509.2 INSPECTION GUIDELINES....500-27

509.2.1 Before Construction....500-27
509.2.2 During Construction....500-28
509.2.3 After Construction....500-29

510 STRUCTURAL PLATE STRUCTURES....500-31

510.1 GENERAL....500-31
510.2 INSPECTION GUIDELINES....500-31

510.2.1 Before Construction....500-31
510.2.2 During Construction....500-32
510.2.3 After Construction....500-33

511 RESERVED

Table of Contents

Section **Page**

512 BEARING DEVICES 500-35

512.1 GENERAL 500-35
512.2 INSPECTION GUIDELINES 500-35

512.2.1 Before Construction 500-35
512.2.2 During Construction 500-35
512.2.3 After Construction 500-36

513 RESERVED
514 PEDESTRIAN AND BIKEWAY RAILING 500-37

514.1 GENERAL 500-37
514.2 INSPECTION GUIDELINES 500-37

514.2.1 Before Construction 500-37
514.2.2 During Construction 500-38
514.2.3 After Construction 500-38

515 WATERPROOF MEMBRANE 500-39

515.1 GENERAL 500-39
515.2 INSPECTION GUIDELINES 500-39

515.2.1 Before Construction 500-39
515.2.2 During Construction 500-40
515.2.3 After Construction 500-41

516 DAMPPROOFING 500-43

516.1 GENERAL 500-43
516.2 INSPECTION GUIDELINES 500-43

516.2.1 Before Construction 500-43
516.2.2 During Construction 500-44
516.2.3 After Construction 500-44

517 WATERPROOFING 500-45

517.1 GENERAL 500-45
517.2 INSPECTION GUIDELINES 500-45

517.2.1 Before Construction 500-45
517.2.2 During Construction 500-46
517.2.3 After Construction 500-46

Table of Contents

Section **Page**

518 WATERSTOPS AND EXPANSIONS JOINTS 500-47

518.1 GENERAL 500-47
518.2 INSPECTION GUIDELINES 500-47

518.2.1 Before Construction 500-47
518.2.2 During Construction 500-48

518.2.2.1 Waterstops 500-48
518.2.2.2 Asphaltic Expansion Devices 500-48
518.2.2.3 Elastomeric Expansion Devices 500-49
518.2.2.4 Modular Expansion Devices 500-49
518.2.2.5 Elastomeric Concrete End Dams 500-50

518.2.3 After Construction 500-50

600 MISCELLANEOUS CONSTRUCTION 600-1
601 STRUCTURAL CONCRETE 600-1

601.1 GENERAL REQUIREMENTS 600-1

601.1.1 Completed Bridge Inspection 600-1
601.1.2 Vertical Clearances 600-1

601.2 FORMWORK AND FALSEWORK 600-2

601.2.1 Form Lumber 600-2
601.2.2 Bracing Considerations 600-2
601.2.3 Foundation Systems 600-2
601.2.4 Falsework Drawing Certification 600-3
601.2.5 Inspection Considerations 600-4

601.3 CONCRETE PRODUCTION 600-5

601.3.1 Load Tickets 600-5
601.3.2 Deviation From Specifications 600-6

601.4 CONCRETE PLACEMENT 600-6

601.4.1 Before Placement 600-6
601.4.2 During Placement 600-7

601.5 CONCRETE FINISHING 600-9
601.6 CONCRETE CURING 600-10
601.7 CONCRETE BRIDGE DECKS 600-10

601.7.1 Pre-Pour Conference 600-11
601.7.2 Stay-in-Place Forms 600-11
601.7.3 Finish and Placement Considerations 600-11
601.7.4 Concrete Placement Considerations 600-12

Table of Contents

Section **Page**

601.7.4.1 Before Placement 600-12
601.7.4.2 During Placement 600-12

601.7.5 Concrete Finishing Considerations 600-14

601.7.5.1 Before Finishing 600-14
601.7.5.2 During Finishing 600-14
601.7.5.3 After Finishing 600-15

601.7.6 Concrete Curing Considerations 600-15
601.7.7 Approach Slabs 600-16

602 REINFORCING STEEL 600-17

602.1 GENERAL 600-17
602.2 INSPECTION GUIDELINES 600-17

602.2.1 Before Construction 600-17
602.2.2 During Construction 600-18

603 CULVERTS AND SEWERS 600-21

603.1 GENERAL 600-21
603.2 INSPECTION GUIDELINES 600-21

603.2.1 Before Construction 600-21
603.2.2 During Construction 600-22
603.2.3 After Construction 600-23

604 MANHOLES, INLETS, AND METER VAULTS 600-25

604.1 GENERAL 600-25
604.2 INSPECTION GUIDELINES 600-25

604.2.1 Before Construction 600-25
604.2.2 During Construction 600-26
604.2.3 After Construction 600-26

605 SUBSURFACE DRAINS 600-27

605.1 GENERAL 600-27
605.2 INSPECTION GUIDELINES 600-27

605.2.1 Before Construction 600-27
605.2.2 During Construction 600-28

606 GUARDRAIL 600-29

606.1 GENERAL 600-29
606.2 INSPECTION GUIDELINES 600-29

Table of Contents

Section **Page**

606.2.1 Before Construction 600-29
606.2.2 During Construction 600-29

607 FENCES 600-33

607.1 GENERAL 600-33
607.2 INSPECTION GUIDELINES 600-33

607.2.1 Before Construction 600-33
607.2.2 During Construction 600-34
607.2.3 After Construction 600-34

608 SIDEWALKS AND BIKEWAYS 600-35

608.1 GENERAL 600-35
608.2 INSPECTION GUIDELINES 600-35

608.2.1 Before Construction 600-35

608.2.1.1 Subgrade 600-35
608.2.1.2 Curb Ramps 600-35
608.2.1.3 Concrete Materials and Equipment 600-36
608.2.1.4 Bituminous Materials and Equipment 600-36

608.2.2 During Construction 600-36

608.2.2.1 Concrete Sidewalks and Bikeways 600-36
608.2.2.2 Bituminous Sidewalks and Bikeways 600-38

609 CURB AND GUTTER 600-39

609.1 GENERAL 600-39
609.2 INSPECTION GUIDELINES 600-39

609.2.1 Before Construction 600-39
609.2.2 During Construction 600-39

609.2.2.1 Concrete Curb and Gutter 600-39
609.2.2.2 Bituminous Curb 600-40

609.2.3 After Construction 600-40

610 MEDIAN COVER MATERIAL 600-41

610.1 GENERAL 600-41
610.2 INSPECTION GUIDELINES 600-41

611 CATTLE GUARDS 600-43

611.1 GENERAL 600-43

Table of Contents

Section **Page**

611.2 INSPECTION GUIDELINES 600-43

612 DELINEATORS AND REFLECTORS 600-45

612.1 GENERAL 600-45
612.2 INSPECTION GUIDELINES 600-45

612.2.1 Before Construction 600-45
612.2.2 During Construction 600-45

613 LIGHTING 600-47

613.1 GENERAL 600-47
613.2 INSPECTION GUIDELINES 600-47

613.2.1 Before Construction 600-47
613.2.2 During Construction 600-48
613.2.3 After Construction 600-49

614 TRAFFIC CONTROL DEVICES 600-51

614.1 GENERAL 600-51
614.2 HIGHWAY SIGNS 600-51

614.2.1 Before Construction 600-51
614.2.2 During Construction 600-52

614.2.2.1 Post Installation 600-52
614.2.2.2 Sign Panels 600-53

614.3 OVERHEAD SIGN STRUCTURES 600-53

614.3.1 General Considerations 600-53
614.3.2 Shop Drawings/Fabrication Inspection 600-53
614.3.3 Substructure Considerations 600-54
614.3.4 Superstructure Considerations 600-55

614.4 TRAFFIC SIGNAL SYSTEMS 600-55

614.4.1 General Considerations 600-55
614.4.2 Shop/Working Drawings 600-56
614.4.3 Substructure Considerations 600-56

614.4.3.1 Before Construction 600-56
614.4.3.2 During Construction 600-57

614.4.4 Superstructure Considerations 600-58

614.4.4.1 Span-Wire Installations 600-58
614.4.4.2 Mast-Arm Installations 600-58

Table of Contents

Section **Page**

614.4.5 Electrical Considerations 600-59

614.4.5.1 Before Construction 600-59
614.4.5.2 During Construction 600-59
614.4.5.3 After Construction 600-60

615 WATER CONTROL DEVICES 600-63

615.1 GENERAL 600-63
615.2 INSPECTION GUIDELINES 600-63

616 SIPHONS 600-65

616.1 GENERAL 600-65
616.2 INSPECTION GUIDELINES 600-65

616.2.1 Before Construction 600-65
616.2.2 During Construction 600-65
616.2.3 After Construction 600-66

617 CULVERT PIPE 600-67

617.1 GENERAL 600-67
617.2 INSPECTION GUIDELINES 600-67

618 PRESTRESSED CONCRETE 600-69

618.1 GENERAL 600-69

618.1.1 Pre-Tensioning/Post-Tensioning 600-69
618.1.2 Creep and Camber 600-69
618.1.3 Precast Girders 600-70
618.1.4 Cast-In-Place Girders 600-70
618.1.5 Segmental Construction 600-70

618.2 INSPECTION GUIDELINES 600-71

618.2.1 Precast Girders 600-71

618.2.1.1 Before Construction 600-71
618.2.1.2 During Construction 600-71
618.2.1.3 After Construction 600-72

618.2.2 Cast-In-Place Girders 600-72

618.2.2.1 Before Construction 600-72
618.2.2.2 During Construction 600-73
618.2.2.3 During Prestressing 600-74
618.2.2.4 After Prestressing 600-76

Table of Contents

Section **Page**

618.2.3 Segmental Construction....600-76
618.2.3.1 Before Construction....600-77

618.2.3.2 During Construction....600-77
618.2.3.3 After Construction....600-78

619 WATER LINES....600-79

619.1 GENERAL....600-79
619.2 INSPECTION GUIDELINES....600-79

619.2.1 Before Construction....600-79
619.2.2 During Construction....600-79
619.2.3 After Construction....600-80

620 FIELD FACILITIES....600-81

620.1 GENERAL....600-81

620.1.1 Trailer Shortages....600-81

620.2 INSPECTION GUIDELINES....600-81

621 RESERVED
622 REST AREAS AND BUILDINGS....600-83

622.1 GENERAL....600-83
622.2 INSPECTION GUIDELINES....600-83

622.2.1 Underground Pipe....600-83

622.2.1.1 General Considerations....600-83
622.2.1.2 Water Lines....600-84
622.2.1.3 Sanitary Sewer Lines....600-85
622.2.1.4 Pipe Joints....600-85
622.2.1.5 Copper Pipe....600-85

622.2.2 Masonry and Tile....600-86

622.2.2.1 General Considerations....600-86
622.2.2.2 Mortar Considerations....600-87
622.2.2.3 Bricks and Concrete Block....600-87
622.2.2.4 Structural Glazed Tile....600-88

622.2.3 Building Infrastructure....600-89

622.2.3.1 Carpentry....600-89
622.2.3.2 Roofing....600-89
622.2.3.3 Doors and Windows....600-90
622.2.3.4 Caulking, Glass, and Glazing....600-90

Table of Contents

Section **Page**

622.2.3.5 Ceramic Tile 600-90
622.2.3.6 Toilet Partitions 600-91
622.2.3.7 Plumbing and Sprinkling Systems 600-91
622.2.3.8 Soil, Waste, Drain, and Vent Piping 600-92
622.2.3.9 Water Piping 600-93

622.2.4 Electrical System 600-94

622.2.4.1 General Considerations 600-94
622.2.4.2 Lamps and Lighting Fixtures 600-96

623 IRRIGATION SYSTEM 600-97

623.1 GENERAL 600-97
623.2 INSPECTION GUIDELINES 600-97

623.2.1 Before Construction 600-97
623.2.2 During Construction 600-97
623.2.3 After Construction 600-98

624 CORROSION RESISTANT CULVERTS 600-101

624.1 GENERAL 600-101

625 CONSTRUCTION SURVEYING 600-103

625.1 GENERAL 600-103

626 MOBILIZATION 600-105

626.1 GENERAL 600-105

627 PAVEMENT MARKING 600-107

627.1 GENERAL 600-107

627.1.1 Surface Preparation and Payment Considerations 600-107

627.2 INSPECTION GUIDELINES 600-107

627.2.1 Before Construction 600-107
627.2.2 During Construction 600-108

628 RESERVED
629 SURVEY MONUMENTATION 600-111

629.1 GENERAL 600-111

630 CONSTRUCTION ZONE TRAFFIC CONTROL 600-113

Table of Contents

Section **Page**

630.1 GENERAL....600-113
630.2 TRAFFIC CONTROL REVIEW PROGRAM....600-113

630.2.1 Overview....600-113
630.2.2 Implementation Procedures....600-114
630.2.3 Inspections During Non-Working Hours....600-114
630.2.4 Review of Method of Handling Traffic....600-115
630.2.5 Responsibilities of the Traffic Control Supervisor....600-117
630.2.6 Flagger Certification....600-119

630.3 INSPECTION GUIDELINES....600-120

630.3.1 Traffic Operations and Project Documents....600-120
630.3.2 Traffic Control Supervisor....600-122
630.3.3 Flaggers....600-122
630.3.4 Construction Signing....600-123
630.3.5 Traffic Control Devices....600-124
630.3.6 Temporary Pavement Markings....600-126
630.3.7 Pilot Car Operations....600-126

APPENDIX A – CONFERENCE AGENDAS....A-1

Preconstruction Conference Notification and Agenda....A-3

Preconstruction Conference Notification Letter – Example....A-5
Preconstruction Conference Notification FAX – Example....A-7
Preconstruction Conference Agenda....A-9

Hot Bituminous Pavement Pre-Paving Conference Agenda....A-25
Hot-Mix Asphalt QC/QA Conference Agenda....A-41
Concrete Pavement Pre-Paving Conference Agenda....A-49
Concrete Pavement QC/QA Conference Agenda....A-63
Structural Concrete Pre-Pour Conference Agenda....A-71
Pre-Survey Conference Agenda....See the *CDOT Survey Manual.*

APPENDIX B – EXAMPLE LETTERS, NOTICES, AND FORMS....B-1

Acceptance Letter....B-2
Buy America Certification Letter....B-3
Contractor's Claim Certification....B-4
Stockpile Material Letter of Vested Interest....B-5
Prompt Payment Notice....B-6
Prompt Payment Law....B-7

Claims Status Report
Completion Instructions....B-8
Example Form....B-9
Form 7 – Weekly Report On Miscellaneous Pay Items
Completion Instructions....B-10
Example Form....B-12

Table of Contents

Section **Page**

Form 10 – Inspector's Report for Force Account Work
Completion Instructions B-14
Example Form B-16
Form 17 – Contractor DBE Payment Certification
Completion Instructions B-19
Example Form B-20
Form 20 – Daily Water Report
Completion Instructions B-21
Example Form B-23
Form 46 – Concrete Truck Mixer Inspection Certification
Completion Instructions B-24
Example Form B-25
FHWA Form 47 – Statement of Materials and Labor Used By Contractors on Highway Construction Involving Federal Funds
Completion Instructions B-26
Example Form B-27
FHWA Instructions for Preparing and Transmitting FORM FHWA-47 ..... B-28
Form 90 – Contract Modification Order ..... See Appendix C
Form 94 – Minor Contract Revision Order ..... See Appendix C
Form 103 – Project Diary
Completion Instructions B-29
Example Form B-30
Form 105 – Speed Memo
Completion Instructions B-32
Example Form B-34
Form 200 – OJT Training Questionnaire
Completion Instructions B-35
Example Form B-36
Form 205 – Sublet Permit Application
Completion Instructions B-37
Example Form B-40
Form 262 – Weekly Time Count Report – Work Days
Completion Instructions B-42
Example Form B-45
Form 263 – Weekly Time Count Report – Calendar Days
Completion Instructions B-46
Example Form B-49
Form 266 – Inspector's Progress Report
Completion Instructions B-50
Example Form B-52
Form 279 – Inspector's Report of Reinforcing Steel Placed
Completion Instructions B-54
Example Form B-56
Form 280 – EEO and Labor Compliance Verification
Completion Instructions B-57
Example Form B-59
Form 282 – Asphalt Paving Inspector's Daily Report
Completion Instructions B-60
Example Form B-63

Table of Contents

Section **Page**

Form 568 – Authorization and Declaration of Temporary Speed Limits
Completion Instructions B-64
Example Form B-65
Form 580 – Equipment Rental Rate Determination Request
Completion Instructions B-66
Example Form B-69
Form 713 – Contractor DBE Subcontractor, Supply and Service Contract Statement
Completion Instructions B-70
Example Form B-71
Form 832 – Trainee Status and Evaluation
Completion Instructions B-72
Example Form B-74
Form 838 – OJT Trainee/Apprentice Record
Completion Instructions B-75
Example Form B-77
Form 859 – Project Control Data
Completion Instructions B-78
Example Form B-86
Form 1186 – Contract Funding Increase/Decrease and Approval Letter
Completion Instructions B-88
Example Form B-90
Form 1212 – Final Acceptance Report
Completion Instructions B-91
Example Form B-93
FHWA Form 1391 – Federal-Aid Highway Construction Contractors Annual EEO Report
Completion Instructions B-94
Example Form B-95
Piling Form
Completion Instructions B-96
Example Form B-98
Traffic Control Review Form
Completion Instructions B-99
Example Form B-100

APPENDIX C – CHANGE ORDER EXAMPLES C-1

Change to Scope or Intent of Contract
Example Letter of Explanation C-2
Example Form 90 ..... C-3
Project Termini Extension, Type I – Routine
Example Letter of Explanation C-4
Example Form 90 ..... C-7
Project Termini Extension, Type II – Critical
Example Letter of Explanation C-8
Example Form 90 ..... C-11
Revision to Design
Example Letter of Explanation C-12
Example Form 90 ..... C-13

Table of Contents

Section **Page**

Revision to Method of Measurement
Example Letter of Explanation C-14
Example Form 90 ..... C-15
Administrative Claim Settlement
Example Letter of Explanation C-16
Example Form 90 ..... C-17
Correction of Design Error
Example Letter of Explanation C-18
Example Form 90 ..... C-19
Damage due to Unforeseen Causes
Example Letter of Explanation C-20
Example Form 90 ..... C-21
Inclusion of Right-of-Way Stipulations
Example Letter of Explanation C-22
Example Form 90 ..... C-23
Initiation of Utility Work – Utility Performs
Example Letter of Explanation C-24
Example Form 90 ..... C-25
Initiation of Utility Work – Contractor Performs
Example Letter of Explanation C-26
Example Form 90 ..... C-27
Extension of Utility Work
Example Letter of Explanation C-28
Example Form 90 ..... C-29
Change in Traffic Control Plan
Example Letter of Explanation C-30
Example Form 90 ..... C-31
Acceptance and Price Adjustment for Non-Specification Material
Example Letter of Explanation C-32
Example Form 90 ..... C-33
Purchase of Material
Example Letter of Explanation C-34
Example Form 90 ..... C-35
Value Engineering
Example Letter of Explanation C-36
Example Form 90 ..... C-37
Minor Contract Revision
Example Letter of Explanation C-38
Example Form 94 ..... C-39

APPENDIX D – MISCELLANEOUS DATA D-1

Legal Vehicle Dimensions D-3
Procedures for Measuring and Documenting Clearances D-5
Grade Stamps of Accredited Lumber Inspection Agencies D-7
Areas of Plane Figures D-17
Trigonometric Solutions of Triangles D-21
Probable Compressive Strength of Concrete Cylinders D-23
Conversion Tables D-24
Conversion Factors – Length Measurements D-25

Table of Contents

Section **Page**

Conversion Factors – Weight Measurements D-26
Conversion Factors – Area Measurements D-27
Conversion Factors – Volume Measurements D-28
Equivalent Weight of Aggregates D-29
Temperature-Volume Corrections for Emulsified Asphalts D-30

[Page Intentionally Blank]