

SECTION 757 RESERVED

SECTION 758 REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT, CURB, AND SIDEWALK

758.01 Description. This work consists of removing portions or all of the existing portland cement concrete pavement, curb, and sidewalk.

758.02 Construction Methods. The material to be removed shall be broken by an approved power breaking machine. A ball type breaker machine shall not be permitted. Extreme care shall be exercised by the Contractor in the operation to ensure that no damage occurs to any existing buried, surface, or aerial utility. The broken concrete materials shall become the property of the Contractor and shall be removed from the Project or otherwise disposed of as specified in [Subsection 106.09](#).

758.03 Method of Measurement. The quantity of removed existing portland cement concrete pavement, curb, and sidewalk will be measured in square yards (square meters) along the top surface of the materials to be removed, as projected on the horizontal plane.

758.04 Basis of Payment. The quantity of removed existing portland cement concrete pavement, curb, and sidewalk will be paid for at the Contract unit price per square yard (square meter). Price and payment will constitute full compensation for all labor, equipment, tools, and incidentals required to complete the work.

All material under existing areas ordered to be removed will be paid for under [Section 202](#)