

SECTION 761 BUTT JOINTS

761.01 Description. This work consists of constructing butt joints by saw cutting and removing the existing hot-mix, hot-laid bituminous concrete or portland cement concrete pavement to provide an area to butt the new hot-mix, hot-laid bituminous concrete pavement against the existing pavement.

761.02 Construction Methods. Construction methods shall conform to the requirements shown on the Plans. Saw cutting equipment shall conform to the requirements of [Subsection 762.02](#). Any saw cut beyond the limits shown on the Plans shall be filled with approved sealant. Pavement that has been removed in order to construct the butt joint shall be disposed of as specified in [Subsection 106.09](#).

761.03 Method of Measurement. The quantity of butt joints will be measured as the number of square yards (square meters) on the surface of the pavement as defined by the limits shown on the Plans.

761.04 Basis of Payment. The quantity of butt joints will be paid for at the Contract unit price per square yard (square meter). Price and payment will constitute full compensation for saw cutting, removing, and disposing of existing pavement; for sealing overcuts; and for all labor, materials, equipment, tools, and incidentals required to complete the work.