

208 PERVIOUS FILL

208.01 DESCRIPTION

This item shall consist of furnishing all materials, labor, tools and equipment necessary to place the Pervious Fill at the locations shown in the contract documents and/or as specified herein.

208.02 MATERIALS

Materials for this work shall conform to [805.02](#).

208.03 CONSTRUCTION REQUIREMENTS

This work shall be carried on in conjunction with the placement and compaction of the adjacent fill. The Pervious Fill material shall be placed in contact with the back of the walls and abutments as shown in the contract documents. The fill shall be compacted in horizontal layers not more than 1 foot in depth, to a minimum of 100 percent of the dry unit weight as determined by AASHTO T 19.

The Pervious Fill shall be placed so as not to mix with the earth backfill. If a form is used between the pervious fill material and earth backfill, none of it shall remain in the completed fill. Any earth backfill removed to place the Pervious Fill will be at the sole expense of the Contractor.

208.04 MEASURE AND PAYMENT

The unit of measure for Pervious Fill will be the cubic yard. The number of cubic yards will be the volume of Pervious Fill placed as determined from plan dimensions.

The number of cubic yards placed will be paid for at the contract unit price per cubic yard, which payment will include all labor, materials, tools, equipment and incidentals necessary to complete the work as specified herein.