

**I. Construction Exits**

Construction exits are paid for per each. Payment is full compensation for all materials including the required geotextile, construction, and removal.

**J. Retrofit**

This item is paid for at the Contract Unit Price per each. Payment is full compensation for all work, supervision, materials (including the stone filter), labor and equipment necessary to construct and remove the retrofit device from an existing or proposed detention pond outlet structure.

**K. Inlet Sediment Trap**

Inlet sediment traps are paid for per each. Payment is full compensation for all materials, construction, and removal

If temporary erosion control measures are required due to Contractor negligence, carelessness, or failure to install permanent controls as part of the work as scheduled, the Contractor shall perform such work at no additional expense to the Department. Perform the work according to Subsection 107.13.

Erosion control work on approved borrow pits or approved haul roads to borrow pits measured for payment will include only items specifically provided for in the Plans and determined not to be maintenance work as stated in Subsection 106.10.D. If the Contractor secures his or her own pit, erosion control measures will be at his or her expense. If a pit is approved and the Contractor elects to use another pit, the Department will pay only up to the contract amount.

The Items in this Section (except temporary grass and temporary mulch) are made as partial payments as follows:

- When the item is installed and put into operation the Contractor will be paid 75 percent of the Contract price.
- When the Engineer instructs the Contractor that the Item is no longer required and is to remain in place or is removed, whichever applies, the remaining 25 percent will be paid.

Temporary devices may be left in place at the Engineer's discretion at no change in cost. Payment for temporary grass and temporary mulch is shown in Section 161.

Payment is made under:

Item No. 163	Construct and remove silt control gate, type__	Per each
Item No. 163	Construct and remove temporary pipe slope drains__	Per linear foot (meter)
Item No. 163	Construct and remove baled straw erosion check__	Per linear foot (meter)
Item No. 163	Construct and remove sediment basin type__, Requires Sta. No.	Per each
Item No. 163	Construct and remove temporary ditch checks__	Per each
Item No. 163	Construct and remove construction exits	Per each
Item No. 163	Construct and remove retrofit, Sta. No.____	Per each
Item No. 163	Construct and remove inlet sediment trap	Per each
Item No. 163	Temporary Grass	Per pound (kilogram)
Item No. 163	Temporary Mulch	Per ton (megagram)
Item No. 700	Agricultural lime__	Per ton (megagram)

**163.5.01 Adjustments**

General Provisions 101 through 150.

## **Section 165—Maintenance of Temporary Erosion And Sedimentation**

### **Control Devices**

**165.1 General Description**

Specifications for this work will be included elsewhere in the Contract.