B. Alter Lakes or Ponds

If alteration is shown as a Pay Item, work shall include activities to change the physical size, shape, or depth of the lake; or to change the high-water level, or elevation of the dam or portions of it. This work shall be done according to the Plan details.

166.3.06 Quality Acceptance

General Provisions 101 through 150.

166.3.07 Contractor Warranty and Maintenance

General Provisions 101 through 150.

166.4 Measurement

Alteration or restoration of a lake is measured by the unit as indicated on the Plans and in the Proposal. Payment is full compensation for all necessary labor, equipment, tools, materials and incidentals required to complete the work to the satisfaction of the Engineer.

166.4.01 Limits

General Provisions 101 through 150.

166.5 Payment

Alteration or restoration of a lake is paid for at the Contract Unit Price bid per each for the specified operation as defined in Subsection 166.3.05, "Construction." Payment is full compensation for furnishing all labor, equipment, materials, tools and incidentals, and performing the work.

A. Restoration of a Lake

When the lake or pond is used as a settling basin, the work is paid for on the following schedule:

- Ten percent of the bid amount will be paid each time the lake or pond is cleaned of silt and debris during the construction period up to four occurrences.
- The remaining amount will be paid when the final cleaning and restoration are complete and accepted.

B. Alteration of a Lake

Alteration is paid on a pro-rata basis of the bid amount as the work progresses.

Payment will be made under:

Item No. 166	Restoration of lake, sta	Per each
Item No. 166	Alteration of lake, sta	Per each

166.5.01 Adjustments

General Provisions 101 through 150.

Section 167—Water Quality Monitoring

167.1 General Description

Specifications for this work will be included elsewhere in the Contract.

Section 170—Silt Retention Barrier

170.1 General Description

This work includes controlling water pollution where embankment construction or material removal may cause stream pollution.

Requirements of Sections 161, 162, and 163 apply to this Item. However, payment will not be made for erosion control items in those sections used with this work.