

446.4.01 Limits

General Provisions 101 through 150.

446.5 Payment

Payment will be made at the Contract Unit Price per square yard (meter) or per linear foot (meter) of reinforcement fabric as shown in Subsection 446.4, "Measurement."

Payment is full compensation for the work specified in this section, including cleaning the surface and furnishing and placing the asphalt cement binder and pavement reinforcement fabric.

Payment will be made under:

Item No. 446	Pavement reinforcement fabric strips, type___ including bituminous binder	Per linear foot (meter)
Item No. 446	Pavement reinforcement fabric full width, type___ including bituminous binder	Per square yard (meter)
Item No. 446	High Strength Pavement Reinforcement Fabric _____ inch (meter) Width	Per linear foot (meter)

446.5.01 Adjustments

General Provisions 101 through 150.

Section 447—Modular Expansion Joints**447.1 General Description**

Specifications for this work will be included elsewhere in the Contract.

Section 448—Portland Cement Concrete End Dams and Patches**448.1 General Description**

Specifications for this work will be included elsewhere in the Contract.

Section 449—Bridge Deck Joint Seals**449.1 General Description**

This work consists of furnishing and installing bridge deck joint sealing systems at the locations shown on the Plans.

These bridge deck joint sealing systems consist of a joint seal and may include concrete headers. Use a joint seal material that conforms to one of the following:

- A preformed elastomeric neoprene profile seal, or
- A low-density, closed cell, cross-linked, ethylene vinyl acetate, polyethylene copolymer, nitrogen-blown seal.

Use either epoxy concrete or elastomeric concrete for header material. Mix and use elastomeric and epoxy concrete material according to the manufacturer's guidelines.

449.1.01 Definitions

General Provisions 101 through 150.

449.1.02 Related References**A. Standard Specifications**

Section 106—Control of Materials

Section 501—Steel Structures

B. Referenced Documents

GDT 111