

- Materials and work necessary to remove lead-based paint and contain the spent materials
- Collection and storage of spent materials, water, and slurry generated by abrasive blasting

**535.4.01 Limits****A. Spent Materials**

Treatment of hazardous waste and subsequent disposal shall be paid for under a force account basis. The Engineer will reimburse the Contractor based upon invoices from the licensed hauler and disposal facility. An additional amount equal to 3% of the total invoices will be paid as administrative costs incurred by the Contractor.

The costs of collecting spent material, furnishing the containers, loading the material into containers, treating the material onsite, and loading the containers into the licensed hauling unit will not be paid for separately. These costs are considered incidental to the pay item.

The disposal of other spent materials collected is incidental to the Pay Item “Painting Existing Steel Structures.”

**B. Piling and Steel Swaybracing**

The cost of applying special protective coatings or paint to piling shall be included in the Contract Price for piling. No separate payment will be made.

The cost of applying special protective coatings or paint to steel swaybracing shall be included in the Contract Price for structural steel. No separate payment will be made.

**535.5 Payment**

Payment is full compensation for the costs, direct and indirect, of complying with the requirements of this Specification.

Payment will be made under:

Item No. 535	Painting existing steel structure, Station No. ____	Per lump sum
Item No. 535	Painting existing steel structure, Bridge I.D. No. ____	Per lump sum
Item No. 535	Painting existing steel structures, Railroad Special, Station No. ____	Per lump sum
Item No. 535	Painting existing steel structures, Railroad Special, Bridge I.D. No. ____	Per lump sum

**535.5.01 Adjustments**

General Provisions 101 through 150.

**Section 537—Cattle Pass****537.1 General Description**

Specifications for this work will be included elsewhere in the Contract.

**Section 538—Post-tensioned Prestressed Concrete Construction****538.1 General Description**

Specifications for this work will be included elsewhere in the Contract.

**Section 540—Removal of Existing Bridge****540.1 General Description**

This work consists of removing and disposing of or salvaging as specified in Subsection 540.3.05.C, “Disposal and Ownership of Material” all or parts of an existing bridge for the Department’s further disposition.