

Payment will be made under:

Item No. 666	Drill holes	Per linear foot (meter)
Item No. 666	Vertical drainage wicks	Per linear foot (meter)

666.5.01 Adjustments

General Provisions 101 through 150.

Section 667—Horizontal Drain

667.1 General Description

Specifications for this work will be included elsewhere in the Contract.

Section 668—Miscellaneous Drainage Structures

668.1 General Description

This work includes constructing catch basins, drop inlets, manholes, junction boxes, spring boxes, drain inlets, special inlets with safety grates, and vertical tee sections.

Construct according to these Specifications and the lines and grades shown on the Plans, or as established by the Engineer.

668.1.01 Definitions

General Provisions 101 through 150.

668.1.02 Related References

A. Standard Specifications

Section 207—Excavation and Backfill for Minor Structures

Section 500—Concrete Structures

Section 607—Rubble Masonry

Section 608—Brick Masonry

Section 801—Fine Aggregate

Section 830—Portland Cement

Section 834—Masonry Materials

Section 843—Concrete Pipe

Section 853—Reinforcement and Tensioning Steel

Section 854—Castings and Forgings

Section 866—Precast Concrete Catch Basin, Drop Inlet, and Manhole Units

B. Referenced Documents

General Provisions 101 through 150.

668.1.03 Submittals

General Provisions 101 through 150.

668.2 Materials

The structures in this section may be constructed of brick, cast-in-place concrete, or pre-cast concrete, unless the Plans or Proposal specifies a specific type of construction.