

**SECTION 310 - BROOMING OFF**

1  
2  
3  
4 **310.01 Description.** This section describes cleaning existing surface or  
5 pavement.

6  
7 **310.02 Materials.** None.

8  
9 **310.03 Construction.** Remove earth, dust and other foreign material, grass and  
10 other growth, raveled material, existing raised pavement markers, and traffic tapes  
11 from entire surface of work area. Remove grass and other growth from edges of  
12 work area and closely crop adjacent growth to prevent interference with subsequent  
13 project construction. Dispose of debris resulting from brooming off operations.

14  
15 Remove loose material and excess dust using mechanically operated street  
16 sweeper or mechanically operated broom, both equipped to contain dust generated  
17 from cleaning operations, or vacuum with HEPA filter. If necessary, supplement  
18 mechanical cleaning by hand brooming. Clean cracks and joints with compressed  
19 air. Complete this work while surface is dry.

20  
21 Control dust emissions in accordance with Section 620 - Dust Control.

22  
23 **310.04 Measurement.** The Engineer will not measure brooming off for payment.

24  
25 **310.05 Payment.** The Engineer will not pay for brooming off separately and will  
26 consider the cost for brooming off as included in the contract prices for the various  
27 contract pay items. The cost is for the work prescribed in this section and the  
28 contract documents.

29  
30  
31 **END OF SECTION 310**