

CHAPTER 1 GENERAL INFORMATION

1.00 GENERAL INFORMATION

- 1.01 OFFICE OF CONSTRUCTION
- 1.02 CONSTRUCTION ENGINEER
- 1.03 DISTRICT CONSTRUCTION ENGINEER (DCE)
- 1.04 PROJECT ENGINEER
- 1.05 PURPOSE OF MANUAL

1.10 ENGINEER RELATIONS

- 1.11 WITH PUBLIC
- 1.12 WITH CONTRACTOR
- 1.13 WITH FHWA & OTHER OUTSIDE AGENCIES
- 1.14 EMPLOYMENT OF CONSULTANTS FOR CONSTRUCTION ENGINEERING AND INSPECTION

1.20 PERSONNEL

- 1.21 EMPLOYEE POLICIES
- 1.22 GUIDELINES FOR CHARGING TIME OF FIELD CONSTRUCTION STAFF

1.30 MISCELLANEOUS

- 1.31 SIGNATURE AUTHORIZATION
- 1.32 DETOUR ROAD AND EMBARGO MAP INFORMATION
- 1.33 HIGH VISIBILITY PROJECT CONSTRUCTION REPORT
- 1.34 MANUAL OF OPERATING PROCEDURES

CHAPTER 2 CONTRACT ADMINISTRATION

2.00 PROJECT ORGANIZATION

- 2.01 AUTHORITY OF ENGINEER
- 2.02 RESPONSIBILITY OF PROJECT ENGINEER
- 2.03 DELEGATION OF RESPONSIBILITY

2.10 PRECONSTRUCTION

- 2.11 PRECONSTRUCTION CONFERENCE
- 2.12 HAUL ROADS
- 2.13 STREAM CROSSINGS
- 2.14 WATER REGISTRATION AND PERMIT

2.20 CONTRACT ADMINISTRATION

- 2.21 OCCUPATIONAL SAFETY AND HEALTH
- 2.22 EQUAL EMPLOYMENT OPPORTUNITY (EEO)
- 2.23 TRAINING PROGRAMS
- 2.24 DAVIS-BACON WAGE REQUIREMENTS
- 2.25 SUBCONTRACTS
- 2.26 USE OF EXCESS PROPERTY OR HIGHWAY RIGHT-OF-WAY
- 2.27 "CONTRACT QUANTITY AGREEMENT" - FORM 830230
- 2.28 RELEASE OF RETAINED FUNDS
- 2.29 CONTRACTOR REQUIRED FINAL DOCUMENTATION

2.30 CONSTRUCTION PERIOD

- 2.31 ADMINISTRATION OF THE CONTRACT PERIOD
- 2.32 NOTICE TO PROCEED (FORM 830237)
- 2.33 WEEKLY REPORT OF WORKING DAYS (FORM 830238)

- 2.34 LIQUIDATED DAMAGES & EXTENSION OF CONTRACT TIME
- 2.35 EQUIPMENT RENTAL RATES
- 2.36 CHANGE ORDERS (FORM 830240)
- 2.37 PROJECT ACCEPTANCE AND AUTHORIZATION FOR FINAL PAYMENT
- 2.38 CONTRACTOR EVALUATION REPORT (FORM 830430)

2.40 PROJECT REVIEW AND AUDITS

- 2.41 RESERVED FOR FUTURE USE
- 2.42 PROJECT ENGINEER'S PRE-AUDIT
- 2.43 DISTRICT OFFICE AUDIT
- 2.44 MANUAL OF OFFICE PROCEDURES
- 2.45 FORMS FOR FINAL PAYMENT PACKET

2.50 CONTRACTOR PAYMENTS AND PRICE ADJUSTMENTS

- 2.51 PAYMENT FOR MATERIAL ALLOWANCE
- 2.52 PAYMENT FOR UNEXPECTED CLASS 12 ROCK EXCAVATION
- 2.53 PRICE ADJUSTMENT GUIDE FOR REASONABLY CLOSE CONFORMING, REASONABLY ACCEPTABLE, AND DEFICIENT WORK
- 2.54 PRICE ADJUSTMENT CHANGE ORDERS
- 2.55 FINAL PAYMENT TO CONTRACTOR
- 2.56 FUEL ADJUSTMENT

2.60 CONSTRUCTION FORMS

2.70 RELEASE OF TEMPORARY EASEMENT (Right of Way Form 636-069)

- 2.71 BRIDGE INVENTORY REPORT
- 2.72 PREPARATION OF "AS-BUILT" PLANS
- 2.73 RELOCATION OF WATER STOP BOXES
- 2.74 PRECONSTRUCTION PROJECT AGREEMENTS

CHAPTER 3 GENERAL INSPECTION

3.00 GENERAL INSPECTION INSTRUCTIONS

- 3.01 INSPECTION PERSONNEL
- 3.02 SUPERVISION BY SUBCONTRACTOR
- 3.03 COMMUNICATION WITH CONSULTANTS AND CONSULTANT PLAN ERRORS
- 3.04 REMOVING MATERIALS FROM PROJECTS
- 3.05 SALVAGED PROJECT MATERIALS REPORTING
- 3.06 NOTICE OF SUSPENSION OR RESUMPTION OF WORK
- 3.07 REQUIREMENTS FOR MONITORING THE CERTIFIED PLANT INSPECTION PROGRAM AND QUALITY MANAGEMENT - ASPHALT (QM-A)

3.10 DIARIES, RECORDS, AND MEASUREMENTS

- 3.11 MEASUREMENT OF PAY QUANTITIES AND RETENTION OF RECORDS

3.20 FIELD TESTS

- 3.21 FIELD TESTING ON CONSTRUCTION PROJECTS
- 3.22 CONTRACTOR ASSISTED SAMPLING AND VALIDATION OF CONTRACTOR TEST RESULTS

3.30 CONTROL OF MATERIALS

- 3.31 IDENTIFICATION OF APPROVED MATERIALS
- 3.32 DOCUMENTATION OF APPROVED STEEL BEAM RAILING

3.40 HAULING OF MATERIALS

3.50 WEIGHING EQUIPMENT FOR DETERMINATION OF PAY QUANTITIES

3.60 SMOOTHNESS

3.61 TESTING

3.62 EVALUATION

3.63 BUMP CORRECTION

3.70 IMPACTS TO ADJOINING PROPERTY

3.71 ACCESS LOCATIONS ON CONSTRUCTION PROJECTS

3.72 RELOCATION OF MAILBOXES

3.73 INTERIM USE OF PROPERTY BETWEEN ACQUISITION & CONSTRUCTION

3.74 INVOLVEMENT OF LAW ENFORCEMENT ON CONSTRUCTION PROJECTS

CHAPTER 4 CONSTRUCTION SURVEY

4.00 GENERAL STAKING REQUIREMENTS

4.10 RIGHT OF WAY

4.11 INSTALLATION OF RIGHT-OF-WAY MARKERS

4.20 LAND MONUMENTS AND ROAD CENTERLINE

4.21 RE-ESTABLISHING ROAD CENTERLINE CONTROL POINTS

4.22 REPLACEMENT OF FEDERAL MONUMENTS & PRESERVATION OF ENGINEERING DATA

4.23 CENTERLINE POINT REFERENCING

4.24 BENCH MARKS

4.30 CONTRACTOR FURNISHED CONSTRUCTION SURVEY

CHAPTER 5 SAFETY

5.00 SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION

5.01 RESPONSIBILITY OF CONTRACTOR

5.02 RESPONSIBILITY OF CONTRACTING AUTHORITY

5.10 EMPLOYEE RIGHT-TO-KNOW

5.20 CONSTRUCTION WORK ZONE TRAFFIC CONTROL

5.21 TRAFFIC CONTROL SPECIFICATION REFERENCES

5.22 TRAFFIC CONTROL EVALUATION AND CHANGES

5.23 CONSTRUCTION ZONE CRASH REPORTING

5.24 STOP SIGNS ON CONSTRUCTION PROJECTS

5.25 "ROAD WORK AHEAD" AND "END ROAD WORK" SIGNS

5.26 NO PASSING ZONES ON CONSTRUCTION PROJECTS

5.27 EQUIPMENT AND MATERIAL STORAGE

5.28 CONSTRUCTION WORK ZONE SIGNING DURING WINTER SHUTDOWN

5.29 FLAGGERS & PILOT CARS

5.30 MULTILANE HIGHWAY TRAFFIC CONTROL ISSUES

5.31 CHANGEABLE MESSAGE SIGN GUIDELINES

- 5.32 ARROW DISPLAYS
- 5.33 TEMPORARY CONCRETE BARRIER RAIL
- 5.34 SIGN MOUNTING TYPES
- 5.35 REMOVAL OF TEMPORARY PAVEMENT MARKINGS
- 5.36 NCHRP 350 CRASHWORTHY WORK ZONE DEVICES
- 5.37 INSTALLATION OF TRAFFIC CONTROL ZONES
- 5.38 SIGNALIZED VS. FLAGGER CONTROLLED HAUL ROAD CROSSINGS
- 5.39 TRAFFIC CONTROL EVALUATION REPORTING FORM

5.40 TRAFFIC QUALITY CONTROL

- 5.41 ROAD CLOSED vs. ROAD CLOSED TO THRU TRAFFIC
- 5.42 TEMPORARY WORK ZONE SPEED LIMITS
- 5.43 FLAGGER AND WORKER SAFETY APPAREL (ANSI 107)

5.50 TEMPORARY INSTALLATION OF ELECTRICAL POWER LINES

CHAPTER 6 GRADING

6.00 GENERAL GRADING INSTRUCTIONS

- 6.01 ROAD CROSSING FOR CONSTRUCTION EQUIPMENT

6.10 SITE PREPARATION

- 6.11 CLEARING AND GRUBBING
- 6.12 REMOVAL AND DISPOSAL OF OLD PAVEMENT
- 6.13 DISPOSAL OF HOT MIX ASPHALT PAVEMENT
- 6.14 DEMOLITION

6.20 TOPSOIL

- 6.21 STRIPPING, SALVAGING, AND SPREADING

6.30 EXCAVATION

- 6.31 PEAT EXCAVATION
- 6.32 ROCK EXCAVATION
- 6.33 USE OF AND PAYMENT FOR WATER USED FOR EXCAVATION AND EMBANKMENT
- 6.34 CONTRACTOR FURNISHED BORROW AREAS
- 6.35 PRESERVATION OF CULTURAL RESOURCES

6.40 EMBANKMENT

- 6.41 EMBANKMENT CONSTRUCTION
- 6.42 OVERHAUL
- 6.43 SETTLEMENT PLATES

6.50 PIPE CULVERTS BY THE GRADING CONTRACTOR

- 6.51 MATERIAL
- 6.52 PIPE INSTALLATION
- 6.53 CULVERT ABANDONMENT
- 6.54 LOAD LIMITS OVER CULVERTS

6.60 SUBDRAINS

- 6.61 TILE RELOCATION
- 6.62 BACKSLOPE DRAINS

6.63 LONGITUDINAL DRAINS

CHAPTER 7 EROSION CONTROL

7.00 GENERAL INSPECTION

7.01 EQUIPMENT

7.02 CONTRACT ADMINISTRATION

7.10 PERMANENT EROSION CONTROL

7.11 PREPARATION OF SEEDBED

7.12 PREPARATION OF SEED MIXTURE

7.13 CONVENTIONAL SEEDING

7.14 HYDRO-SEEDING (HYDRAULIC SEEDING)

7.15 URBAN SEEDING

7.16 OVERSEEDING

7.17 OVERSEEDING AND FERTILIZING

7.18 AERIAL SEEDING

7.20 FERTILIZER

7.21 EXAMPLE CALCULATIONS

7.22 APPLICATION OF FERTILIZER

7.30 MULCH

7.31 EXAMPLE CALCULATION (English Units only)

7.40 WATER POLLUTION CONTROL (SOIL EROSION)

7.41 CONTRACTOR REQUIREMENTS

7.50 SODDING

7.51 PAYMENT

7.60 SPECIAL DITCH CONTROL

7.61 PLACEMENT

7.62 MAINTENANCE

7.63 PAYMENT

7.70 SUGGESTED EROSION CONTROL DEVICES FOR SPECIFIC SITUATIONS

CHAPTER 8 HOT MIX ASPHALT (HMA) PAVEMENT, BASES, AND SUBBASES

8.00 TABLES AND REPORT FORMS

8.01 TABLES FOR BITUMINOUS MATERIALS AND HMA CONSTRUCTION

8.02 REPORT FORMS

8.10 ACCEPTANCE AND TESTING

8.11 FIELD TESTS AND CERTIFICATION OF MATERIALS

8.12 RESPONSIBILITY AND DOCUMENTING HMA MIXTURE PROPORTIONING CHANGES

8.13 DENSITY CONTROLS FOR HMA CONSTRUCTION

8.14 TESTING FOR SMOOTHNESS

8.15 CHECKING TRANSVERSE JOINTS FOR SMOOTHNESS

8.20 MEASUREMENTS AND PAYMENT COMPUTATIONS

8.21 ASPHALT BINDER

8.22 TARGET VALUES FOR ASPHALT BINDER CONTENT IN JOB MIXES

8.23 WEIGHING OF HMA MATERIALS

8.30 EQUIPMENT USE AND INSPECTION

8.31 INSPECTION AT HMA PLANTS

8.32 INSPECTING THE MIXING TIME OF HMA PLANTS

8.40 GENERAL CONSTRUCTION

8.41 UNSTABLE SUBGRADES AND SUBBASES

8.42 STAKING METHOD FOR HMA PAVEMENTS

8.43 GUIDELINE STRINGS AND EDGE ALIGNMENT

8.44 LONGITUDINAL JOINTS

8.45 TACK COATS USING EMULSIONS

8.50 BASE, INTERMEDIATE, AND SURFACE COURSES

8.51 HMA WEDGE CONSTRUCTION FOR SUPERELEVATION OF CURVES

8.52 LAYING WIDTHS FOR HMA

8.53 SPREAD RATES FOR HMA BASE, INTERMEDIATE, AND SURFACE COURSES

8.54 HMA RESURFACING ON CITY STREETS

8.55 COLD WEATHER HMA CONSTRUCTION

8.56 RELEASE AGENTS AND SOLVENTS

8.60 RUMBLE STRIPS IN HMA SHOULDERS

8.61 CONSTRUCTION CONSIDERATIONS - MILLED RUMBLE STRIPS

8.62 CONSTRUCTION CONSIDERATIONS - ROLLED RUMBLE STRIPS

8.70 INSPECTOR'S GUIDE - HMA PAVING & RESURFACING

8.80 USE OF SPECIAL EQUIPMENT

CHAPTER 9 PORTLAND CEMENT CONCRETE (PCC) PAVEMENT

9.00 GENERAL

9.01 PRE-CONCRETING CONFERENCE

9.02 "PCC PLANT PAGE" (FORMS 800240E and 800240M)

9.03 USE OF COMMERCIAL READY MIX CONCRETE ON PAVING PROJECTS

9.04 CONCRETE DELIVERY TIMES

9.10 EQUIPMENT

9.11 TEMPLATE FOR CHECKING GRADES ON DRIVES ON URBAN PAVING PROJECTS

9.12 USE AND CARE OF WHEELED SURFACE CHECKER

9.13 ACCUMULATION OF MATERIALS IN TRANSPORTING VEHICLES

9.14 PCC FINISHING MACHINES

9.15 OPERATING FINISHING EQUIPMENT ON PREVIOUSLY PLACED CONCRETE IN MULTIPLE-LANE CONSTRUCTION WORK

9.16 EQUIPMENT WEIGHT LIMITATIONS ON NEW PAVEMENTS & PCC OVERLAYS

9.20 PAVEMENT JOINTS

9.21 JOINT SAWING

9.22 CLEANING JOINTS

- 9.23 SEALING SAWED JOINTS
- 9.24 RESERVED FOR FUTURE USE
- 9.25 CD, ED, EE & EF JOINTS, AND OTHER DOWELED SUPPORT ASSEMBLIES
- 9.26 LONGITUDINAL JOINTS DESIGN
- 9.27 LONGITUDINAL JOINT (L JOINT) TIE-STEEL INSPECTION
- 9.28 SAW CUTS IN FULL DEPTH PCC PATCHES

9.30 INTAKES AND UTILITY ACCESSES

- 9.31 INTAKE CONSTRUCTION ON PAVING JOBS
- 9.32 BOX-OUTS FOR UTILITY ACCESSES
- 9.33 BOX-OUTS ON SLIPFORM PAVING

9.40 SURFACE FINISHING

- 9.41 USE OF WATER IN FINISHING CONCRETE
- 9.42 MICROTEXTURE AND MACROTEXTURE
- 9.43 GROOVE DEPTH DETERMINATION
- 9.44 PAVEMENT CROWN
- 9.45 STRAIGHTEDGEING PAVEMENT SURFACE
- 9.46 PAVEMENT DATE STAMPING

9.50 PROTECTION, CURING, AND REPAIR

- 9.51 PREVENTION OF RAIN DAMAGE TO PLASTIC CONCRETE
- 9.52 CURING OF KEYED AND DOWELED JOINTS
- 9.53 REPAIR OF DEFICIENT PAVEMENT
- 9.54 MUD BALL REPAIR
- 9.55 COLD WEATHER PAVING AND PLANT OPERATIONS
- 9.56 CURING APPLICATION

9.60 CONCRETE MATERIALS ISSUES

- 9.61 CONCRETE SAMPLING LOCATIONS
- 9.62 TESTING PROCEDURES
- 9.63 AIR ENTRAINMENT IN PLASTIC CONCRETE
- 9.64 CONCRETE VIBRATION AND CONSOLIDATION
- 9.65 PAVEMENT THICKNESS CORES
- 9.66 PAVEMENT SMOOTHNESS
- 9.67 QUALITY MANAGEMENT CONCRETE (QM-C)

9.70 PCC PATCHING

- 9.71 PCC PATCHING
- 9.72 PARTIAL-DEPTH PCC PATCHES

CHAPTER 10 ENVIRONMENTAL

10.00 INTRODUCTION

10.10 CLEAN AIR ACT

- 10.11 VOCs

10.20 UNDERGROUND TANKS

- 10.21 REGISTRATION
- 10.22 REMOVAL OF USTs

10.30 STORM WATER DISCHARGE

- 10.31 NOTICE OF INTENT (NOI)
- 10.32 TYPES OF STORM WATER PERMITS
- 10.33 ADMINISTERING PROJECTS WITH STORM WATER DISCHARGE PERMITS
- 10.34 QUESTIONS OFTEN ASKED

10.40 WETLANDS AND SECTION 404 PERMITS - INTRODUCTION

- 10.41 WETLANDS - DEFINITION AND REGULATION
- 10.42 PERMIT PROCESS
- 10.43 MITIGATION
- 10.44 MITIGATION AS-BUILT PLANS
- 10.45 MITIGATION MONITORING
- 10.46 PRECONSTRUCTION CONFERENCE
- 10.47 COMPLETED WORK CERTIFICATION FORM
- 10.48 CONSTRUCTION WORK NOT SHOWN ON PLANS

10.50 BRIDGE PAINTING

- 10.51 METHODS OF PAINT REMOVAL
- 10.52 CONTAINMENT
- 10.53 TOUCH-UP WORK
- 10.54 PAINT WASTE DISPOSAL
- 10.55 PAINTING ISSUES

10.60 DISPOSAL OF CONSTRUCTION WASTES

- 10.61 DEMOLITION WASTE, CLEARING & GRUBBING
- 10.62 ASBESTOS
- 10.63 PAINT WASTE
- 10.64 LIGHT BULBS, THERMOSTATS, & BALLASTS

10.70 WELLS AND WATER POLLUTION

- 10.71 SURFACE SPILLS (ON LAND OR WATER)
- 10.72 PLUGGING WELLS (WATER OR MONITORING)

CHAPTER 11 STRUCTURES

11.00 INTRODUCTION

- 11.01 REMOVAL OF BRIDGES
- 11.05 PILE DRIVING CAP AND HAMMER INFORMATION

11.10 EARTHWORK FOR STRUCTURES

- 11.11 EXCAVATION
- 11.12 BACKFILLING STRUCTURES

11.20 FOUNDATIONS

- 11.21 STAKING AND CHECKING LOCATIONS OF STRUCTURES
- 11.22 PILING AND PILE DRIVING
- 11.23 SPLICING PILE
- 11.24 PILING ACCEPTANCE
- 11.25 WAVE EQUATION
- 11.26 PREBORED HOLES
- 11.27 DRILLED SHAFTS

11.30 BRIDGES

- 11.31 FALSEWORK
- 11.32 BRIDGES - STEEL BEAM
- 11.33 BRIDGES - CONCRETE BEAM

11.40 REINFORCEMENT

- 11.41 PLACEMENT AND CHECKING (BRIDGE FLOORS)
- 11.42 EPOXY COATED REINFORCEMENT
- 11.43 CAGE STEEL (DRILLED SHAFTS)
- 11.44 SPLICING
- 11.45 PAYMENT FOR REINFORCING STEEL

11.50 CONCRETE (STRUCTURAL, CLASS X, AND FLOWABLE MORTAR)

- 11.51 PCC PLANT PAGE (FORMS 800240E and 800240M)
- 11.52 USE OF READY MIXED STRUCTURAL CONCRETE
- 11.53 ADMIXTURES
- 11.54 USE OF INSULATED FORMS FOR PROTECTION
- 11.55 DECK PLACEMENT AND HEAT OF HYDRATION
- 11.56 PLACEMENT METHODS (PUMPING, BELTING, AND CRANE BUCKET)
- 11.57 FORM REMOVAL
- 11.58 CLASS 3 CONCRETE SURFACE FINISH (RAIL AND BEAMS)
- 11.59 FLOWABLE MORTAR

11.60 DECKS AND OVERLAYS

- 11.61 DECK OVERLAY PREPARATION
- 11.62 SEQUENCE OF POURING
- 11.63 INSTALLATION OF JOINTS
- 11.64 BRIDGE FLOORS
- 11.65 CONCRETE
- 11.66 APPROACH SECTIONS
- 11.67 SMOOTHNESS OF BRIDGE DECKS

11.70 BARRIER RAILS

- 11.71 F-SHAPE & RETROFIT RAIL
- 11.72 SLIP FORM BARRIER RAIL
- 11.73 CAST-IN-PLACE (RETROFIT) BARRIER RAIL
- 11.74 CAST-IN-PLACE OPEN BARRIER RAIL FORM REMOVAL

11.80 REINFORCED CONCRETE CULVERTS

- 11.81 DESIGN CHANGES ON CULVERTS
- 11.82 INSTALLING REINFORCING STEEL, PLACING CONCRETE, AND FORM REMOVAL
- 11.83 BOX CULVERT CURTAIN WALLS
- 11.84 BOX CULVERT BELL JOINTS

CHAPTER 12 INCIDENTAL CONSTRUCTION

12.00 UTILITIES

- 12.01 UTILITY RELOCATION
- 12.02 UTILITY RELOCATION - FEDERAL AID PROJECTS
- 12.03 RAILROAD AGREEMENTS FOR HIGHWAY PROJECT ACCOMMODATION
- 12.04 "CERTIFICATE OF COMPLETION AND FINAL ACCEPTANCE FOR AGREEMENT WORK"
(FORM 640003)

12.10 PERMANENT LIGHTING

- 12.11 SHOP DRAWINGS
- 12.12 STAKING OF LIGHT POLE FOOTINGS
- 12.13 FOOTINGS FOR LIGHT POLES
- 12.14 WOOD POLES ON LIGHTING PROJECTS
- 12.15 TESTING LIGHTING CIRCUITS
- 12.16 PAYMENT FOR LIGHTING PROJECT ELECTRIC POWER
- 12.17 COMPLETION AND ACCEPTANCE

12.20 PERMANENT SIGNING

- 12.21 ACCEPTANCE OF SIGNS ON SIGNING CONTRACTS
- 12.22 OVERHEAD SIGN TRUSS CONSTRUCTION

12.30 FORMED STEEL BEAM GUARDRAIL

- 12.31 GENERAL INSTRUCTIONS
- 12.32 FORMED STEEL BEAM GUARDRAIL INSTALLATION
- 12.33 END ANCHORAGE
- 12.34 BRIDGE CONNECTIONS
- 12.35 OBJECT MARKERS
- 12.36 DELINEATORS

12.40 PAVEMENT SURFACE REPAIR

- 12.41 DIAMOND GRINDING
- 12.42 NIGHTTIME DIAMOND GRINDING