

831 - DITCH LINING

SECTION 831

DITCH LINING

831.1 DESCRIPTION

Construct the designated types of ditch lining as shown in the Contract Documents.

BID ITEMS

Aggregate Ditch Lining (*)
Aggregate Backslope Ditch Lining
Concrete Ditch Lining
Concrete Backslope Ditch Lining
*Size

UNITS

Ton
Ton
Square Yard
Square Yard

831.2 MATERIALS

Provide materials that comply with the applicable requirements.

Concrete and Grout	DIVISION 400
Stone	DIVISION 1100
Type 2 Liquid Membrane-Forming Compound	DIVISION 1400
Welded Steel Wire Fabric	DIVISION 1600
Fibrous Concrete Reinforcement	DIVISION 1700

831.3 CONSTRUCTION REQUIREMENTS

a. General. Construct the ditch to the lines and grades shown in the Contract Documents before placing the ditch lining. Prepare for the ditch lining by undercutting the finished ditch to the depth required for the ditch lining. When required, compact the excavated area. The subgrade shall be well compacted prior to placing ditch lining. After the ditch lining is completed, backfill and compact around the structures.

b. Aggregate Ditch Lining and Aggregate Backslope Ditch Lining. Construct the aggregate ditch lining and aggregate backslope ditch lining according to the Contract Documents.

c. Concrete Ditch Lining and Concrete Backslope Ditch Lining. Construct the concrete ditch lining and concrete backslope ditch lining according to the Contract Documents. After the steel reinforcement is in place, place the concrete starting at the lower end and progressing to the upper end of the ditch lining.

Use Grade 3.0(AE) concrete, unless shown otherwise in the Contract Documents.

Fibrous concrete reinforcement may be used in lieu of steel mesh, unless specified otherwise in the Contract Documents. If fibrous concrete reinforcement is used, comply with these requirements:

- Use the fibers at the rate specified by the manufacturer. Add the fibers to the concrete mixture at the same time the individual concrete components are added and before the mixing revolutions are started at the concrete batch plant.
- Have a technical representative of the fiber manufacturer present at the concrete batch plant to obtain proper proportioning and mixing of the product. The Engineer will waive this requirement if the Contractor can provide evidence of previously satisfactorily using the product.

Finish the concrete surface with a wooden float, followed by a light brooming. Do not walk on the concrete surface during placement.

Apply Type 2 liquid membrane-forming compound as the curing medium. Apply the curing medium immediately after the concrete surface is finished, and before the set takes place. Maintain the cure for 7 days. In cold weather, maintain the concrete temperature above 32°F for the first 4 days of the 7 day cure.

831 - DITCH LINING

831.4 MEASUREMENT AND PAYMENT

The Engineer will measure aggregate ditch lining and aggregate backslope ditch lining by the ton.

The Engineer will measure concrete ditch lining by the square yard, measured along the finished surfaces.

Payment for "Aggregate Ditch Lining", "Aggregate Backslope Ditch Lining", "Concrete Ditch Lining" and "Concrete Backslope Ditch Lining" at the contract unit prices is full compensation for the specified work.