

**TABLE OF CONTENTS**  
**PART I**

<b>SECTION</b>	<b>PAGE</b>
<b>1.00 GENERAL.....</b>	<b>1</b>
1.01 PURPOSE .....	1
<b>1.02 DEFINITIONS .....</b>	<b>1</b>
<b>1.03 KANSAS DEPARTMENT OF TRANSPORTATION.....</b>	<b>1</b>
1.03.01 ORGANIZATION AND OVERVIEW OF ORGANIZATIONAL STRUCTURE .....	1
1.03.02 SECRETARY OF TRANSPORTATION .....	4
1.03.03 THE ASSISTANT SECRETARY AND STATE TRANSPORTATION ENGINEER..	4
1.03.04 DIVISION DIRECTORS .....	4
1.03.05 BUREAU OF CONSTRUCTION AND MAINTENANCE .....	9
1.03.06 BUREAU OF MATERIALS AND RESEARCH.....	9
1.03.07 BUREAU OF TRAFFIC ENGINEERING .....	9
1.03.08 DISTRICT ORGANIZATION.....	10
1.03.09 THE DISTRICT ENGINEER .....	10
1.03.10 DISTRICT CONSTRUCTION ENGINEER .....	10
1.03.11 DISTRICT MATERIALS ENGINEER .....	11
1.03.12 METRO AND AREA ENGINEER.....	11
1.03.13 FIELD ENGINEER.....	11
1.03.14 ENGINEERS AND ENGINEERING TECHNICIANS .....	12
<b>1.04 RELATIONS.....</b>	<b>12</b>
1.04.01 GENERAL .....	12
1.04.02 GENERAL PUBLIC .....	12
1.04.03 ADJACENT PROPERTY OWNERS .....	13
1.04.04 LOCAL OFFICIALS .....	13
1.04.05 UTILITIES .....	13
1.04.06 CONTRACTOR.....	14
1.04.07 INTERDEPARTMENT RELATIONS .....	14
1.04.08 FEDERAL HIGHWAY ADMINISTRATION .....	14
<b>1.05 INTEGRITY OF THE INSPECTOR .....</b>	<b>15</b>
1.05.01 INTEGRITY .....	15
<b>1.06 EQUIPMENT .....</b>	<b>16</b>
1.06.01 ENGINEERING EQUIPMENT .....	16
1.06.02 VEHICULAR EQUIPMENT .....	16
<b>1.07 SAFETY .....</b>	<b>17</b>
1.07.01 GENERAL .....	17
1.07.02 VEHICULAR TRAFFIC .....	17
1.07.03 OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION .....	18
1.07.04 CREW SAFETY .....	18
1.07.05 ACCIDENT REPORTS .....	19
1.07.06 HAZARDOUS MATERIALS ACCIDENTS .....	20
1.07.07 ACCIDENT PREVENTION MEETINGS.....	21

**TABLE OF CONTENTS**  
**PART I (Continued)**

SECTION	PAGE
<b>1.08 PERSONNEL .....</b>	<b>21</b>
1.08.01 EMPLOYMENT REGULATIONS .....	21
1.08.02 EXPENSES, TIME RECORDS AND EQUIPMENT RECORDS.....	21
<b>1.09 HISTORICAL SITES.....</b>	<b>21</b>
1.09.01 ARCHAEOLOGICAL AND PALEONTOLOGICAL SALVAGE.....	21
<b>1.10 LABOR REGULATIONS.....</b>	<b>21</b>
1.10.01 GENERAL .....	21
1.10.02 ENFORCEMENT OF LABOR PROVISIONS.....	21
<b>1.11 EQUAL EMPLOYMENT OPPORTUNITY .....</b>	<b>27</b>
1.11.01 GENERAL .....	27
1.11.02 APPLICABILITY .....	28
1.11.03 DUTIES OF FIELD ENGINEER.....	28
<b>1.12 UTILITY RELOCATION AND ADJUSTMENT .....</b>	<b>28</b>
1.12.01 GENERAL .....	28
1.12.02 PERMITS .....	28
1.12.03 AGREEMENTS .....	29
1.12.04 UTILITY CHANGE ORDERS .....	30
1.12.05 PRECONSTRUCTION CONFERENCE.....	30
1.12.06 PROGRESS OF WORK.....	30
1.12.07 INSPECTION OF WORK.....	30
1.12.08 LUMP SUM AGREEMENTS.....	31
1.12.09 ACTUAL COST AGREEMENTS .....	31
1.12.10 INSPECTION OF RECOVERED MATERIAL .....	31
1.12.11 FINAL BILLING .....	32
1.12.12 PROCEDURES FOR UTILITY RELOCATION ON KDOT PROJECTS .....	32
1.12.13 PROCEDURES FOR UTILITY RELOCATION FOR LOCAL PROJECTS .....	36
<b>1.13 RIGHT OF WAY REVIEW .....</b>	<b>38</b>
1.13.01 PRECONSTRUCTION REVIEW .....	38
1.13.02 UTILITIES .....	38
1.13.03 ENCROACHMENTS .....	38
1.13.04 MAILBOX ADJUSTMENTS .....	38
1.13.05 BORROW .....	39
<b>1.14 SALES TAX EXEMPTION.....</b>	<b>39</b>
1.14.01 GENERAL .....	39
1.14.02 EXEMPTION CERTIFICATE NUMBER .....	39
1.14.03 PROJECT COMPLETION CERTIFICATION .....	40
<b><u>INDEX TO PLATES</u></b>	
ORGANIZATIONAL CHART .....	3

**TABLE OF CONTENTS**  
**PART II**

SECTION	PAGE
<b>2.00 CONTRACT ADMINISTRATION .....</b>	<b>1</b>
<b>2.01 BIDDING REQUIREMENTS AND CONDITIONS.....</b>	<b>1</b>
<b>2.02 AWARD AND EXECUTION OF CONTRACT .....</b>	<b>1</b>
<b>2.03 LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC .....</b>	<b>1</b>
2.03.01 GENERAL .....	1
2.03.02 PUBLIC CONVENIENCE AND SAFETY .....	1
2.03.03 TRAFFIC CONTROL DEVICES .....	1
<b>2.04 SCOPE OF WORK.....</b>	<b>2</b>
2.04.01 QUANTITY CHANGES .....	2
2.04.02 DETOURS .....	3
2.04.03 USE OF MATERIAL FOUND ON THE PROJECT .....	3
<b>2.05 PROJECT ORGANIZATION.....</b>	<b>4</b>
2.05.01 PROJECT ASSIGNMENT .....	4
2.05.02 DELEGATION OF AUTHORITY.....	4
2.05.03 CONTRACT DOCUMENTS .....	5
2.05.04 PROJECT ORIENTATION AND REVIEW .....	5
2.05.05 PROJECT PERSONNEL CONFERENCE .....	5
2.05.06 CONSTRUCTION ENGINEERING .....	6
<b>2.06 PRECONSTRUCTION CONFERENCE .....</b>	<b>6</b>
<b>2.07 CONTROL OF WORK.....</b>	<b>9</b>
2.07.01 AUTHORITY .....	9
2.07.02 CORRESPONDENCE.....	10
2.07.03 RESPONSIBILITY, AUTHORITY AND BEHAVIOR OF THE INSPECTOR .....	10
2.07.04 REMOVAL OF UNACCEPTED AND UNAUTHORIZED WORK .....	12
2.07.05 PARTIAL AND FINAL ACCEPTANCE .....	13
<b>2.08 CONTROL OF MATERIALS.....</b>	<b>13</b>
<b>2.09 PROSECUTION AND PROGRESS .....</b>	<b>13</b>
2.09.01 SUBCONTRACTING .....	13
2.09.02 PROSECUTION AND PROGRESS .....	14
2.09.03 CHARACTER OF WORKERS, METHODS AND EQUIPMENT .....	16
2.09.04 CONTRACT TIME .....	16
2.09.05 CLAIMS AGAINST CONTRACTORS.....	16
2.09.06 CONTRACTOR CLAIMS .....	16

**TABLE OF CONTENTS**  
**PART III**

SECTION NO.	PAGE
<b>3.00 SURVEYING EQUIPMENT .....</b>	<b>1</b>
<b>3.01 EQUIPMENT RECORDS .....</b>	<b>1</b>
3.01.01 RECEIPT OF EQUIPMENT .....	1
3.01.02 ANNUAL INVENTORY .....	1
3.01.03 SERIAL NUMBERS .....	1
<b>3.02 CARE AND USE OF SURVEYING EQUIPMENT .....</b>	<b>1</b>
<b>3.03 MAINTENANCE AND LUBRICATION OF SURVEYING INSTRUMENTS .....</b>	<b>2</b>
<b>3.04 SURVEYS FOR EARTHWORK .....</b>	<b>2</b>
3.04.01 GENERAL .....	2
3.04.02 CHECKING GRADE .....	2
3.04.03 STAKES .....	4
3.04.04 FIELD NOTES .....	4
3.04.05 ELECTRONIC FIELD NOTES .....	6
3.04.06 SIGNALS .....	7
3.04.07 CHECKING ALIGNMENT .....	8
3.04.08 RECOVERING CENTER LINE .....	8
3.04.09 STAKING CENTER LINE .....	10
3.04.10 CHECKING ANGLES .....	10
3.04.11 CHECKING THE DISTANCES .....	10
3.04.12 REESTABLISHING THE CENTER LINE REFERENCE AND CONTROL POINTS .....	10
3.04.13 STAKING HORIZONTAL CURVES .....	12
3.04.14 CURVE WITH SPIRAL TRANSITIONS .....	14
3.04.15 PRELIMINARY STAKING OF RIGHT-OF-WAY .....	18
3.04.16 LAND MONUMENTS .....	18
<b>3.05 BENCH MARKS .....</b>	<b>22</b>
3.05.01 SETTING NEW BENCH MARKS .....	22
3.05.02 BENCH MARKS AS TURNING POINTS .....	22
3.05.03 EQUALIZING SIGHTS .....	22
3.05.04 DIFFERENCE BETWEEN BENCH MARK ELEVATIONS TO BE COMPARED IN CHECKING .....	22
3.05.05 ALLOWABLE VARIATION .....	23
3.05.06 NOTES .....	23
3.05.07 ADJUSTMENT OF BENCH MARK ELEVATIONS .....	24
3.05.08 GOVERNMENT BENCH MARKS .....	25
<b>3.06 CROSS SECTIONS .....</b>	<b>26</b>
3.06.01 ORIGINAL CROSS SECTIONS .....	26
3.06.02 ROADWAY CROSS SECTIONS .....	26
3.06.03 NOTES .....	28
3.06.04 BORROW AREAS .....	29
3.06.05 CHANNEL CHANGES .....	29
3.06.06 PLOTTING CROSS SECTIONS .....	31

**TABLE OF CONTENTS**  
**PART III (Continued)**

SECTION NO.	PAGE
<b>3.07 SLOPE STAKES AND GRADE STAKES.....</b>	<b>32</b>
3.07.01 GENERAL .....	32
3.07.02 SLOPE STAKES.....	33
3.07.03 OFFICE PREPARATION OF NOTES .....	33
3.07.04 NOTES FOR STEEP SIDEHILL SECTIONS .....	34
<b>3.08 GRADE STAKES .....</b>	<b>34</b>
3.08.01 GENERAL .....	34
3.08.02 FIELD NOTES FOR SLOPE STAKES AND GRADE STAKES .....	36
<b>3.09 FINISHING STAKES .....</b>	<b>43</b>
3.09.01 FINISHING STAKES.....	43
3.09.02 FINISHING STAKE NOTES .....	44
3.09.03 OFFICE PREPARATION OF NOTES .....	45
<b>3.10 FINAL CROSS SECTIONS AND COMPUTATIONS.....</b>	<b>45</b>
3.10.01 GENERAL .....	45
3.10.02 FIELD NOTES.....	46
3.10.03 DETERMINATION OF END AREAS .....	49
3.10.04 COMPUTATIONS .....	53
<b>3.11 MISCELLANEOUS NOTES AND STAKING.....</b>	<b>53</b>
3.11.01 STAKES FOR GUARD FENCE AND GUIDEPOSTS .....	53
3.11.02 RIGHT-OF-WAY MONUMENTS.....	54
<b>3.12 HORIZONTAL &amp; VERTICAL CONTROL FOR CONSTRUCTION PROJECTS ..</b>	<b>54</b>
<b>3.13 SURVEYS FOR BITUMINOUS OVERLAYS &amp; REFERENCE STRING LINES....</b>	<b>55</b>
<b>3.14 FENCING .....</b>	<b>55</b>
<b>3.15 SIGNING AND DELINEATION .....</b>	<b>56</b>
<b>3.16 CONTROL FOR AERIAL PHOTOGRAPHY.....</b>	<b>56</b>
<b>3.17 ROADSIDE IMPROVEMENTS .....</b>	<b>56</b>
<b>3.18 ELECTRIC LIGHTING .....</b>	<b>56</b>
<b>3.19 EROSION CONTROL.....</b>	<b>56</b>
<b>3.20 SEEDING.....</b>	<b>57</b>
<b>3.21 TERRACES.....</b>	<b>57</b>
<b>3.22 HIGH WATER MARKS.....</b>	<b>57</b>
<b>3.23 SURVEYS FOR STRUCTURES.....</b>	<b>59</b>
3.23.01 GENERAL .....	59
3.23.02 ALIGNMENT AND STATIONING .....	61
3.23.03 TURNING ANGLES FOR PIERS AND ABUTMENTS .....	61
3.23.04 TRIANGULATION .....	62
3.23.05 ELEVATIONS .....	64
3.23.06 STAKES .....	64
3.23.07 CROSS SECTIONS FOR BRIDGES AND CULVERTS .....	65
3.23.08 NOTES.....	66
3.23.09 SURVEY FOR STRUCTURES ON SECONDARY PROJECTS .....	67

**TABLE OF CONTENTS**  
**PART III**

SECTION NO.	PAGE
<b>3.24 SURVEYS FOR PAVEMENTS .....</b>	<b>67</b>
3.24.01 GENERAL .....	67
3.24.02 STAKING FOR SUBGRADE CONTROL .....	68
3.24.03 PAVING GRADE AND LINE STAKES .....	68
3.24.04 STAKING FOR GUTTERS .....	68
3.24.05 OFF-SETTING STAKES FROM ALIGNMENT TANGENT .....	69
3.24.06 OFF-SETTING ON HORIZONTAL CURVES .....	69
3.24.07 NOTES .....	69
<b>3.25 COMPLETED CONSTRUCTION PLANS .....</b>	<b>69</b>
3.25.01 GENERAL .....	69
3.25.02 LAND MONUMENTS .....	69
3.25.03 PROJECT CONTROL .....	69
3.25.04 BENCH MARKS .....	69

**INDEX TO FIGURES**

FIGURE NO.	PAGE
III-1 VERTICAL CURVES .....	3
III-2 CONSTRUCTION STAKES .....	4
III-3 ALIGNMENT NOTES .....	9
III-4 INTRADOS-EXTRADOS .....	13
III-5 HORIZONTAL CURVE .....	14
III-6 SPIRAL CURVE .....	16
III-7A & 7B LAND SURVEY REFERENCE REPORT .....	20
III-8 BENCH MARK LEVELS .....	24
III-9 ADJUSTMENT OF BENCH MARK ELEVATIONS .....	25
III-10 GRADE STAKES, SLOPE STAKES AND ORIGINAL CROSS SECTIONS .....	30
III-11 SLOPE STAKES AND GRADE CONTROL STAKES .....	37
III-12 ALLOWANCE FOR SETTLEMENT OF EARTHWORK .....	40
III-13A END AREA QUANTITIES .....	41
III-13B EARTHWORK TABULATIONS .....	42
III-14 FINISH GRADE STAKING NOTES .....	45
III-15 LAYER CROSS SECTIONS .....	47
III-16 BORROW PIT .....	49
III-17 CRISSCROSS METHODS FOR DETERMINING THE AREA OF ANY PRISM .....	50
III-18 KANSAS WATER OFFICE - HIGHWATER MARKS .....	58
III-19 EXAMPLE-CULVERT STAKING .....	59
III-20 EXAMPLE-MULTIPLE BOX BRIDGE STAKING .....	60
III-21 BRIDGE CONSTRUCTION STAKING DIAGRAM .....	63
III-22 CULVERT STAKING NOTES .....	67
III-23 ADDITIONAL REFERENCES .....	70
III-24 CONVERSION FACTORS .....	71
III-25 SURFACES AND VOLUMES OF SOLIDS .....	74
III-26 CENTERS OF GRAVITY OR ORDINARY PLANE FIGURES .....	77
III-27 TRIGONOMETRIC FUNCTIONS .....	79

**TABLE OF CONTENTS**  
**PART IV**

SECTION NO.	PAGE
<b>4.00 CONSTRUCTION INSPECTION .....</b>	<b>1</b>
<b>4.01 CLEARING AND GRUBBING.....</b>	<b>1</b>
4.01.01 GENERAL.....	1
4.01.02 CHECK LIST FOR CLEARING AND GRUBBING.....	2
<b>4.02 GRADING - EXCAVATION AND EMBANKMENT .....</b>	<b>2</b>
4.02.01 GENERAL.....	2
4.02.02 EMBANKMENTS .....	4
4.02.03 GRADE POINTS .....	5
4.02.04 COMPACTION AT STRUCTURES .....	5
4.02.05 ROCK EMBANKMENTS .....	6
4.02.06 SURPLUS MATERIAL .....	6
4.02.07 MOISTURE CONTROL .....	6
4.02.08 PRE-WATERING .....	7
4.02.09 EXCAVATION .....	7
4.02.10 ROCK EXCAVATION .....	8
4.02.11 CLASSIFICATION .....	9
4.02.12 FINISH GRADING .....	9
4.02.13 GRADING RECORDS.....	10
4.02.14 CHECK LIST FOR GRADING.....	11
<b>4.03 STRUCTURES.....</b>	<b>12</b>
4.03.01 GENERAL.....	12
4.03.02 LOCATION.....	12
4.03.03 INSPECTION .....	13
4.03.04 SAFETY .....	14
4.03.05 EXCAVATION .....	14
4.03.06 COFFERDAMS.....	15
4.03.07 CULVERT FOUNDATION.....	17
4.03.08 BEARING PILES .....	17
4.03.09 DRILLED SHAFTS .....	23
4.03.10 SUPERSTRUCTURES .....	24
4.03.11 BRIDGE DECK WEARING SURFACE .....	25
<b>4.04 PORTLAND CEMENT CONCRETE PAVEMENT .....</b>	<b>26</b>
4.04.01 GENERAL.....	26
4.04.02 CONCRETE PAVEMENT METHODS.....	26
4.04.03 ORGANIZATION OF PORTLAND CEMENT CONCRETE .....	26
PAVEMENT PROJECT .....	26
4.04.04 DUTIES AND RESPONSIBILITIES OF THE PROJECT ENGINEER .....	27
OR PROJECT MANAGER .....	27
4.04.05 DUTIES AND RESPONSIBILITIES OF THE SURVEY PARTY CHIEF .....	27
4.04.06 DUTIES AND RESPONSIBILITIES OF THE CONCRETE PLANT INSPECTOR .....	28
4.04.07 DUTIES AND RESPONSIBILITIES OF THE SLAB INSPECTOR.....	33
4.04.08 CORING PORTLAND CEMENT CONCRETE PAVEMENT OR BASE COURSE .....	51

**TABLE OF CONTENTS**  
**PART IV (Continued)**

SECTION NO.	PAGE
<b>4.05 BITUMINOUS SURFACE .....</b>	<b>52</b>
4.05.01 GENERAL.....	52
4.05.02 MATERIALS .....	52
4.05.03 DESIGN.....	52
4.05.04 PRE-CONSTRUCTION CONFERENCES.....	53
4.05.05 CONVENTIONAL SEALING.....	54
4.05.06 BITUMINOUS PRIME COAT .....	62
4.05.07 SLURRY SEALING.....	63
4.05.08 MODIFIED SLURRY SEAL .....	68
4.05.09 COLD RECYCLED BITUMINOUS CONSTRUCTION .....	69
<b>4.06 BASE COURSES AND SUB-BASES.....</b>	<b>72</b>
4.06.01 GENERAL.....	72
4.06.02 EQUIPMENT .....	72
4.06.03 MATERIALS .....	72
4.06.04 SUBGRADE PREPARATION .....	73
4.06.05 PRODUCTION AND DELIVERY OF MATERIAL.....	73
4.06.06 ROAD MIXING METHODS .....	73
4.06.07 TRAVELING PLANT MIX METHODS .....	75
4.06.08 CENTRAL PLANT MIX METHODS .....	76
4.06.09 AERATION.....	76
4.06.10 LAYING AND COMPACTING .....	76
4.06.11 CURING AND MAINTENANCE .....	77
4.06.12 SHOULDERs, ENTRANCES AND SIDEROADS.....	77
<b>4.07 LIGHT TYPE SURFACING .....</b>	<b>78</b>
4.07.01 GENERAL.....	78
4.07.02 EQUIPMENT .....	78
4.07.03 CONSTRUCTION PROCEDURES.....	78
<b>4.08 ROADSIDE IMPROVEMENT .....</b>	<b>78</b>
4.08.01 GENERAL.....	78
4.08.02 DELIVERY OF PLANT MATERIALS .....	78
4.08.03 WORK PREPARATORY TO PLANTING.....	79
4.08.04 PLANTING TREES, SHRUBS AND VINES .....	79
4.08.05 PLANTING SODS AND SEEDS.....	80
4.08.06 MULCH.....	80
4.08.07 PARK STRUCTURES .....	81
4.08.08 ACCEPTING MATERIALS .....	81

**INDEX TO FIGURES**

FIGURE NO.	PAGE
FIGURE IV-1 MEASUREMENTS FOR CHECKING UNIFORM PAVEMENT .....	34
FIGURE IV-2 METHOD OF SQUARING BASKETS .....	38
FIGURE IV-3 PAVEMENT STATIONING.....	48
FIGURE IV-4 BITUMINOUS SEALING DESIGN.....	56
FIGURE IV-5 ASPHALT DISTRIBUTOR DATA .....	61

## TABLE OF CONTENTS

### PART V

<u>SECTION</u>		<u>PAGE</u>	
5.00	MATERIALS CONTROL	Rev 8/03	5.01-1
<b>5.01</b>	<b>GENERAL</b>	<b>Rev 8/03</b>	<b>5.01-1</b>
5.01.01	Organization and Functions of the Bureau of Materials and Research		5.01-1
5.01.02	Reasons for Quality Control/Quality Assurance (QC/QA)		5.01-1
5.01.03	Procedures for Quality Assurance		5.01-3
5.01.04	Quality Control/Quality Assurance (QC/QA) Tests		5.01-5
<b>5.02</b>	<b>AGGREGATES</b>	<b>Rev 8/05</b>	<b>5.02-1</b>
5.02.01	General		5.02-1
5.02.02	Types of Production		5.02-1
5.02.03	Inspection Responsibilities		5.02-1
5.02.04	Approval of Deposits		5.02-1
5.02.05	Inspection, Sampling and Testing		5.02-3
<b>5.03</b>	<b>ASPHALT MATERIAL</b>	<b>Rev 8/05</b>	<b>5.03-1</b>
5.03.01	General		5.03-1
5.03.02	Basis of Acceptance		5.03-1
5.03.03	Sampling Procedures		5.03-2
5.03.04	Responsibilities of the Resident Inspector		5.03-2
5.03.05	Asphalt Sampling Frequency		5.03-3
5.03.06	Testing Performed for each Sampling Frequency Level		5.03-3
<b>5.04</b>	<b>BRICK AND CONCRETE MASONRY UNITS</b>	<b>Rev 2/98</b>	<b>5.04-1</b>
5.04.01	General		5.04-1
5.04.02	Basis of Acceptance		5.04-1
5.04.03	Methods of Inspection		5.04-1

## TABLE OF CONTENTS-PART V (CONTINUED)

<u>Section</u>		<u>Page</u>	
<b>5.05</b>	<b>CONCRETE CURING MATERIALS</b>	Rev 1/00	<b>5.05-1</b>
5.05.01	General		5.05-1
5.05.02	Burlap		5.05-1
5.05.03	Liquid Membrane Forming Compounds		5.05-1
5.05.04	White Polyethylene Sheeting		5.05-1
5.05.05	Concrete Curing Blanket		5.05-2
<b>5.06</b>	<b>JOINT SEALING AND JOINT FILLER MATERIALS</b>	Rev 8/05	<b>5.06-1</b>
5.06.01	General		5.06-1
5.06.02	Hot Type Joint Sealing Compound		5.06-1
5.06.03	Cold Applied, Chemically Cured Joint Sealing Compound		5.06-1
5.06.04	Preformed Expansion Joint Filler for Concrete		5.06-2
5.06.05	Preformed Elastomeric Compression Joint Seals for Concrete		5.06-2
5.06.06	Materials for Filling and Sealing Joints in Pipe		5.06-2
<b>5.07</b>	<b>MISCELLANEOUS MATERIALS</b>	Rev 8/05	<b>5.07-1</b>
5.07.01	General		5.07-1
5.07.02	Admixtures for Portland Cement Concrete		5.07-1
5.07.03	Calcium Chloride		5.07-2
5.07.04	Reflective Sheeting		5.07-2
5.07.05	Electric Lighting and Traffic Signal Equipment		5.07-3
5.07.06	Center Mount Reflectors		5.07-4
5.07.07	Bearing Pads or Mats for Structures		5.07-4
5.07.08	Permanent Signs		5.07-5
<b>5.08</b>	<b>MISCELLANEOUS METALS</b>	Rev 2/98	<b>5.08-1</b>
5.08.01	General		5.08-1
5.08.02	Aluminum Alloys and Cast Aluminum		5.08-1
5.08.03	Galvanized Coating of Accessories for Flapgates and Flood Gates		5.08-2
5.08.04	Sheet Metal for Signs		5.08-2

**TABLE OF CONTENTS-PART V (CONTINUED)**

<u>Section</u>		<u>Page</u>	
<b>5.09</b>	BRIDGE PAINTS AND PAVEMENT MARKING MATERIALS	Rev 8/05	5.09-1
5.09.01	General	5.09-1	
5.09.02	Types of Packaging	5.09-1	
5.09.03	Basis of Acceptance	5.09-1	
5.09.04	Methods of Inspection and Sampling	5.09-2	
<b>5.10</b>	CULVERT, SEWER AND UNDERDRAIN PIPE	Rev 8/05	5.10-1
5.10.01	General	5.10-1	
5.10.02	Reinforced Concrete Pipe	5.10-1	
5.10.03	Clay Pipe	5.10-1	
5.10.04	Cast Iron Pipe	5.10-2	
5.10.05	Corrugated Metal Pipe, Pipe Arches and End Sections	5.10-2	
5.10.06	Structural Plate for Pipe, Pipe Arches and Arches	5.10-3	
5.10.07	Asphalt Coated Corrugated Metal Pipe, Pipe Arches, Coupling Bands and Structural Plate	5.10-4	
5.10.08	Corrugated Polyethylene Tubing for Underdrains	5.10-4	
5.10.09	Corrugated Polyethylene Pipe	5.10-4	
5.10.10	Polyvinyl Chloride (PVC) Pipe	5.10-5	
<b>5.11</b>	PORTLAND CEMENT AND LIME	Rev 8/05	5.11-1
5.11.01	General	5.11-1	
5.11.02	Portland Cement	5.11-1	
5.11.03	Hydrated Lime and Quicklime	5.11-10	
<b>5.12</b>	MATERIALS FOR ROADSIDE IMPROVEMENTS	Rev 2/98	5.12-1
5.12.01	General	5.12-1	
5.12.02	Plants	5.12-1	
5.12.03	Seeds	5.12-1	
5.12.04	Nitrogen Fixing Bacteria	5.12-3	
5.12.05	Agricultural Limestone	5.12-4	

## TABLE OF CONTENTS-PART V (CONTINUED)

<u>Section</u>			<u>Page</u>
5.12.06	Fertilizers		5.12-4
5.12.07	Summary of Inspection, Testing and Reporting Requirements		5.12-5
<b>5.13</b>	<b>STEEL AND IRON</b>	Rev 8/05	<b>5.13-1</b>
5.13.01	General		5.13-1
5.13.02	Reinforcing Steel		5.13-1
5.13.03	Welded Steel Wire Fabric		5.13-1
5.13.04	Structural Steel		5.13-1
5.13.05	Deep Beam Guard Rail and Fittings		5.13-2
5.13.06	Steel Shells for Cast-in-Place Concrete Piles		5.13-2
5.13.07	Miscellaneous Steel Products		5.13-3
5.13.08	Materials for Fencing		5.13-4
<b>5.14</b>	<b>TIMBER, LUMBER, PILING AND POSTS</b>	Rev 4/05	<b>5.14-1</b>
<b>5.15</b>	<b>WATER FOR USE WITH PORTLAND CEMENT</b>	Rev 2/98	<b>5.15-1</b>

## KT TABLE OF CONTENTS

<u>Section</u>			<u>Revision Date</u>
<b>5.16</b>	<b>SAMPLING AND TEST METHODS FOREWORD</b>		08-05
<b>5.16.01</b>	KT-1	Sampling Aggregates	08-05
<b>5.16.02</b>	KT-2	Sieve Analysis of Aggregates	08-05
<b>5.16.03</b>	KT-3	Material Passing 75 µm (No. 200) Sieve by the Wash Method	08-05
<b>5.16.04</b>	KT-4	Percent Retained on the 75 µm (No. 200) Sieve by Dry Screening	08-05
<b>5.16.05</b>	KT-5	Unit Weight of Aggregate	08-05

## TABLE OF CONTENTS-PART V (CONTINUED)

<u>Section</u>			<u>Revision Date</u>
<a href="#"><b>5.16.06</b></a>	KT-6	Specific Gravity and Absorption of Aggregate	08-05
<a href="#"><b>5.16.07</b></a>	KT-7	Clay Lumps and Friable Particles in Aggregate	08-05
<a href="#"><b>5.16.08</b></a>	KT-8	Shale or "Shalelike" Materials in Aggregate	08-05
<a href="#"><b>5.16.09</b></a>	KT-9	Soft or Friable Particles in Aggregate	Deleted-99
<a href="#"><b>5.16.10</b></a>	KT-10	Plasticity Test	08-05
<a href="#"><b>5.16.11</b></a>	KT-11	Moisture Test	08-05
<a href="#"><b>5.16.12</b></a>	KT-12	Standard Compaction Test	08-05
<a href="#"><b>5.16.13</b></a>	KT-13	Field Density Tests of Soils, Treated Base Courses, and Water Bound Base Courses	08-05
<a href="#"><b>5.16.14</b></a>	KT-14	Marshall Test of Bituminous Mixes	02-98
<a href="#"><b>5.16.15</b></a>	KT-15	Bulk Specific Gravity and Unit Weight of Compacted Asphalt Mixtures	08-05
<a href="#"><b>5.16.16</b></a>	KT-16	Volatile Distillate Content and Moisture Content of Bituminous Mixes	02-98
<a href="#"><b>5.16.17</b></a>	KT-17	Sampling Fresh Concrete	08-05
<a href="#"><b>5.16.18</b></a>	KT-18	Air Content of Freshly Mixed Concrete by the Pressure Method	08-03
<a href="#"><b>5.16.19</b></a>	KT-19	Air Content of Fresh Concrete by the Volumetric Method	01-00
<a href="#"><b>5.16.20</b></a>	KT-20	Mass per Cubic Meter (Foot), Yield Cement Factor and Air Content (Gravimetric) of Fresh Concrete	02-02
<a href="#"><b>5.16.21</b></a>	KT-21	Slump of Portland Cement Concrete	01-00

**TABLE OF CONTENTS-PART V (CONTINUED)**

<u>Section</u>			<u>Revision Date</u>
<a href="#"><b>5.16.22</b></a>	KT-22	Making and Curing Compression and Flexural Test Specimens in the Field	01-00
<a href="#"><b>5.16.23</b></a>	KT-23	Flexural Strength of Concrete (Third Point Loading Method)	02-02
<a href="#"><b>5.16.24</b></a>	KT-24	Determination of Free Moisture or Absorption of Aggregate for Use in Concrete	08-05
<a href="#"><b>5.16.25</b></a>	KT-25	Sampling and Splitting Plant Mixed Asphalt Mixtures	08-05
<a href="#"><b>5.16.26</b></a>	KT-26	Sampling Asphalt Materials	08-05
<a href="#"><b>5.16.27</b></a>	KT-27	Sampling Joint Compound Materials	08-05
<a href="#"><b>5.16.28</b></a>	KT-28	Sampling Paint Materials and Mixed Paints	08-05
<a href="#"><b>5.16.29</b></a>	KT-29	Field Sampling of Portland Cement, Lime and Fly Ash	08-05
<a href="#"><b>5.16.30</b></a>	KT-30	Field Sampling of Thermoplastic Pavement Marking Material	01-99
<a href="#"><b>5.16.31</b></a>	KT-31	Determination of Percentage of Crushed Particles in Crushed Gravel	08-05
<a href="#"><b>5.16.32</b></a>	KT-32	Method of Test for Density of Compacted Asphalt Mixtures by Nuclear Method	08-05
<a href="#"><b>5.16.33</b></a>	KT-33	Bitumen Content of Paving Mixtures by Reflux Extraction	02-98
<a href="#"><b>5.16.34</b></a>	KT-34	Sieve Analysis of Extracted Aggregate	08-05
<a href="#"><b>5.16.35</b></a>	KT-35	Sticks in Aggregate	08-05
<a href="#"><b>5.16.36</b></a>	KT-36	Density of Fresh Concrete in Bridge Deck Overlays by Nuclear Gauge	02-02

**TABLE OF CONTENTS-PART V (CONTINUED)**

<u>Section</u>			<u>Revision Date</u>
<a href="#"><b>5.16.37</b></a>	KT-37	Making, Curing, and Testing Cement Treated and Unbound Bases in the Laboratory	08-05
<a href="#"><b>5.16.38</b></a>	KT-38	Density of Fresh Concrete in Pavement by Nuclear Gauge	02-02
<a href="#"><b>5.16.39</b></a>	KT-39	Theoretical Maximum Specific Gravity of Asphalt Paving Mixtures	08-05
<a href="#"><b>5.16.40</b></a>	KT-40	Bitumen Content of Paving Mixtures by the Nuclear Asphalt Content (AC) Gauge	Deleted-03
<a href="#"><b>5.16.41</b></a>	KT-41	Determination of Density and Moisture Content of Portland Cement Treated Bases by Nuclear Method	08-05
<a href="#"><b>5.16.42</b></a>	KT-42	Sieve Analysis for Acceptance of Lime or Cement Treated Soils	08-03
<a href="#"><b>5.16.43</b></a>	KT-43	Moisture Content of Asphalt Mixtures or Mineral Aggregates - Microwave Oven Method	08-05
<a href="#"><b>5.16.44</b></a>	KT-44	Method of Testing the Strength of Portland Cement Concrete Using the Maturity Method	08-03
<a href="#"><b>5.16.45</b></a>	KT-45	Determination of Dry Paint Film Thickness with the Magnetic Gauge	08-05
<a href="#"><b>5.16.46</b></a>	KT-46	Determination of Pavement Profile with the Profilograph	02-98
<a href="#"><b>5.16.47</b></a>	KT-47	Determination of Hot-in-Place Recycled Asphalt Pavement (HIPR)	08-05
<a href="#"><b>5.16.48</b></a>	KT-48	Determination of the Density of Portland Cement Treated Base (Field Molded)	Deleted-03
<a href="#"><b>5.16.49</b></a>	KT-49	Method For Obtaining and Testing Drilled Cores	08-05
<a href="#"><b>5.16.50</b></a>	KT-50	Uncompacted Void Content of Fine Aggregate	08-05

**TABLE OF CONTENTS-PART V (CONTINUED)**

<u>Section</u>		<u>Revision Date</u>
<a href="#"><b>5.16.51</b></a>	KT-51      Field Density and Moisture Tests of Soils By Nuclear Gauge	02-02
<a href="#"><b>5.16.52</b></a>	KT-52      Field Density and Moisture Tests of Soils by Nuclear Gauge - TROXLER 3440	Deleted 02
<a href="#"><b>5.16.53</b></a>	KT-53      Compaction and Shear Properties of Bituminous Mixtures by Means of the Gyratory Testing Machine (GTM)	Deleted 05
<a href="#"><b>5.16.54</b></a>	KT-54      Determination of Pavement Profile with the Profilograph - "Metric Version"	02-98
<a href="#"><b>5.16.55</b></a>	KT-55      Plastic Fines in Combined Aggregates by use of the Sand Equivalent Test	08-05
<a href="#"><b>5.16.56</b></a>	KT-56      Resistance of Compacted Asphalt Mixture to Moisture Induced Damage	08-05
<a href="#"><b>5.16.57</b></a>	KT-57      Determination of Asphalt Content and Gradation of Hot Mix Asphalt Concrete by the Ignition Method	08-05
<a href="#"><b>5.16.58</b></a>	KT-58      Method for Preparing and Determining the Density of Hot Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor	08-05
<a href="#"><b>5.16.59</b></a>	KT-59      Flat and Elongated Particles in Coarse Material Test	08-05
<a href="#"><b>5.16.60</b></a>	KT-60      Indirect Tensile Test	08-03
<a href="#"><b>5.16.61</b></a>	KT-61      Raveling Test on Recycled Asphalt Specimens	08-03
<a href="#"><b>5.16.62</b></a>	KT-62      Percent Solids of Lime Slurry	08-03
<a href="#"><b>5.16.63</b></a>	KT-63      Method for Determining Draindown Characteristics In Uncompacted Asphalt Mixtures	08-05

**TABLE OF CONTENTS-PART V (CONTINUED)**

<u>Section</u>			<u>Revision Date</u>
<a href="#"><b>5.16.64</b></a>	KT-64	Method for Determining Volume of Voids in Compacted Filler or Fines	08-05
<a href="#"><b>5.16.65</b></a>	KT-65	Sampling and Splitting Cement Treated Base Mixtures	08-05
<a href="#"><b>5.16.66</b></a>	KT-66	Sampling Epoxy Pavement Marking	08-05
<a href="#"><b>5.16.67</b></a>	KT-67	Sampling Glass Beads	08-05
<a href="#"><b>5.16.68</b></a>	KT-68	Sampling Traffic Paint	08-05
<u>Section</u>			<u>Page</u>
5.17	CALCULATIONS		5.17.01-1
<a href="#"><b>5.17.01</b></a>	Absolute Volume and Percent of Voids in a Unit Volume of Aggregate	Rev 8/05	5.17.01-1
<a href="#"><b>5.17.02</b></a>	Theoretical Specific Gravity of a Combination of Aggregates	Rev 8/05	5.17.02-1
<a href="#"><b>5.17.03</b></a>	Volume of Asphalt Materials	Rev 8/05	5.17.03-1
<a href="#"><b>5.17.04</b></a>	Calculations for the Marshall Mix Design of Bituminous Mixtures	Rev 1/00	5.17.04-1
<a href="#"><b>5.17.05</b></a>	Rounding-Off of Numbers	Rev 8/03	5.17.05-1
<a href="#"><b>5.17.06</b></a>	Using Random Numbers	Rev 8/03	5.17.06-1
<a href="#"><b>5.17.07</b></a>	Fineness Modulus of Aggregates (Gradation Factor)	Rev 8/05	5.17.07-1
<a href="#"><b>5.17.08</b></a>	Comparison of Quality Control and Verification Tests	Rev 02/02	5.17.08-1
<a href="#"><b>5.17.09</b></a>	Statistics	Rev 8/05	5.17.09-1
<a href="#"><b>5.17.10</b></a>	Contractor's Quality Control Plan	Rev 8/05	5.17.10-1

## TABLE OF CONTENTS-PART V (CONTINUED)

<u>Section</u>		<u>Page</u>	
	<b>5.17.10.01</b> HMA: Contractor's Quality Control Plan	Rev 8/05	<b>5.17.10.01-1</b>
	<b>5.17.10.01.A</b> Appendix A	Rev 8/05	
	<b>5.17.10.01.B</b> Appendix B	Rev 8/05	
	<b>5.17.10.02</b> Concrete: Contractor's Quality Control Plan	Rev 8/03	<b>5.17.10.02-1</b>
	<b>5.17.10.02.A</b> Appendix A	Rev 1/00	
	<b>5.17.10.03</b> Concrete Structures: Contractor's Quality Control plan	Rev 8/03	<b>5.17.10.03-1</b>
<b>5.18</b>	<b>MIX DESIGN METHODS</b>		<b>5.18.01-1</b>
	<b>5.18.01</b> Concrete Mix Design	Rev 8/03	<b>5.18.01-1</b>
	<b>5.18.02</b> Bituminous Mix Design	Rev 8/05	<b>5.18.02-1</b>
	<b>5.18.03</b> Superpave Mix Design	Rev 2/98	<b>5.18.03-1</b>
	<b>5.18.04</b> Mix Design Procedures for CIR (Cold in Place Recycling) Material	Rev 8/05	<b>5.18.04-1</b>
<b>5.19</b>	<b>SAMPLING AND TESTING REQUIREMENTS</b>	Rev 8/05	<b>5.19-1</b>
	<b>5.19.01</b> Project Sampling and Testing Frequencies		<b>5.19-1</b>
	<b>5.19.02</b> Required Sample Sizes		<b>5.19-1</b>
<b>5.20</b>	<b>LABORATORY AND SAMPLE</b>	Rev 8/05	<b>5.20-1</b>
	<b>5.20.01</b> Laboratory Identification		<b>5.20-1</b>
	<b>5.20.02</b> Sample Identification		<b>5.20-1</b>
	<b>5.20.03</b> Sample Identification Forms		<b>5.20-3</b>

## TABLE OF CONTENTS-PART V (CONTINUED)

<u>Section</u>			<u>Page</u>
<a href="#">5.21</a>	NUCLEAR GAUGE	Rev 8/03	5.21-1
<a href="#">5.21.01</a>	1.13.2 SOM		5.21.01-1
	RADIOLOGICAL SAFETY GUIDELINES		
<a href="#">5.21.02</a>	Independent Assurance Replicate (ASR) Check for Nuclear Gauges	Rev 8/05	5.21.02-1
<a href="#">5.21.03</a>	Segregation Check Using the Nuclear Density Gauge	Rev 8/03	5.21.03-1
<a href="#">5.21.04</a>	Joint Density Evaluation Using the Nuclear Density Gauge	Rev 8/05	5.21.04-1
<a href="#">Appendix A</a>	Sampling and Testing Frequency Chart	Rev 8/05	A-1
<a href="#">Appendix B</a>	Construction using Quality Control/Quality  Assurance Specification Sampling and Testing Frequency Chart	Rev 8/05	B-1
<a href="#">Appendix C</a>	Specification for Independent Assurance Program	Rev 8/05	C-1