

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
601.21 Gabions, Galvanized	cubic meter [Cubic Yard]
601.211 Gabions, Galvanized and Hand Filled	cubic meter [Cubic Yard]
601.22 Gabions, PVC Coated	cubic meter [Cubic Yard]
601.221 Gabions, PVC Coated and Hand Filled Yard]	cubic meter [Cubic
601.23 Mattresses, Galvanized: _____	cubic meter [Cubic Yard]
601.24 Mattresses, PVC Coated: _____	cubic meter [Cubic Yard]

SECTION 602 - PIPE LINING

Reserved

SECTION 603 - PIPE CULVERTS AND STORM DRAINS

603.01 Description This work shall consist of constructing or reconstructing pipe culverts and storm drains, in accordance with these specifications, the Standard Detail plans and in reasonably close conformity with the lines and grades shown on the plans or established.

The word "pipe" in these specifications shall include both round pipe and pipe arches..

603.02 Materials Meet Sections:

Joint Mortar	705.02
Flexible Gaskets	705.03
Flexible Culvert Polyvinylchloride (PVC) Pipe	706.08
Corrugated Steel, Metallic Coated Pipe	707.02
Fiber-bonded Corrugated Steel Pipe & Pipe Arches	707.04
Corrugated Aluminum Alloy Pipe & Pipe Arches	707.06
Polymer Precoated, Galvanized Corrugated Steel	707.07