

The final payment of the remaining ¼ shall be made upon completion of the work.

Testing facilities, bituminous liquids and Portland cement, will not be paid for directly but all costs will be considered incidental to the various contract items.

Payment will be made under:

| <u>Pay Item</u> | <u>Pay Unit</u> |
|-----------------------------------|-----------------|
| 639.18 Field Office, Type A | Each |
| 639.19 Field Office, Type B | Each |
| 639.21 Testing Facilities - Soils | Lump Sum |

SECTION 640 - VACANT

SECTION 641 - REST AREA FACILITIES

Reserved

SECTION 642 - STEPS

642.01 Description This work shall consist of the construction of wooden steps, precast concrete steps or cast-in-place concrete steps in accordance with these specifications and in reasonably close conformity with dimensions and designs shown on the plans.

642.02 Materials Materials for the steps shall meet the requirements as specified in the following Sections of Division 700 - Materials:

| | |
|----------------------------|--------|
| Exterior Ready Mixed Paint | 708.01 |
| Timber Preservative | 708.05 |
| Precast Concrete Units | 712.06 |

Wood shall be well-seasoned spruce or pine, Number 1 dimension lumber. Nails and