

Payment will be made under:

| <u>Pay Item</u> | <u>Pay Unit</u> |
|--------------------------------------|-----------------|
| 643.60 Flashing Beacon at: | Lump Sum |
| 643.71 Traffic Signal Modification: | Lump |
| Sum | |
| 643.72 Temporary Traffic Signal: | Lump |
| Sum | |
| 643.80 Traffic Signals at: __ | Lump Sum |
| 643.81 Traffic Signal Control System | Lump Sum |
| 643.83 Video Detection System | Lump Sum |
| 643.86 Traffic Signal Loop Detector | Each |
| 643.90 Interconnect Wire Between: | Lump Sum |
| 643.91 Mast Arm Pole | Each |
| 643.92 Pedestal Pole | Each |
| 643.93 Strain Pole | Each |
| 643.94 Dual Purpose Pole | Each |

SECTION 644 - GLARE BARRIER

Reserved

SECTION 645 - HIGHWAY SIGNING

645.01 Description This work shall consist of furnishing and installing new signs, sign supports, delineators, and breakaway devices and removing, relocating and/or modifying existing signs and sign supports, in accordance with these specifications and in reasonably close conformity with the plans.

645.02 General All equipment shall be new unless otherwise specified. Requests for substitution of any specified material shall be submitted in writing with all documentation (specifications, mill certifications, etc.) in order to enable the Department to evaluate the proposal. Substitutes for specified material may be accepted, upon approval of the Fabrication Engineer. Substitutes shall give equal or better service than the specified