

aggregate, hauling, placing, compacting, removal and disposal, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.

**SECTION 106 — HOT MIX ASPHALT (HMA)
FOR MAINTENANCE OF TRAFFIC**

106.01 DESCRIPTION. This work shall consist of constructing HMA pavement for maintenance of traffic as specified in the Contract Documents or as directed by the Engineer.

106.02 MATERIALS.

Tack Coat (Rapid Setting)	904.03
HMA	904.04
Crack Filler	911.01 & 911.01.01
Production Plant	915

106.03 CONSTRUCTION. Refer to the applicable portions of 504.03.

106.04 MEASUREMENT AND PAYMENT. Hot Mix Asphalt for Maintenance of Traffic will be measured and paid for at the Contract unit price per ton. The payment will be full compensation for all tack coat, crack filler, hauling, placing, compacting, removal and disposal, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.

SECTION 107 — CONSTRUCTION STAKEOUT

107.01 DESCRIPTION. This work shall consist of furnishing, placing and maintaining construction layout stakes as specified in the Contract Documents or as directed by the Engineer.

The Contractor shall, as part of the construction stakeout operation, before any clearing operation commences, demarcate any wetlands and the limit of clearing throughout the entire project as shown in the Contract Documents and labeled as Limit of Clearing or Wetlands to the satisfaction of the Engineer.

Where limits of clearing are not shown in the Contract Documents, the limit of clearing will be the top of cut, toe of slope or limit of ditch excavation.