

**Intersection Utility Stakeout.** The Contractor shall notify the appropriate agencies listed below a minimum of 72 hours (excluding weekends and holidays) prior to the Contractor's anticipated beginning of any underground work.

- (a) Request a MISS UTILITY stakeout and possess a valid MISS UTILITY clearance ticket number for any underground work.
- (b) Contact all utilities within the limits of the project who are not a member of MISS UTILITY and obtain a stakeout of their respective facilities.
- (c) Request the Office of Traffic & Safety's Signal Operations Section to stakeout Administration maintained traffic signal facilities.
- (d) Request the District Engineer to stakeout their lighting facilities.

The Contractor shall stakeout the proposed construction as indicated in the Contract Documents and allow the Engineer to verify location of the proposed facilities.

**107.03.07 Right-of-Way and Easement Lines.** The Contractor shall define only right-of-way and easement lines of the project for adjacent property owners, promptly upon request.

**107.03.08 Subgrade, Subbase and Base Controls.** The Contractor shall furnish for subgrade, subbase and base courses, a string line and grade with fixed controls having a maximum longitudinal and transverse spacing of 25 ft.

The Contractor shall place along each form line for cement concrete pavement line and grade with fixed controls not to exceed 25 ft.

**107.03.09 Flagging.** The flagging shall be placed continuously through wetland areas. In areas where trees are not to be disturbed, the Contractor shall individually flag those trees in a line along the clearing limits that are not to be moved or destroyed. If the clearing or wetland flagging has been destroyed and the Engineer determines that its use is still required, the Contractor shall reflag the areas.

If the Contractor does not replace destroyed flagging within 48 hours after notification by the Engineer that replacement flagging is needed, the Engineer may proceed to have the area reflagged. The cost of the reflagging by the Engineer will be charged to the Contractor and deducted from any monies due under the Contract.

At the completion of construction, the Contractor shall remove all flagging.

**107.04 MEASUREMENT AND PAYMENT.** Construction Stakeout will not be measured but will be paid for at the Contract lump sum price. The payment will be full compensation for furnishing, placing and maintaining construction layout stakes, flagging of clearing limits and wetlands, and for all material, labor, equipment, tools, and incidentals necessary to complete the work. Payment of the Contract lump sum price will be prorated and paid in equal amounts on each monthly estimate. The number of months used for prorating will be the number estimated to complete the work.

## SECTION 108 — MOBILIZATION

**108.01 DESCRIPTION.** This work shall consist of the construction preparatory operations, including the movement of personnel and equipment to the project site and for the establishment of the Contractor's offices, buildings, and other facilities necessary to begin work.

**108.02 MATERIALS.** Not applicable.

**108.03 CONSTRUCTION.** All work performed in providing the facilities and services shall be done in a safe and workmanlike manner.

**108.04 MEASUREMENT AND PAYMENT.** Mobilization will not be measured but will be paid for at the Contract lump sum price. The cost of all required insurance and bonds will be incidental to the Mobilization item.

Payment of 50 percent of the Mobilization item will be made in the first monthly estimate after the Contractor has established the necessary facilities. The remaining 50 percent will be prorated and paid in equal amounts on each of the next five monthly estimates. The payment will be full compensation for all material, labor, equipment, tools, and incidentals necessary to complete the work.

Payment of the Mobilization item will not be made more than once, regardless of the fact that the Contractor may have, for any reason, shut the work down on the project, moved their equipment away from the project and then back again.

If an item for mobilization is not provided, the cost of mobilization including the required insurance and bonds will be incidental to the other items specified in the Contract Documents.