

CHANNEL OR STREAM CHANGE EXCAVATION (CLASS 5) 202

is believed the planned quantities are incorrect. When recomputation reveals an error, the corrected quantity will be used.

201.04.08 The excavated material or common borrow required to fill the temporary wedge area in conformance with 201.03.11, maintaining the 4:1 or flatter slope, compaction, and removal of the material will not be measured but the cost will be incidental to the Contract unit price for the pertinent Class of Excavation. For measurement and payment of Drums refer to 104.12.04.

201.04.09 Backfill for unsuitable material will be measured and paid for at the Contract unit price for the pertinent item specified in the Contract Documents.

SECTION 202 — CHANNEL OR STREAM CHANGE EXCAVATION (CLASS 5)

202.01 DESCRIPTION. This work shall consist of excavation for changes in streams and channels when specified in the Contract Documents. The Contractor shall use all suitable materials from excavation in the construction throughout the Contract.

202.02 MATERIALS. Not applicable.

202.03 CONSTRUCTION. Refer to the applicable provisions of Section 201.

202.04 MEASUREMENT AND PAYMENT. Class 5 Excavation will be measured and paid for at the Contract unit price per cubic yard. The payment will be full compensation for all excavation and hauling, formation and compaction of embankments and backfill, backfilling old stream beds or otherwise disposing of excess and unsuitable materials, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.

Material will be measured in its original position and the volume computed by the Method of Average End Area. The cross sectional area measured will not include liquids. Measurement for Class 5 Excavation excludes any material removed outside the limits of payment as specified in the Contract Documents.