

CATEGORY 300 DRAINAGE

SECTION 301 — CLASS 3 EXCAVATION FOR INCIDENTAL CONSTRUCTION

301.01 DESCRIPTION. This work shall consist of excavation below the planned elevation as specified in the Contract Documents or as directed by the Engineer.

301.02 MATERIALS. Not applicable.

301.03 CONSTRUCTION. The area to be excavated shall be the size, depth and location as authorized by the Engineer. Backfill shall conform to Section 302. Refer to 402.03.01 for excavated material.

301.04 MEASUREMENT AND PAYMENT. Class 3 Excavation for Incidental Construction will be measured and paid for at the Contract unit price per cubic yard. The payment will be full compensation for all material, labor, equipment, tools, and incidentals necessary to complete the work.

Backfill. Backfill will be measured and paid for as specified in 302.04.

SECTION 302 — SELECTED BACKFILL

302.01 DESCRIPTION. This work shall consist of placing selected backfill material as specified in the Contract Documents or as directed by the Engineer.

302.02 MATERIALS.

No. 57 Aggregate	901.01
Crusher Run Aggregate CR-6	901.01

302.03 CONSTRUCTION. Unsuitable foundation material shall be replaced as directed by the Engineer. Refer to Section 210 for compaction.

302.04 MEASUREMENT AND PAYMENT. Selected Backfill using No. 57 Aggregate or Selected Backfill using Crusher Run Aggregate CR-6 will be measured and paid for at the Contract unit price per cubic yard. The payment will be full compensation for compaction