

CATEGORY 600 SHOULDERS

SECTION 601 — EARTH SHOULDERS

601.01 DESCRIPTION. This work shall consist of constructing shoulders using earth as specified in the Contract Documents.

601.02 MATERIALS. Refer to Section 204.

601.03 CONSTRUCTION. Refer to 204.03 and 208.03.

601.04 MEASUREMENT AND PAYMENT. Earth shoulders will not be measured but the cost will be incidental to the Contract unit price for the pertinent Excavation item.

SECTION 602 — CURB, COMBINATION CURB AND GUTTER, AND MONOLITHIC MEDIAN

602.01 DESCRIPTION. This work shall consist of constructing concrete curb, concrete combination curb and gutter, concrete curb openings, concrete monolithic median, and hot mix asphalt (HMA) curb as specified in the Contract Documents or as directed by the Engineer.

602.02 MATERIALS.

Crusher Run Aggregate CR-6	901.01
Aggregate	901.01, Size No. 57
Curing Materials	902.07
Form Release Compound	902.08
Concrete Mix No. 2	902.10
Hot Mix Asphalt	904
Tack Coat	904.03
Reinforcement Steel	908.01
Joint Sealer	911.01
Preformed Joint Filler	911.02
Borrow Excavation	916.01