

**Recycled Composite Material.** Wheel stops manufactured of recycled composite material shall be as specified by the manufacturer and shall be insect resistant.

The manufacturer shall furnish certification as specified in TC-1.02.

**608.03 CONSTRUCTION.** Wheel stops shall be located and secured in place as specified in the Contract Documents. Only one type of wheel stop will be permitted for each project.

**608.04 MEASUREMENT AND PAYMENT.** Wheel Stops will be measured and paid for at the Contract unit price per each. The payment will be full compensation for all anchors, material, labor, equipment, tools, and incidentals necessary to complete the work.

**SECTION 609 — SHOULDER EDGE DROP OFF  
GRADING ADJUSTMENT**

**609.01 DESCRIPTION.** This work shall consist of constructing the area adjacent to the outside edge of the shoulder to eliminate the shoulder edge drop off.

**609.02 MATERIALS.**

Crusher Run Aggregate CR-6	901.01
Bank Run Gravel Subbase	901.01
Select Borrow	916.01.01
Common Borrow	916.01.04
Topsoil	920.01
Hot Mix Asphalt Millings or Grindings	Size of individual particles shall be less than 2 in. as determined visually.

**609.03 CONSTRUCTION.** When the outside edge of the shoulder exceeds 2-1/2 in. in height above the existing groundline, the wedge shaped area shall be filled and graded to a slope of 4:1 or flatter. The material shall be compacted as specified in the Contract Documents or as directed by the Engineer. The grading adjustment shall be completed by the end of the day that the drop off is created and prior to opening to traffic.

The material, lines and grades, and the cross section shall be as specified in the Contract Documents.

**609.04 MEASUREMENT AND PAYMENT.** Crusher Run Aggregate CR-6, Bank Run Gravel Subbase, Select Borrow, Common Borrow, Topsoil, and Hot Mix Asphalt Millings or Grindings for Shoulder Edge Drop Off will be measured and paid for at the Contract unit price per ton, cubic yard or square yard, as specified in the Contract Documents. The payment will be full compensation for furnishing, hauling, placing, compacting, maintaining, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.