

811.03.02 Pull and Junction Boxes. Conduit entrance shall be provided with conduit hubs or bosses of sufficient thickness that five full threads of the conduit shall engage the threaded holes in the box.

811.04 MEASUREMENT AND PAYMENT. Electrical Hand Holes, Manholes, and Pull and Junction Boxes will be measured and paid for at the Contract unit price per each unless otherwise specified in the Contract Documents. The payment will be full compensation for all excavation, aggregate drain, concrete, bolts, bricks, pipes, backfill, sealer, frames and covers, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.

SECTION 812 — WOOD SIGN SUPPORTS

812.01 DESCRIPTION. This work shall consist of furnishing and erecting wood sign supports as specified in the Contract Documents or as directed by the Engineer. Signs shall be as specified in Section 813.

812.02 MATERIALS. Wood supports shall be No. 1 dense grade.

Wood	921.05
Preservatives	921.06

812.03 CONSTRUCTION. Wood sign supports shall be placed in the ground in a plumb position to the depth and lateral orientation specified in the Contract Documents. Backfill shall consist of suitable excavation material compacted in place. Holes for embedding sign supports shall be augered or dug using methods approved by the Engineer. Driving or hammering wood sign supports into undisturbed earth is prohibited.

When specified in the Contract Documents, wood sign supports shall have drilled holes conforming to the breakaway requirements specified in AASHTO Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals, or as indicated in the Contract Documents.

812.04 MEASUREMENT AND PAYMENT. Wood Sign Supports will be measured and paid for at the Contract unit price per linear foot for the length and size specified in the Contract Documents. The payment will be full compensation for all excavation and backfill, drilled holes, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.