

compensation for the mounting hardware and for all material, labor, equipment, tools, and incidentals necessary to complete the work.

813.04.02 Administration furnished signs and mounting hardware will be measured and paid for at the Contract unit price per square foot for the completed sign installed. The payment will be full compensation for all transportation, drilling holes as specified, installation, and for all materials, labor, equipment, tools, and incidentals necessary to complete the work.

813.04.03 Clearing for signing will not be measured but the cost will be incidental to the Contract unit price for furnishing and installing the signs.

SECTION 814 — SIGNAL HEADS

814.01 DESCRIPTION. This work shall consist of furnishing and installing vehicle traffic control signal heads and pedestrian traffic control signal indications and mounting hardware as specified in the Contract Documents or as directed by the Engineer.

814.02 MATERIALS.

Traffic Signal Heads

950.15

814.03 CONSTRUCTION.

Aiming. Signal heads shall be aimed to be visible in conformance with the minimum requirements of the MUTCD.

814.04 MEASUREMENT AND PAYMENT. Aluminum, Polycarbonate, and Optically Programmed Signal Heads and Pedestrian Signal Indications furnished and installed will be measured and paid for at the Contract unit price per each section of signal head type and size as specified in the Contract Documents. The payment will be full compensation for all lens, mounting hardware, assembly, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.