

822.04.06 Concrete for sign foundation, galvanized steel beam sign posts, breakaway base support system for steel beams and wood sign supports for new sign supports, if required, will be paid for as specified in the applicable portions of Sections 801, 802, 812 and 821.

SECTION 823 — REMOVE AND RELOCATE OR REMOVE AND DISPOSE OF ROADWAY LIGHTING STRUCTURES

823.01 DESCRIPTION. This work shall consist of removing and relocating or removing and disposal of roadway lighting structures as specified in the Contract Documents or as directed by the Engineer.

823.02 MATERIALS.

Hardware	909.10
Conduit	921.07

823.03 CONSTRUCTION. Concrete foundations shall be removed as specified in 207.03.01. All holes caused by this removal shall be backfilled and compacted as approved by the Engineer. Lighting structures removed and not reused shall become the property of the Contractor. Lighting structures scheduled to be reused on the same project shall be removed and stored by the Contractor in conformance with GP-6.02.

All existing cable shall be made safe in conformance with the appropriate electrical codes and as directed by the Engineer.

823.04 MEASUREMENT AND PAYMENT. Remove and Dispose of Roadway Lighting will be measured and paid for at the Contract unit price per each. The payment will be full compensation for the removal and disposal of the lighting structure, removal of existing concrete foundation and all material, labor, equipment, tools, and incidentals to complete the work.

Remove and Relocate Roadway Lighting Structure will be measured and paid for at the Contract unit price per each. The payment will be full compensation for the removal, storage, reinstallation, connection to existing lighting circuits, removal of existing concrete foundations, and for all material, labor, equipment, tools, and incidentals necessary to complete the work.