

Section 209. PROJECT CLEANUP

209.01 Description. This work consists of the removal and disposal of all debris; including fences, fallen timber, logs, guardrail sections and posts, rocks, boulders, and all other rubbish from within the project limits according to sections 201 and 205.

209.02 Materials. None Specified.

209.03 Construction. Project cleanup will be an ongoing operation. Project cleanup shall apply to the area within the right-of-way but not in excess of 50 feet beyond the grading limits. All holes and ruts resulting from the construction operations shall be filled with approved material, compacted, leveled, and restored.

209.04 Measurement and Payment.

Contract Item (Pay Item)	Pay Unit
Project Cleanup	Lump Sum

Any existing culverts, sewers, or drainage structures that contain sediment or debris from the Contractor's operation will be cleaned out at the Contractor's expense.

Payment for **Project Cleanup** shall be paid upon completion of the Contractor's cleanup operation. If there is no contract item for **Project Cleanup**, payment for such work will be considered as having been included in the contract unit prices bid for other contract items.