

# DIVISION 100

## CONTRACT ADMINISTRATION & INSPECTION PROCEDURES

<b>101.00</b>	<b>CONSTRUCTION ORGANIZATION</b>	1
<b>101.01</b>	<b>PURPOSE OF MANUAL</b>	1
<b>101.02</b>	<b>ENGINEER'S DUTIES AND AUTHORITY</b>	1
Authority of the Director.....	1	1
General.....	1	1
Delegation of Authority .....	1	1
General .....	1	1
<b>101.03</b>	<b>CONSTRUCTION DIVISION</b> .....	2
<b>101.04</b>	<b>CHAIN OF COMMAND</b> .....	4
<b>101.05</b>	<b>CONSTRUCTION ENGINEER</b> .....	4
Interpretation of Specifications .....	4	4
<b>101.06</b>	<b>DISTRICT ENGINEER (DE)</b> .....	5
<b>101.07</b>	<b>DISTRICT CONSTRUCTION ENGINEER (DCE)</b> .....	5
<b>101.08</b>	<b>PROJECT MANAGER (PM)</b> .....	6
Delegation of Responsibility.....	7	7
<b>101.09</b>	<b>CONSTRUCTION TECHNICIAN (CT)</b> .....	7
<b>102.00</b>	<b>GENERAL RESPONSIBILITIES</b> .....	9
<b>102.01</b>	<b>PROMPT EXERCISE OF AUTHORITY</b> .....	9
<b>102.02</b>	<b>APPEALED DECISIONS</b> .....	9
<b>102.03</b>	<b>INTEGRITY OF EMPLOYEES</b> .....	10
Removing Materials from Projects.....	11	11
<b>102.04</b>	<b>PRESENCE ON SITE</b> .....	12
<b>102.05</b>	<b>PLANS AND WORKING DRAWINGS</b> .....	12
<b>102.06</b>	<b>PLAN ERRORS/OMISSIONS</b> .....	12
<b>102.07</b>	<b>ENGINEER RELATIONS</b> .....	13
<b>102.08</b>	<b>PUBLIC RELATIONSHIPS</b> .....	13
General Project Supervision .....	13	13
Residents Along Construction Projects .....	13	13
Services Relationships .....	13	13
News Media Relationships .....	14	14
Relations with Cities and Counties.....	14	14
<b>102.09</b>	<b>CONTRACTOR (PARTNERING) RELATIONSHIPS (SSHC Section 113)</b> .....	15
<b>102.10</b>	<b>FHWA &amp; OTHER OUTSIDE AGENCIES RELATIONSHIPS</b> .....	15
<b>102.11</b>	<b>EMPLOYMENT OF CONSULTANTS FOR CONSTRUCTION ENGINEERING AND INSPECTION</b> .....	16
Agreement Responsibilities.....	16	16
Project Manager.....	16	16
<b>102.12</b>	<b>PERSONNEL</b> .....	17
<b>102.13</b>	<b>EMPLOYEE POLICIES</b> .....	17
<b>102.14</b>	<b>STAFF REQUIREMENTS</b> .....	17
Field Estimates.....	17	17
Adjustments.....	17	17
Field Personnel Duties & Staff Requirements .....	17	17

102.15	SUBCONTRACTS .....	18
<b>Subcontract Request And Approval</b>	.....	<b>18</b>
Contractor's Requirements.....	.....	18
Project Manager Involvement.....	.....	19
Field Approval of Subcontract Work.....	.....	19
Exemptions from Subcontract Requirements .....	.....	20
102.16	DETOUR REPORT .....	24
102.17	CONTROL NUMBERS AND CONTRACT NUMBERS .....	24
102.18	PROJECT DOCUMENTS DISPOSITION .....	24
103.00	PRECONSTRUCTION.....	25
103.01	PRECONSTRUCTION CONFERENCE .....	25
103.02	ADMINISTRATION DETAILS.....	26
103.03	PROJECT DETAILS .....	32
103.04	ADDITIONAL TOPICS FOR DISCUSSION .....	35
103.10	ONE CALL NOTIFICATION.....	37
<b>Fiber Optic Cable</b>	.....	<b>37</b>
103.11	UTILITIES AND RAILROAD REHABILITATION .....	37
General.....	.....	37
Preventing Damage to Utility Properties .....	.....	37
Beginning Rehabilitation.....	.....	38
Inspecting Rehabilitation Work.....	.....	38
103.12	<b>HAUL ROADS (SSHC Section 107)</b> .....	39
103.20	<b>CONTRACT ADMINISTRATION</b> .....	40
103.21	NEBRASKA & FHWA FORMS & REPORTS - PREPARED BY CONTRACTOR ..40	40
103.22	OCCUPATIONAL SAFETY AND HEALTH.....	41
<b>103.23 EQUAL EMPLOYMENT OPPORTUNITY (EEO)</b>	.....	<b>42</b>
Contractor's Responsibility.....	.....	42
Project Manager Involvement .....	.....	42
103.24	TRAINING & TRAINEE PROGRAMS .....	44
Contractor's Responsibility.....	.....	44
Project Manager's Involvement.....	.....	46
103.25	<b>WAGES AND EMPLOYMENT</b> .....	47
103.26	<b>DAVIS-BACON AND RELATED ACTS REQUIREMENTS (Payrolls)</b> .....49	49
103.27	DISADVANTAGED BUSINESS ENTERPRISE (DBE) SUBCONTRACTOR .....	54
103.28	LEASE OF PROPERTY BEYOND THE HIGHWAY RIGHT-OF-WAY.....	59
<b>103.29 CONTRACTOR'S USE OF HIGHWAY RIGHT-OF-WAY</b>	.....	<b>59</b>
103.30	"CONTRACT QUANTITIES" .....	59\\
103.31	<b>CONTRACTOR'S SALES TAX EXEMPTION</b> .....	60
103.32	LOTUS NOTES – NOTIFICATION.....	60
103.33	<b>PRIME CONTRACTORS/SUBCONTRACTORS</b> .....	60
103.40	<b>FREIGHT RATES</b> .....	61
103.50	<b>BARRICADES, DANGER, WARNING, AND DETOUR SIGNS</b> .....	62
103.60	<b>SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION</b> .....	63
103.61	<b>Responsibility of Contractor</b> .....	63
Safety Inspections .....	.....	63
Postings .....	.....	63
Checklist Safety Program .....	.....	63
Crystalline Silica Exposure & OSHA Notification .....	.....	64

<b>104.00 CONSTRUCTION INSPECTION.....</b>	66
104.01 CONTRACT TIME DETERMINATION.....	66
<b>Tentative Beginning Date .....</b>	66
<b>Notice to Proceed.....</b>	66
<b>Beginning the Counting of Working Days .....</b>	67
<b>Calendar Day .....</b>	67
<b>Working Day.....</b>	67
<b>Current Controlling Operation.....</b>	67
<b>Working Day Report and Diary Record .....</b>	69
104.02 CHARACTER OF WORKPERSONS, METHODS, AND EQUIPMENT .....	70
104.03 TEMPORARY SUSPENSION OF WORK.....	71
<b>Specification Provisions.....</b>	71
<b>Specialty Items, Time Suspensions.....</b>	71
104.04 PROGRESS OF WORK .....	73
104.05 WINTER WORK .....	74
104.06 WEEKLY REPORT OF WORKING DAYS .....	74
104.07 RENTAL RATE GUIDELINES.....	75
104.08 CHANGE ORDER - SUPPLEMENTAL AGREEMENTS	
( <i>SSHC Subsection 104.02</i> ) .....	79
<b>Policy for Change Orders.....</b>	79
<b>Subcontracted Items .....</b>	79
<b>Contract Unit Price .....</b>	79
<b>Change Order Approval Limits .....</b>	80
<b>FHWA/Certification Acceptance .....</b>	80
Cost Overrun/Underrun Notification ( <i>DR Form 74</i> ) .....	86
Work Orders.....	86
Force Account Agreements and Statements.....	87
<b>Force Account Agreements.....</b>	87
<b>Force Account Statements .....</b>	89
<b>Alterations of Plans or Character of Work.....</b>	90
104.09 VALUE ENGINEERING .....	91
104.10 PLANT INSPECTION.....	93
<b>104.11 PLANT REPORTS.....</b>	94
104.20 FIELD TESTS .....	95
104.21 FIELD TESTING ON CONSTRUCTION PROJECTS.....	95
<b>Materials.....</b>	95
<b>Project Acceptance Sampling and Testing .....</b>	95
<b>Assurance Sampling and Testing .....</b>	95
104.30 TRUCKS/HAULING OF MATERIALS.....	96
104.40 SCALES.....	97
104.41 SCALE TICKETS.....	97
104.42 TRUCK PLATFORM SCALE APPROVAL .....	98
<b>Truck Platform Scale Use .....</b>	98
104.50 SMOOTHNESS.....	99
104.51 TESTING .....	99
104.52 EVALUATION .....	99
<b>Bridge Approach Smoothness .....</b>	99

<b>Bridge Deck Smoothness</b>	99
104.53   BUMP CORRECTION	100
104.60   LIQUIDATED DAMAGES & EXTENSION OF CONTRACT TIME	100
<b>Liquidated Damages</b>	100
<b>Contract Time Extensions</b>	100
104.70   ACCIDENTS	102
<b>105.00   MEASUREMENT AND PAYMENT</b>	103
105.01   GENERAL	103
105.02   MEASUREMENT OF QUANTITIES AND COMPENSATION FOR ALTERED QUANTITIES	103
105.03   CANCELLED ITEMS (MATERIALS FURNISHED BY CONTRACTOR AND NOT USED DUE TO CHANGES IN PLANS)	104
105.04   PARTIAL PAYMENT	104
105.05   FIELD MEASUREMENT AND PAYMENT	105
Photographs and Video Tapes	105
Field Records - General	105
Field SiteManager Entries or SiteManager Item Documentation	105
Scale Tickets	106
105.06   CONTRACTOR'S ESTIMATES	107
Stockpiling	108
Contractor's Statement of Compliance	109
Contractor's Statement of Materials and Labor	110
105.07   FIELD COMPUTATIONS FOR FINAL PAYMENT	110
<b>General</b>	110
<b>Roadway Excavation</b>	110
Data Collector	110
Planimeter Method	111
Overhaul	113
Foundation Course	113
Gravel Surfacing	114
Prime Coat and Tack Coat	114
Asphaltic Concrete Surface Course and Base Course	115
Concrete Pavement	115
<b>Removal of Existing Structures and Preparation of Existing Structures</b>	115
Removal of Existing Structures	115
Preparation of Existing Box Culverts	116
<b>Excavation for Structures</b>	116
Excavation for Bridges	116
Concrete Seal Course	116
Excavation for Culverts	117
General	117
Typical Channel Section	117
<b>Piles and Pile Driving</b>	118
Sheet Piling	118
Concrete Construction and Reinforcement	119
Culverts	119
Concrete Pipe Culverts	119

<b>Corrugated Metal Pipe and Pipe Arch Culverts</b> .....	120
<b>Corrugated Metal Pipe</b> .....	120
<b>Corrugated Metal Pipe Arches</b> .....	120
<b>Pipe Ordered But Not Used</b> .....	120
<b>Culvert Pipe</b> .....	121
<b>Sewers</b> .....	121
<b>Excavation</b> .....	121
<b>Pipe Computations</b> .....	121
<b>Guardrail</b> .....	122
<b>Seeding and Slope Protection</b> .....	122
<b>105.08 BORROW AND LOCAL PIT MATERIALS OBTAINED BY THE CONTRACTOR</b> .....	122
<b>Borrow and Local Pit Materials Furnished by the State or County and Not Involving the Contractor</b> .....	123
<b>105.09 SUMMARY OF FINAL QUANTITIES</b> .....	124
<b>105.10 MOBILIZATION</b> .....	124
<b>Method of Measurement and Basis of Payment</b> .....	124
<b>105.11 SALVAGED PROJECT MATERIALS REPORTING</b> .....	124
<b>106.00 PROJECT FINALIZATION</b> .....	125
<b>106.01 FINAL PAYMENT TO CONTRACTOR</b> .....	125
<b>106.02 PRICE ADJUSTMENT CHANGE ORDERS</b> .....	125
<b>106.03 EQUIPMENT PURCHASED BY CONSTRUCTION CONTRACTS</b> .....	125
<b>106.04 PROJECT ACCEPTANCE AND AUTHORIZATION FOR FINAL PAYMENT</b> .....	125
<b>Notification of Project Completion (DR Form 91) - All Projects</b> .....	126
<b>106.05 FINAL PACKAGE</b> .....	126
<b>106.06 FINAL COMPUTATIONS</b> .....	126
<b>106.07 ACCEPTANCE AND FINAL PAYMENT</b> .....	126
Final Inspection and Acceptance .....	126
<b>Interest Payments on Delayed Estimates</b> .....	127
<b>106.08 FINAL RECORDS</b> .....	128
<b>Introduction</b> .....	128
<b>Right-of-Way</b> .....	128
<b>Crop Damage</b> .....	128
<b>Alternate Crop Damage Procedure</b> .....	129
<b>106.09 STATEMENT OF MATERIALS AND LABOR</b> .....	132
<b>106.10 AS BUILT PLANS</b> .....	133
<b>Clearance Letter</b> .....	137
<b>106.11 OVERRUNS AND UNDERRUNS LETTER</b> .....	137
<b>106.12 CONTRACTOR EVALUATIONS</b> .....	137
<b>106.13 LETTER OF TRANSMITTAL</b> .....	141
<b>106.14 FINALING PROCEDURES</b> .....	141
<b>106.15 UNAUTHORIZED WORK</b> .....	142
<b>106.16 USE OF ADJACENT LAND UNDER CONTRACT OR LEASE</b> .....	142
<b>106.17 FINAL CLEANING UP</b> .....	142
<b>106.18 CONSULTANT INSPECTION</b> .....	143

## DIVISION 200 -- EARTHWORK

<b>SECTION 201.00 -- EARTHWORK INSPECTION CHECKLIST .....</b>	145
<b>202.00 GENERAL GRADING INSTRUCTIONS.....</b>	146
Grading Inspection .....	146
Blue Tops.....	146
Rounding of Hinge Points .....	146
Erosion Control.....	146
<b>203.00 CLEARING AND GRUBBING .....</b>	148
<b>203.01 CONSTRUCTION METHODS .....</b>	148
Disposal of Waste .....	148
<b>204.00 REMOVAL OF STRUCTURES AND OBSTRUCTIONS.....</b>	161
<b>204.01 CONSTRUCTION METHODS .....</b>	161
Removal and Disposal of Old Pavement.....	161
Disposal of Asphaltic Concrete Pavement.....	161
Hazardous Material (Wells, Asbestos Fibers in ACC, Building Removal, Underground Storage Tanks, Archeological Remains).....	161
<b>205.00 EXCAVATION .....</b>	162
<b>205.01 DESCRIPTION.....</b>	162
<b>205.02 MATERIAL REQUIREMENTS.....</b>	162
Embankment and Excavation Soils Criteria .....	162
Unsuitable Material.....	163
Rock Material.....	163
Contractor Furnished Borrow Areas.....	163
Approval For Soil Type .....	164
Preservation of Cultural Resources .....	164
Nebraska Game and Parks Commission Approval of Borrow Sites.....	164
<b>205.03 EQUIPMENT .....</b>	166
Overweight Axle Loads .....	166
Hauling On or Over Surfaced Roads .....	166
<b>205.04 CONSTRUCTION METHODS .....</b>	166
Embankment Construction .....	166
Site Preparation .....	166
Deposition of Embankment Material .....	166
Compaction .....	167
Moisture Density Curves .....	168
Construction of Embankment Toe Berms .....	168
Construction of Bridge Approach Fills .....	169
Earthwork-Measured-in-Embarkment .....	169
Prewatering Plan .....	169
Payment for Water for Embankment Construction.....	169
Finishing.....	170
Tentative Acceptance .....	170
<b>206.00 TOPSOIL .....</b>	171
<b>206.01 CONSTRUCTION METHODS .....</b>	171
Stripping, Salvaging, and Spreading .....	171
Topsoil on Roadway Cuts and Embankments .....	171
<b>206.02 BASIS OF PAYMENT .....</b>	171
<b>207.00 OVERHAUL .....</b>	172

## DIVISION 300 - SUBGRADE PREPARATION

<b>301.00 CHECKLISTS (See Division 200).....</b>	175
<b>302.00 BASE COURSE AND SUBGRADE INSPECTION .....</b>	176
<b>303.00 SUBGRADE PREPARATION AND SHOULDER SUBGRADE PREPARATION.....</b>	177
<b>303.01 CONSTRUCTION METHODS .....</b>	177
Prime Coat.....	178
Subgrade Preparation After Removal of Existing Approach Slabs.....	178
<b>303.02 METHOD OF MEASUREMENT .....</b>	179
<b>304.00 SUBGRADE STABILIZATION.....</b>	180
<b>304.01 DESCRIPTION.....</b>	180
<b>304.02 MATERIAL REQUIREMENTS.....</b>	180
<b>304.03 EQUIPMENT .....</b>	180
<b>304.04 CONSTRUCTION METHODS .....</b>	180
<b>305.00 EARTH SHOULDER CONSTRUCTION.....</b>	181
<b>305.01 DESCRIPTION.....</b>	181
<b>305.02 CONSTRUCTION METHODS .....</b>	181
<b>305.03 METHOD OF MEASUREMENT .....</b>	181
<b>306.00 FOUNDATION COURSE .....</b>	182
<b>306.01 DESCRIPTION.....</b>	182
<b>306.02 MATERIAL REQUIREMENTS.....</b>	182
<b>306.03 CONSTRUCTION METHODS .....</b>	182
<b>306.04 BASIS OF PAYMENT .....</b>	185
<b>307.00 ROCK OR AGGREGATE SURFACING.....</b>	186
<b>307.01 DESCRIPTION.....</b>	186
<b>307.02 MATERIAL REQUIREMENTS.....</b>	186
<b>307.03 EQUIPMENT .....</b>	186
<b>307.04 CONSTRUCTION METHODS .....</b>	187
<b>307.05 METHOD OF MEASUREMENT .....</b>	188
<b>307.06 BASIS OF PAYMENT .....</b>	188

## DIVISION 400

### LIGHTING, SIGNS, TRAFFIC SIGNALS & TRAFFIC CONTROL

<b>401.00</b>	<b>LIGHTING CHECKLIST</b>	193
	SSHC References .....	193
	Other References .....	193
<b>402.00</b>	<b>LIGHTING</b>	197
<b>402.01</b>	<b>GENERAL INFORMATION</b>	197
	SSHC References .....	197
	Other References .....	197
	General Comment .....	197
	Special Construction Items.....	197
<b>402.02</b>	<b>PRECONSTRUCTON CONFERENCE</b>	197
<b>402.03</b>	<b>SHOP DRAWINGS AND MATERIALS LIST</b>	198
402.04	CONSTRUCTION REQUIREMENTS .....	198
	Staking of Light Pole and Tower Foundations .....	198
	Wood Poles Used on Lighting Projects .....	198
	Testing of Lighting Systems .....	198
	Poles and Towers.....	199
	Poles and Tower Foundations .....	199
	Luminaires .....	199
	Lighting Control Centers.....	200
	High Mast Lowering System .....	200
	Temporary Lighting System.....	200
402.05	PAYMENT FOR ELECTRIC POWER USED BY THE LIGHTING SYSTEM.....	201
402.06	COMPLETION -AND ACCEPTANCE OF THE PROJECT.....	201
<b>403.00</b>	<b>TRAFFIC SIGNALS</b> .....	202
403.01	GENERAL .....	202
403.02	PRE-CONSTRUCTION CONFERENCE .....	202
403.03	PRELIMINARY STAKING .....	202
403.04	SAW CUT LOOP LOCATION.....	202
403.05	TEMPORARY SIGNAL .....	202
<b>403.06</b>	<b>ELECTRICAL POWER</b> .....	203
403.07	STATE SUPPLIED MATERIAL .....	203
403.08	SAFETY.....	203
403.09	ITEMS TO CHECK WHEN INSTALLING .....	203
403.10	FINAL SIGNAL TURN ON.....	206
<b>404.00</b>	<b>CONSTRUCTION WORK ZONE TRAFFIC CONTROL</b> .....	207
404.01	TRAFFIC CONTROL SPECIFICATION REFERENCES .....	207
404.02	TRAFFIC CONTROL SIGNING CHANGES.....	207
404.03	CONSTRUCTION ZONE ACCIDENT REPORTING .....	208
	Investigation Procedure .....	208
	Accident Notification Procedure.....	209
	Reporting of Severe Personal Injury and Fatal Accidents .....	209
404.04	STOP SIGNS ON CONSTRUCTION PROJECTS .....	209
404.05	"ROAD WORK AHEAD" AND "END ROAD WORK" SIGNS.....	210
404.06	NO PASSING ZONES ON CONSTRUCTION PROJECTS .....	210

404.07	EQUIPMENT AND MATERIAL STORAGE .....	210
404.08	CONSTRUCTION WORK ZONE SIGNING DURING WINTER SHUTDOWN....	211
	Uncompleted Projects .....	211
	Multi-Contract Projects .....	211
	Special Concerns .....	212
404.09	FLAGGERS & PILOT CARS.....	212
	Flagger Bid Item .....	212
	Slow/Slow Paddles .....	212
	Slow/Slow Paddles .....	212
	Method of Measurement .....	213
404.10	INTERSTATE TRAFFIC CONTROL REQUIREMENTS .....	213
	Median Crossings .....	213
	Traffic Control Removal for Head-to-Head Projects.....	213
	Raised Pavement Markers .....	214
404.11	CHANGEABLE MESSAGE SIGN GUIDELINES .....	214
404.12	FLASHING ARROW PANELS .....	214
404.13	SIGN MOUNTING DEVICES .....	215
404.14	REMOVAL OF TEMPORARY PAVEMENT MARKINGS.....	215
404.15	WORK AREA SPEED ZONE .....	216
	Speed Limits in Maintenance Work Areas.....	216
<b>Signing</b>	.....	<b>218</b>
<b>Recordkeeping</b>	.....	<b>220</b>
404.16	BRIDGE APPROACH GUARD RAILS.....	220
404.17	INERTIAL BARRIER SYSTEMS .....	221
404.18	BARRICADES/PLASTIC DRUMS.....	221
405.00	SIGNS .....	222
405.01	DEDUCTION FOR SIGNS .....	222
405.02	SIGN MAINTENANCE.....	222

## DIVISION 500

### BITUMINOUS PAVEMENT

501.01	ASPHALT PAVEMENT CHECKLIST .....	227
502.00	ASPHALT PAVEMENT .....	232
502.10	ASPHALT PAVEMENT DESCRIPTION .....	232
502.20	ASPHALT PAVEMENT MATERIAL REQUIREMENTS.....	232
502.20.1	ASPHALT ACCEPTANCE AND TESTING .....	232
Field Tests and Certification of Materials .....	232	
Asphalt Materials.....	232	
Aggregates.....	233	
502.20.2	RESPONSIBILITY AND DOCUMENTING ASPHALT MIXTURE PROPORTIONING CHANGES .....	233
Adjusting Asphalt Cement Contents .....	233	
Documenting Corrective Action for Noncomplying Air Voids Test on Specimens Taken from Constructed Pavement .....	233	
Adjusting Aggregate Proportions .....	234	
Filler-Bitumen Ratio.....	234	
502.20.3	ASPHALT REPORT FORMS.....	234
Form Identification and Use .....	235	
502.30	ASPHALT PAVEMENT EQUIPMENT .....	236
502.30.1	INSPECTION AT ASPHALT PLANTS.....	236
502.30.2	INSPECTING THE MIXING TIME OF ASPHALT PLANTS.....	236
502.30.3	USE OF SPECIAL EQUIPMENT .....	237
Material Transfer Vehicle .....	237	
Mat Smoothness Machine .....	238	
Windrow Pick-up Equipment .....	238	
502.40	ASPHALT PAVEMENT CONSTRUCTION METHODS.....	239
502.40.1	UNSTABLE SUBGRADES AND SUBBASES .....	239
Locating Unstable Areas.....	239	
Determining Cause .....	239	
Drying and Recompaction.....	239	
Special Treatments.....	240	
502.40.2	GRADELINE STRINGS AND EDGE ALIGNMENT .....	240
502.40.3	LONGITUDINAL JOINTS .....	241
502.40.5	DENSITY CONTROLS FOR ASPHALTIC CONCRETE CONSTRUCTION ..242	
Procedures for Construction of Test Strips .....	244	
Resolving Density - Void Conflicts.....	244	
502.40.6	LAYING WIDTHS FOR ASPHALT .....	245
502.40.6a	POLICY FOR PLACEMENT OF TEMPLATE CORRECTION ON OVERLAY 245	
502.40.7	PLACEMENT RATES FOR HOT MIX ASPHALT BASES, BINDER, AND SURFACE COURSES .....	246
502.40.8	COLD WEATHER ASPHALT CONSTRUCTION .....	246
502.40.9	RUMBLE STRIPS IN ASPHALT SHOULDERS.....	246
502.40.10	QUALITY CONTROL MONITORING .....	246
502.50	ASPHALT PAVEMENT METHOD OF MEASUREMENT AND PAYMENT ..251	

<b>502.50.1</b>	<b>TESTING FOR SMOOTHNESS .....</b>	251
<b>_</b>	<b>Incentive/Disincentive Payments for Asphaltic Concrete Smoothness .....</b>	251
<b>Use of Straightedge .....</b>	253	
<b>502.50.2</b>	<b>CHECKING TRANSVERSE JOINTS FOR SMOOTHNESS .....</b>	253
<b>502.50.3</b>	<b>PERFORMANCE GRADED BINDER .....</b>	254
<b>Tank Measurement and Asphalt Cement Content Determination .....</b>	254	
<b>Measuring Asphalt Cement for Small Quantities.....</b>	255	
<b>Asphalt Cement Quantities and Pay Adjustments .....</b>	255	
<b>Asphalt Cement Quantities and Pay Adjustments .....</b>	255	
<b>502.50.4</b>	<b>TARGET VALUES FOR ASPHALTIC CONCRETE PRODUCED .....</b>	255
<b>502.50.5</b>	<b>MEASURING ASPHALT MATERIALS .....</b>	255
<b>503.00</b>	<b>ASPHALT CURBS .....</b>	257
<b>504.00</b>	<b>STATE MAINTENANCE PATCHING.....</b>	258
<b>505.00</b>	<b>P.E.P. GUIDELINES .....</b>	259
<b>506.00</b>	<b>MILLINGS.....</b>	260
<b>507.00</b>	<b>TACK COATS USING EMULSIONS .....</b>	260a
<b>For Dilution .....</b>	260a	
<b>Application Rate for Diluted Emulsion .....</b>	260a	
<b>Sample for Compliance .....</b>	260a	
<b>Measurement for Pay .....</b>	260a	
<b>Settlement of Diluted Emulsions .....</b>	260a	

## DIVISION 600

### PORLAND CEMENT CONCRETE (PCC) PAVEMENT

<b>601.00 CONCRETE PAVEMENT CHECKLISTS .....</b>	263
<b>601.01 CONCRETE PAVEMENT CHECKLIST .....</b>	263
<b>601.02 CONCRETE PLANT CHECKLIST .....</b>	265
<b>601.03 CONCRETE PAVEMENT REPAIR CHECKLIST .....</b>	267
<b>602.00 PORTLAND CEMENT CONCRETE (PCC) PAVEMENT .....</b>	269
<b>602.10 DESCRIPTION.....</b>	269
<b>602.20 PCC PAVEMENT MATERIAL REQUIREMENTS.....</b>	270
<b>602.201 Composition of Concrete .....</b>	270
<b>602.202 Concrete Strength.....</b>	270
<b>602.203 Concrete Sampling Locations.....</b>	270
<b>602.204 Testing Procedures .....</b>	271
<b>602.205 Air Entrainment in Plastic Concrete .....</b>	271
<b>602.206 Ready Mix Concrete .....</b>	271
<b>602.207 Concrete Discharge Times .....</b>	271
<b>602.208 Miscellaneous Material Requirements.....</b>	272
<b>602.30 PCC PAVEMENT EQUIPMENT .....</b>	273
<b>602.031 General .....</b>	273
<b>602.032 Batching Equipment.....</b>	273
<b>602.303 Cement Bulk Handling Equipment .....</b>	273
<b>602.304 Scales.....</b>	273
<b>602.305 Concrete Mixers.....</b>	273
<b>602.306 Hauling Equipment .....</b>	274
<b>602.307 Subgrade Trimmer.....</b>	275
<b>602.308 Concrete Spreader.....</b>	275
<b>602.309 Finishing Equipment .....</b>	275
<b>602.3010 Slip Form Paving Equipment.....</b>	276
<b>602.3011 Saws Used on New Pavement &amp; Unbonded PCC Overlays .....</b>	276
<b>602.3012 Miscellaneous Equipment .....</b>	276
<b>602.3013 Accumulation of Materials in Transporting Vehicles .....</b>	277
<b>602.40 PCC PAVEMENT PRECONCRETING CONFERENCE .....</b>	278
<b>602.401 PCC Daily Report of Pavement Laid (DR Form 85) .....</b>	278
<b>602.50 PCC PAVEMENT CONSTRUCTION METHODS.....</b>	279
<b>602.501 Subgrade General .....</b>	279
<b>602.502 Preparation of Subgrade .....</b>	279
<b>602.503 Foundation Course.....</b>	279
<b>602.504 Grades on Drives in Cities.....</b>	280
<b>602.505 Protection of Pavement .....</b>	280
<b>602.506 Operating Finishing Equipment on Previously Placed Concrete in             Multiple-Lane Construction .....</b>	280
<b>602.507 Surface Cleaning .....</b>	280
<b>602.508 Material Inspections .....</b>	280
<b>602.509 Batching Inspections .....</b>	281
<b>602.5010 Cement Hauling Inspections.....</b>	283

<b>602.5011 Mixing and Hauling.....</b>	284
<b>602.5012 Forms.....</b>	287
<b>602.5013 Placing Reinforcing Steel.....</b>	288
<b>602.5014 Tie-Bar Steel Inspection.....</b>	288
<b>602.5015 Inlet and Utility Accesses.....</b>	289
<b>602.5016 Box-Outs for Utility Accesses.....</b>	289
<b>602.5017 Box-Outs on Slip-Form Paving .....</b>	290
<b>602.5018 Placing and Spreading.....</b>	290
<b>602.5019 Slip-Form Construction.....</b>	291
<b>602.5020 Surface Finishing.....</b>	293
<b>602.5021 Use of Water in Finishing Concrete .....</b>	294
<b>602.5022 Tining .....</b>	295
<b>Tine Determination.....</b>	296
<b>Guidelines for Tining Concrete Pavement.....</b>	296
<b>602.5023 Pavement Depression .....</b>	296
<b>602.5024 Pavement Station Stamping.....</b>	296
<b>602.5025 Integral Curb Placement.....</b>	297
<b>602.5026 Protection and Curing.....</b>	297
<b>602.5027 Joints.....</b>	298
Sealing Joints .....	300
Hot Poured Sealants .....	300
Preformed Polychloroprene Elastomeric Type.....	301
Silicone Sealants.....	302
Mastic Sealants .....	302
Cleaning Joints .....	302
Sealing Sawed Joints .....	302
Joint Filling .....	302
Sealing Equipment .....	303
Backer Rod .....	303
Doweled Support Assemblies.....	303
Dowel Tolerances .....	303
Dowel Assembly Placement.....	303
Marking Joint Locations .....	304
Blanking Bands .....	304
Longitudinal Joint Design .....	304
Curing of Keyed and Doweled Joints .....	304
<b>602.5028 Prevention of Rain Damage to Plastic Concrete .....</b>	304
<b>602.5029 Repair of Deficient Pavement.....</b>	305
Recommended Repair Method.....	305
<b>602.5030 Mud Ball Repair .....</b>	307
<b>602.5031 Cold Weather Paving and Plant Operations .....</b>	308
Cold Weather Pavement Protection .....	308
Cold Weather Plant Operation.....	308
<b>602.60 PCC PAVEMENT METHOD OF MEASUREMENT.....</b>	309
<b>602.601 Smoothness Tests (Profilograph) .....</b>	309
<b>602.602 Requirements for Thickness .....</b>	309
<b>602.603 Material Quantities .....</b>	309
<b>602.604 Concrete Driveways .....</b>	309
<b>602.605 Records and Reports .....</b>	310

<b>603.00 PCC PAVEMENT PATCHING.....</b>	311
<b>603.10 Full Depth PCC Patches.....</b>	311
<b>603.20 SAW CUTS IN FULL DEPTH PCC PATCHES .....</b>	311

## DIVISION 700

### BRIDGES, CULVERTS & RELATED CONSTRUCTION

<b>701.00</b>	<b>CHECKLISTS</b>	315
<b>701.01</b>	<b>PILES AND PILE DRIVING CHECKLIST</b>	315
<b>701.02</b>	<b>CONCRETE CONSTRUCTION CHECKLIST</b>	322
<b>701.03</b>	<b>CONCRETE BRIDGE FLOORS CHECKLIST</b>	323
<b>701.04</b>	<b>STEEL STRUCTURES CHECKLIST</b>	325
<b>701.05</b>	<b>CONCRETE BRIDGE DECK REPAIR WITH SILICA FUME CONCRETE</b>	326
<b>702.00</b>	<b>EXCAVATION FOR STRUCTURES (SSHC Section 702)</b>	328
<b>702.01</b>	<b>DESCRIPTION</b>	328
<b>702.02</b>	<b>MATERIAL REQUIREMENTS</b>	328
	Unsuitable Material Excavation	328
<b>702.03</b>	<b>CONSTRUCTION METHODS</b>	328
	Culvert Excavation	328
	General Structure Backfilling	329
	Concrete Seal Course	330
	Foundations	330
	Common Survey Errors	331
	Encountering Old Substructures	331
	Bridge Deck Removal	331
<b>703.00</b>	<b>PILING AND PILE DRIVING (SSHC Section 703)</b>	332
<b>703.01</b>	<b>EQUIPMENT</b>	332
	Diesel Hammers	332
	Bearing and Penetration	332
	Dynamic Pile Analyzer	333
<b>703.02</b>	<b>CONSTRUCTION METHODS</b>	333
	Pile Driving Constraints	333
	Splicing Pile	333
	Steel Pile Cutoffs	333
	Pile Groups/Categories	333
	Inspection of Piles Prior to and During Installation	336
	Precast Concrete Piles	336
	Steel Pipe Piles	337
	Steel Sheet Piles	338
	Inspection of Driving Equipment	338
	Inspection of Driving Equipment During Installation	340
	Single Acting Diesel Hammers	340
	Field Driving Problem	343
<b>704.00</b>	<b>BRIDGES (STEEL STRUCTURES) (SSHC Section 708)</b>	347
<b>704.01</b>	<b>DESCRIPTION</b>	347
<b>704.02</b>	<b>MATERIAL REQUIREMENTS</b>	347
<b>704.03</b>	<b>CONSTRUCTION METHODS</b>	347
	Falsework (SSHC Subsection 704.03)	347
	Temporary Fastenings	347
	Submitting Plans	348
	Bridges-Steel Beam	348
	Structural Joints	349

High Strength Fasteners.....	352
Welding .....	360
Shear Connectors.....	360
Trouble Shooting.....	364
Weld Spatter.....	365
Undercut.....	365
Rough Welding .....	365
Porosity and Surface Holes .....	365
Poor Fusion.....	366
Shallow Penetration.....	366
Cracking.....	366
How to Reduce Arc Blow .....	367
The Effects of Fixturing on Arc Blow .....	368
<b>704.04     METHOD OF MEASUREMENT</b>	369
<b>704.05     BASIS OF PAYMENT</b>	369
<b>705.00     REINFORCEMENT</b> .....	371
<b>705.01     DESCRIPTION</b> .....	371
<b>705.02     MATERIAL REQUIREMENTS</b> .....	371
<b>705.03     CONSTRUCTION METHODS</b> .....	371
Placement and Checking.....	371
Slab Thickness .....	371
Clearance of Slab Reinforcement .....	372
Protection of Material .....	372
Placing and Fastening .....	372
Special Attention Areas .....	373
Epoxy-Coated Reinforcement .....	374
Care and Handling .....	374
Field Inspection .....	375
Repair of Damaged Coating .....	376
Bar Designation System .....	379
Splicing.....	379
<b>705.04     METHOD OF MEASUREMENT</b>	381
<b>706.00     CONCRETE CONSTRUCTION</b> .....	382
<b>706.01     DESCRIPTION</b> .....	382
<b>706.02     MATERIAL REQUIREMENTS</b> .....	382
Composition of Concrete .....	382
Admixtures .....	382
Air Entraining Admixtures .....	383
Water Reducing Admixtures (Type A) (optional).....	384
High Range Water Reducing Admixtures (Type F) (optional).....	384
Retarding Admixtures (required).....	385
Accelerating Admixtures (optional).....	385
Finely Divided Mineral Admixtures .....	386
Concrete Temperatures .....	388
<b>706.03     CONSTRUCTION METHODS</b> .....	390
Prepour Meeting.....	390
Concrete Plant Inspector's Checklist .....	391
Falsework.....	394
Forms.....	404

Removal of Forms and Falsework .....	404
Use of Insulated Forms for Protection.....	405
Placing Concrete .....	405
Placement Considerations .....	406
Placement Methods .....	408
Pump Placement .....	409
Consolidation of Concrete .....	410
Reinforcement Bar Cover.....	410
Use of Finishing Machine.....	411
Straightedging .....	411
Tining.....	411
Curing.....	412
Ways to Avoid Deck Cracks .....	412
Seal Bridge Deck Cracks .....	413
Cold Weather Placement .....	413
Floor Drains .....	413
Flowable Fill .....	413
Installation of Joints .....	414
Curing Concrete.....	416
Concreting in Cold Weather .....	416
Simultaneous Casting of Deck and Approach Slabs .....	417
Surface Checking (Not in Spec) .....	417
Test Procedure for Smoothness.....	418
Smoothness of Bridge Decks.....	418
Approach Sections.....	419
Setting Beams .....	420
<b>706.04     METHOD OF MEASUREMENT .....</b>	420
<b>707.00     DECKS AND OVERLAYS .....</b>	421
<b>707.01     DESCRIPTION.....</b>	421
<b>707.02     MATERIAL REQUIREMENTS .....</b>	421
<b>707.03     CONSTRUCTION METHODS .....</b>	421
General.....	421
Bridge Deck Curing.....	423
Bridge Deck Joints.....	423
Deck Overlay Preparation.....	423
Class I Floor Repair .....	423
Work on Adjacent Lanes.....	423
<b>708.00     Bridge Diaphragms.....</b>	424
<b>709.00     Girder Shims .....</b>	425
Definition .....	425
<b>710.00     Pot Bearings.....</b>	428
<b>711.00     Barrier Rails .....</b>	429
Fixed Form Jersey & Retrofit Rail.....	429
Cast-In-Place (Retrofit) Barrier Rail.....	429
Slip Form Barrier Rail .....	430
<b>711.02     Material Requirements (See Section 706.....</b>	430
<b>711.03     Construction Methods .....</b>	430
Concrete Surface Finish (Rail and Beams.....	430
Surface Finish.....	430

<b>712.00</b>	<b>HAND RAILS .....</b>	432
<b>712.01</b>	<b>DESCRIPTION.....</b>	432
<b>712.02</b>	<b>MATERIAL REQUIREMENTS.....</b>	432
<b>712.03</b>	<b>CONSTRUCTION METHODS .....</b>	432
	Ornamental Handrail.....	432
<b>713.00</b>	<b>PAINTING.....</b>	433
<b>713.01</b>	<b>DESCRIPTION.....</b>	433
	Painting .....	433
<b>713.02</b>	<b>MATERIAL REQUIREMENTS.....</b>	433
	Mixing Paint.....	433
<b>713.03</b>	<b>CONSTRUCTION METHODS .....</b>	434a
	Painting Structural Steel .....	434a
<b>CULVERTS .....</b>		434b
	<b>GENERAL .....</b>	434b
<b>715.00</b>	<b>CONCRETE BOX CULVERTS .....</b>	434c
<b>715.01</b>	<b>DESCRIPTION.....</b>	434c
<b>715.02</b>	<b>MATERIAL REQUIREMENTS.....</b>	434c
	<b>CONSTRUCTION METHODS .....</b>	434c
	General.....	434c
	Placing Concrete and Form Removal .....	434c
	Placing Concrete .....	434c
	Sheet Pile Turndown.....	434d
	Removal of Wall Forms .....	434g
	Flume Reinforcement .....	434g
	Backfilling Culverts – Typical Grading .....	434g
	Joints .....	434h
<b>716.00</b>	<b>CULVERT PIPE .....</b>	434j
<b>716.01</b>	<b>DESCRIPTION.....</b>	434j
<b>716.02</b>	<b>CONSTRUCTION METHODS .....</b>	434j
	Culvert List.....	434j
	Pipe Bedding.....	434j
	Temporary Culvert Pipe .....	434j
	Salvaged Culvert Pipe .....	434k
<b>CONCRETE PIPE CULVERTS .....</b>		434t
<b>717.01</b>	<b>DESCRIPTION.....</b>	434t
<b>717.02</b>	<b>MATERIAL REQUIREMENTS.....</b>	434t
	Pipe Marking.....	434t
	Ordering Material.....	434t
<b>717.03</b>	<b>CONSTRUCTION METHODS .....</b>	434u
	Excavation and Backfilling .....	434u
	Installation .....	434v
<b>718.00</b>	<b>CORRUGATED METAL PIPE CULVERTS .....</b>	434w
<b>718.01</b>	<b>DESCRIPTION.....</b>	434w
<b>718.02</b>	<b>MATERIAL REQUIREMENTS.....</b>	434w
	Pipe Marking.....	434w
	Ordering Material.....	434w
<b>718.03</b>	<b>CONSTRUCTION METHODS .....</b>	434w
	Excavating and Backfilling .....	434w
	Installation .....	434w

## DIVISION 800

### ROADSIDE DEVELOPMENT AND EROSION CONTROL

800.00	GENERAL COMMENTS .....	435
801.00	REMOVING AND RESETTING TREES .....	438
801.01	REMOVING AND RESETTING TREES CHECKLIST .....	438
802.00	FURNISHING AND PLANTING OF PLANT MATERIALS.....	439
802.01	FURNISHING AND PLANTING OF PLANT MATERIALS CHECKLIST.....	439
803.00	SEEDING .....	442
803.01	SEEDING CHECKLIST.....	442
803.02	PERMANENT SEEDING DATES.....	444
803.03	PREPARATION OF SEED BED .....	444
803.04	SEED .....	444
804.00	FERTILIZER.....	445
804.01	FERTILIZER CHECKLIST (See Seeding Checklist) .....	445
804.02	EXAMPLE CALCULATIONS .....	445
804.03	APPLICATION OF FERTILIZER .....	447
805.00	MULCH.....	448
805.01	MULCHING CHECKLIST (See Seeding Checklist) .....	448
805.02	EXAMPLE CALCULATION.....	448
805.03	WEEDS.....	448
805.04	ACCEPTABLE MULCH.....	448
805.04	ACCEPTABLE MULCH.....	448
806.00	SODDING .....	449
806.01	SODDING CHECKLIST .....	449
806.02	SOD PLACEMENT .....	450
	SHAPE SOD BED .....	450
	APPLY FERTILIZER .....	450
	PLACE SOD .....	450
	FINISH SOD .....	450
	WATER.....	450
	TAMP.....	450
807.00	EROSION CONTROL.....	451
807.01	EROSION CONTROL CHECKLIST .....	451
<b>807.02</b>	<b>FILTER FABRIC.....</b>	452
808.00	EROSION CHECKS.....	452
808.01	EROSION CHECKS CHECKLIST.....	452
808.02	PLACEMENT .....	452
	Shape .....	452
	Check Slots.....	452
	Finish.....	452
	Fertilize.....	452
	Seed.....	452
	Special Ditch Control Material.....	452
809.00	SILT FENCING.....	454
809.01	SILT FENCING CHECKLIST.....	454
<b>809.02</b>	<b>SILT FENCE.....</b>	454
810.00	SLOPE PROTECTION.....	456
810.01	SLOPE PROTECTION CHECKLIST .....	456

811.00	SLOPE PROTECTION NETTING .....	457
811.01	SLOPE PROTECTION NETTING CHECKLIST.....	457
812.00	COVERCROP SEEDING .....	458
812.01	COVERCROP SEEDING CHECKLIST.....	458
812.02	WATER POLLUTION CONTROL (SOIL EROSION).....	458
812.03	TEMPORARY WATER POLLUTION, CONTROL (SOIL EROSION).....	459
812.04	CONTRACTOR REQUIREMENTS .....	459
813.00	PEAT MOSS .....	461
813.01	PEAT MOSS CHECKLIST .....	461

## DIVISION 900

### INCIDENTAL CONSTRUCTION

901.00	FIELD LABORATORIES AND SCALE HOUSES.....	465
901.01	GENERAL REQUIREMENTS .....	465
901.02	METHOD OF MEASUREMENT .....	465
901.03	BASIS OF PAYMENT .....	465
902.00	GUARDRAIL CHECKLIST .....	466
<b>903.00</b>	<b>W-BEAM/THRIE-BEAM GUARDRAIL.....</b>	<b>467</b>
903.01	DESCRIPTION.....	467
903.02	MATERIAL REQUIREMENTS.....	468
903.03	CONSTRUCTION METHODS.....	468
W-Beam and Thrie-Beam Guardrail Installation.....	469	
Rail Alignment.....	469	
Guardrail Posts .....	469	
Rail Section Location .....	469	
Rail Height.....	469	
Lapping of Guardrail.....	470	
Bridge Connections .....	470	
End Anchorage .....	471	
903.04	METHOD OF MEASUREMENT .....	471
904.00	SUBDRAIN EARTHWORK.....	472
904.01	SUBDRAINS.....	472
904.02	BACKSLOPE DRAINS.....	472
904.03	LONGITUDINAL DRAINS .....	472
Trench Excavation .....	472	
Outlets.....	472	
Porous Backfill .....	472	

## **DIVISION 1000** **MATERIAL DETAILS**

1001.00	GENERAL .....	477
1001.01	MATERIAL CERTIFICATIONS .....	477
1001.02	MATERIAL CERTIFICATION RECEIPT & INTEREST DATE DETERMINATION.	477
1002.00	APPROVED PRODUCTS LIST .....	478
1002.01	DESCRIPTION.....	478
1002.02	ACCESS COMMANDS .....	478
1002.03	ADDITIONS/DELETIONS TO THE APPROVED PRODUCTS LIST.....	479
1003.00	WHITE PIGMENTED CURING COMPOUND AND HOT-POUR JOINT SEALER....	480
1003.01	DESCRIPTION.....	480
1003.02	REPORTING MATERIAL USAGE .....	480
1004.00	PCC REQUIREMENTS.....	481
1004.01	CEMENT CERTIFICATIONS .....	481
1004.02	CONCRETE STRENGTH.....	481a
1004.03	CONCRETE CYLINDER POLICY .....	481a
1005.00	MATERIAL & RESEARCH DIVISION'S FINAL REVIEW PROCEDURES .....	481c

## DIVISION 1100

### ENVIRONMENTAL

<b>DIVISION 1100 - ENVIRONMENTAL .....</b>	485
1100.10   INTRODUCTION.....	485
<b>1100.11   ENVIRONMENTAL REGULATIONS .....</b>	486
<b>1100.12   REGULATORY AUTHORITIES.....</b>	487
EPA.....	487
OSHA.....	487
Nebraska Department of Environmental Quality (DEQ) .....	487
<b>1100.13   ENVIRONMENTAL LAWS.....</b>	488
AHERA.....	488
CAA.....	488
CERCLA .....	488
CWA.....	488
NPDES.....	488
OSHA.....	488
RCRA.....	488
SARA.....	489
SDWA.....	489
TSCA.....	489
<b>1100.14   WETLANDS.....</b>	489
Special Environmental Conditions .....	489
Army Corps 404 Permits .....	493
Permit Determination and Acquisition .....	493
Note on Title Sheet of Plans .....	493
(DEC) Water Quality Certifications .....	494
Dept. of Water Resources Flood Plain Permits .....	494
404 Determination Checklist.....	495
<b>1100.15   WASTED GENERATED.....</b>	497
Solid Waste.....	497
Open Dumping.....	497
Toxic and Hazardous Wastes .....	497
Free Liquids .....	497
<b>1100.16   WATER WELLS .....</b>	497
<b>1100.17   ARCHEOLOGICAL AND PALEONTOLOGICAL DISCOVERIES .....</b>	498
<b>1100.20   UNDERGROUND TANKS.....</b>	499
<b>1100.21   REGISTRATION .....</b>	499
<b>1100.22   REMOVAL OF USTs .....</b>	500
Removal of Known Tanks.....	500
Removal/Discovery of Unknown Tanks ("Orphan" Tanks) .....	505
<b>1100.30   STORM WATER DISCHARGE .....</b>	509
<b>1100.31   NOTICE OF INTENT (NOI).....</b>	509
<b>1100.32   CONSTRUCTION DIVISION POLICIES .....</b>	509
<b>1100.33   QUESTIONS OFTEN ASKED .....</b>	510
<b>1100.40   BRIDGE PAINTING .....</b>	513
<b>1100.41   METHODS OF PAINT REMOVAL .....</b>	514

Open Abrasive Blast Cleaning.....	514
Closed Abrasive Blast - (Vacuum Blasting) .....	515
Hand and Power Tool Cleaning .....	515
<b>1100.42 CONTAINMENT.....</b>	<b>516</b>
Design Considerations .....	516
Rules-of-Thumb.....	517
<b>1100.43 PAINT WASTE DISPOSAL .....</b>	<b>517</b>
Toxic Characteristic Leaching Procedure Testing .....	517
Hazardous Waste Designation.....	518
Notice for Transfer of Nonhazardous Paint Waste .....	518
<b>1100.50 DISPOSAL OF CONSTRUCTION WASTES.....</b>	<b>520</b>
<b>1100.51 ASBESTOS .....</b>	<b>520</b>
Health Concerns.....	520
Asbestos Removal.....	520
1100.60 WELLS AND WATER POLLUTION.....	522
<b>1100.61 SURFACE WATER.....</b>	<b>522</b>
What Does This Mean? .....	522
Who Do We Report To?.....	522
Reportable Quantities .....	522
What is Meant by Contain and Clean-up? .....	523
<b>1100.62 WELLS.....</b>	<b>523</b>

## **DIVISION 1200**

### **SITEMANAGER**

<b>DIVISION 1200 -- SITEMANAGER.....</b>	527
1200.01    INTRODUCTION.....	527
1200.02    INFORMATIONAL GUIDANCE.....	527
1200.03    SITEMANAGER SUPPORT LIST .....	528

## DIVISION 1300

### PROJECT SURVEYS

<b>DIVISION 1300 -- PROJECT SURVEYS .....</b>	531
<b>1300.01 GENERAL.....</b>	531
General. Horizontal and Vertical Control .....	531
Grade And Alignment Stakes .....	531
Staking.....	531
The Department's ROW Line .....	531
Consultant Survey Data .....	531
Consultant Surveyors.....	531
Survey Accuracy .....	531
<b>1300.02 CONSTRUCTION STAKES.....</b>	534
General - Construction Staking .....	534
Minimum Survey Requirements .....	535
Survey Stake Minimum Requirement Examples .....	540
<b>1300.03 CONSTRUCTION SURVEY BASIC REQUIREMENTS.....</b>	542
GeoPak Guidance .....	542
Checking Bench Levels.....	545
Reproducing And Referencing Centerline.....	546
Checking Plan Grade And Calculating Grade Revisions .....	547
Staking Right-Of-Way Fence and Right-Of-Way Limit Listing .....	548
Setting Slope Stakes .....	548
Setting Finishing Stakes .....	550
Setting Trimming Or Paving Form Stakes .....	550
Contractor's Forms on Large Structures .....	551
Checking Culvert Lengths, Culvert Lists, Slope Stakes, Blue Top Stakes, Paving Hubs .....	552
Culvert List – Box Culverts .....	553
Staking Culverts And Structures .....	555
Land Survey Monuments.....	555
U.S. Survey Monuments.....	556
Preserving, Perpetuating.....	557
Perpetuation Of Section Corner Markers.....	559
Setting Witness Corners.....	559
Installation Of Right-Of-Way Markers .....	562
Location Of Markers .....	562
Benchmarks .....	562
Permanent Benchmarks Along Rural Highways.....	563
<b>1300.04 TAKING PRECONSTRUCTION CROSS SECTIONS.....</b>	564
Preliminary Survey Requirements .....	564
Preliminary Survey with Data Collector/GeoPak.....	564
Preconstruction Cross Sections .....	564
Cross Section Accuracy .....	564
Preliminary Cross Sections Used to Compute Final Quantities .....	565
Intersections .....	565
Other Excavation Areas .....	566
Cross Section Notes .....	566
<b>1300.05 FINAL CROSS SECTIONS AND FINAL QUANTITIES .....</b>	567

General .....	567
Final Cross Section Guidance .....	567
Earthwork Calculations .....	568
Surfacing Data.....	571
Shoulder Construction.....	575
Preconstruction Cross Section Notes .....	575
Zero-Zero Sections .....	575
Interpolated Cross Sections .....	575
Width Of Preliminary And Preconstruction Cross Sections .....	576
Example Of Note .....	576
Extension Made Without Note .....	576
Preparation And Submittal of Records.....	576
Plotting Cross Sections.....	577
<b>1300.06 CONTRACTOR FURNISHED CONSTRUCTION SURVEY .....</b>	<b>578</b>
Construction Staking And Surveying As Contract Item.....	578
Additional Survey Work Payment.....	578
Contractor's Responsibilities Include .....	578
Department Responsibilities .....	579
Special Attention Items.....	579
Documentation .....	579
Contract Administration.....	579
<b>1300.07 ENGINEERING EQUIPMENT, SUPPLIES AND SERVICES .....</b>	<b>580</b>
General .....	580
Responsibility .....	580
Engineering, Surveying And Testing Equipment.....	580
Requisition And Transfer.....	580
Precautions And Maintenance Of Survey Equipment.....	581
Total Stations (Maintenance).....	582
Electronic Digital Theodolite/Transit (Precautions).....	582
Electronic Digital Theodolite/Transit (Maintenance).....	583
Survey Levels (General Precautions) .....	583
Survey Levels (Maintenance) .....	584
Adjustment Of Instruments .....	584
Transporting Equipment.....	585
Damaged Equipment .....	585
Shipping.....	585
Care of Equipment .....	586
Salvage Of Equipment .....	586
Supplies .....	586
Stakes.....	587
Local Purchase Of Services .....	587
Equipment Inventory.....	587
Non-NDOR Equipment Calibration Policy.....	587