

accepted material placed in the stockpile. No deduction will be made for the weight of bitumen used in the mixture.

- B. **Bitumen.** Bitumen will be measured according to Section 109 and the quantity of bitumen will be the number of Tons used in the accepted work.

403.06 BASIS OF PAYMENT.

Payment will be made at the Contract Unit Price for the following:

Pay Item	Pay Unit
Stockpiled Hot Bituminous Mix	Ton
Liquid Asphalt	Ton

This payment will be full compensation for all labor, equipment, and materials necessary to complete the work.

SECTION 405 REMOVE AND SALVAGE BITUMINOUS PAVEMENT

405.01 DESCRIPTION.

This work consists of partially or completely removing a bituminous surface, and loading, hauling, and stockpiling the material.

405.02 CONSTRUCTION REQUIREMENTS.

- A. **Prepare Stockpile Site.** The Contractor shall remove and stockpile all available topsoil, up to a maximum of one foot. The site shall be shaped and compacted so water drains away from the salvaged bituminous stockpile. The Contractor shall furnish, place, compact, and shape to drain, a 6-inch depth of granular material, with less than 30% passing the No. 200 sieve over the stockpile site.
- B. **Remove and Salvage Bituminous Surfacing.** Salvaged bituminous surfacing shall be removed, without contamination, to the specified depth, width, location, and surface tolerance designated. Before removal, the surface shall be cleaned of all debris. Tracked or wheeled loaders may be used for removal. The use of earthmoving equipment such as dozers or scrapers will not be permitted unless the Contractor can satisfactorily demonstrate to the Engineer that no contamination from underlying material will occur.

During the removal operations the Contractor shall control the dust and prevent any littering on the traffic lanes.

If the Project is open to traffic, the edge of the area where the surfacing has been removed shall be tapered up to meet the surface of the adjacent remaining pave-

ment. This shall be done at each end of the removal operation, and at intersecting roadways, at the end of the day.

At the end of the work day all equipment, materials, residue from salvage operations, or other items that may be a hazard to traffic shall be removed from the roadway according to Section 107.05.

- C. **Stockpiling.** The salvaged material shall be stockpiled according to Section 106.06. Each stockpile shall be located to facilitate future processing and access to the material without interference of other stockpiles.

405.03 METHOD OF MEASUREMENT.

- A. **Prepare Stockpile Site.** Prepare Stockpile Site will be measured as a completed and accepted unit item to be bid as a "Lump Sum." The Lump Sum shall be considered payment for removing and stockpiling topsoil; shaping and compacting sub-grade; furnishing, placing, shaping, and compacting granular material; all labor, equipment, materials, and incidental items required for the stockpile site(s). Only one Lump Sum bid item will be paid under each Contract.
- B. **Remove and Salvage Bituminous Surfacing.** Remove and Salvage Bituminous Surfacing will be measured by one of the following:
1. Ton, weighed to the nearest 0.10 Ton of material in the hauling unit.
 2. Cubic Yard, measured to the nearest 1/4 Cubic Yard of material in the hauling unit.
 3. Square Yard, measured to the nearest Square Yard of bituminous surfacing in place prior to milling or removing.

The work of cleaning the surface; removing, loading, hauling (if not a specified Pay Item); stockpiling the removed material; brooming; water used in milling; and all labor, equipment, materials, and incidentals required to complete the Bid Item, will not be measured for payment but will be considered incidental.

- C. **Hauling.** Hauling, if specified as a Pay Item, will be measured by either the Ton-Mile, or the Cubic Yard-Mile.

405.04 BASIS OF PAYMENT.

Payment will be made at the Contract Unit Price for the following:

Pay Item	Pay Unit
Prepare Stockpile Site	Lump Sum
Remove and Salvage Bituminous Surfacing	Ton, Cubic Yard, Square Yard
Hauling	Ton-Mile, Cubic Yard-Mile

This payment will be full compensation for all labor, equipment, and materials necessary to complete the work.