

SECTION 766 MAILBOX ASSEMBLIES

766.01 DESCRIPTION.

This work consists of removing existing mailbox assemblies, furnishing and installing new support systems at locations shown on the Plans, and transferring and fastening the existing or new boxes to the new support systems.

766.02 MATERIALS.

Mailbox support systems and hardware shall be as shown on the Plans. Other support systems meeting the dimensions, metal thickness, strength, and galvanizing requirements are acceptable if they have been crash tested and approved by the Federal Highway Administration (FHWA).

766.03 CONSTRUCTION REQUIREMENTS.

The mailbox owner will be required to furnish a postal service approved mailbox, either new or existing, for installation on the new support system. Maintenance of the new support and mailbox will be the responsibility of the owner.

If construction activities require the removal of the existing support system but delay the installation of the permanent system, the Contractor shall temporarily reinstall the existing system, or furnish and install a temporary system at a location approved by the Engineer.

When construction has progressed sufficiently to allow permanent installation, the Contractor shall install the mailbox assemblies and mailboxes at specified locations and according to details shown on the Plans.

766.04 METHOD OF MEASUREMENT.

Permanent mailbox assemblies will be measured by each Unit complete and in place. The types of assemblies ("single", "double", and "multiple") will be shown on the Plans but will not be measured separately. All types will be grouped together under the Pay Item.

766.05 BASIS OF PAYMENT.

Pay Item	Pay Unit
Mailbox (All Types)	Each

This payment will be full compensation for all labor, equipment, and materials necessary to complete the work.