

606.06. BASIS OF PAYMENT.

Accepted waterproofing, measured as provided above, will be paid for at the contract unit price as follows:

- (A) WATERPROOFING TYPE A SQUARE FEET (SQUARE METERS)
- (B) WATERPROOFING TYPE B SQUARE FEET (SQUARE METERS)
- (C) WATERPROOFING TYPE C SQUARE FEET (SQUARE METERS)
- (D) WATERPROOFING TYPE D SQUARE FEET (SQUARE METERS)

Such payment shall be full compensation for furnishing all materials, equipment, labor, and incidentals to complete the work as specified.

**SECTION 607
ASPHALT PLANKING**

607.01. DESCRIPTION.

This work shall consist of furnishing materials and placing asphalt plank in reasonably close conformity with the dimensions as shown on the Plans or established by the Engineer.

607.02. MATERIALS.

Materials shall meet the requirements specified in the following Subsections of Section 700 - Materials:

Asphalt	708.03
Asphalt Plank	718.01

607.04. CONSTRUCTION METHODS.

First, protect the surface by coating it with hot asphalt.

NOTE: Not less than 50 pounds of asphalt per 100 square feet (2.4 kilograms of asphalt per square meters) shall be used. Place the planks while this asphalt coating is still hot. Heavily coat the edges of the planks with hot asphalt as they are set. Set the planks as closely together as possible, pushing each one tightly against the previously laid plank in such a manner as to completely fill the joints between the planks with hot asphalt—until you squeeze a small amount of asphalt out of the joints. If any joints are not completely closed after all the planks have been placed, fill them with hot asphalt.

When necessary to cut plank lengthwise or at ends, make the cuts in a professional manner.

607.05. METHOD OF MEASUREMENT.

Measure *asphalt planking* by the area in square feet (square meters).

607.06. BASIS OF PAYMENT.

Accepted asphalt planking, measured as provided above, will be paid for at the Contract unit price as follows:

- ASPHALT PLANKING SQUARE FEET (SQUARE METERS)

Such payment shall be full compensation for furnishing all materials, equipment, labor, and incidentals to complete the work as specified.