

SECTION 884 BRIDGE GUARDRAIL RETROFITS

884.01. DESCRIPTION.

This work shall consist of furnishing materials and installing bridge guardrail retrofits in accordance with these specifications and in reasonably close conformity with the locations and dimensions shown on the plans or established by the engineer.

884.02. MATERIALS.

Materials shall meet the requirements of the following specifications:

Portland Cement Concrete	Section 701
Reinforcing Steel	Section 723
Metal Beam Railing	Subsection 732.01
Aluminum Alloy Tubes for Railings	Subsection 732.03
Cast Aluminum Alloy Bridge Railing Posts	Subsection 732.03
Pipe Railing	Subsection 732.04

884.04. CONSTRUCTION METHODS.

Carry out the installation of bridge guardrail retrofits in conformance with the details shown on the plans.

884.05. METHOD OF MEASUREMENT.

Guardrail retrofits and removal, measured by the linear foot (meter), shall include all materials and hardware necessary for installation.

884.06. BASIS OF PAYMENT.

Accepted bridge guardrail retrofit and removal, measured as provided above, will be paid for at the contract unit price as follows:

- (A) BRIDGE GUARDRAIL RETROFIT LINEAR FOOT (METER)
- (B) BRIDGE PARPET RETROFIT LINEAR FOOT (METER)
- (C) REMOVE BRIDGE RAIL & POSTS LINEAR FOOT (METER)

Such payment shall be full compensation for furnishing all materials, equipment, labor, and incidentals required to complete the work as specified.