

SECTION 697—RESET TEMPORARY IMPACT ATTENUATING DEVICES

697.1 DESCRIPTION—This work is the resetting of a temporary impact attenuating device from one construction area to another within the project limits, as indicated.

697.2 MATERIAL—[Section 696.2](#)

697.3 CONSTRUCTION—[Section 696.3](#) and as follows:

Reset temporary impact attenuating device if construction operations require a change in the protection of traffic, or as directed. Store or transport the attenuating devices as required.

697.4 MEASUREMENT AND PAYMENT—Each