

SECTION 936—STRUCTURE MOUNTED SIGNS

936.1 DESCRIPTION—This work is the furnishing and installation of signs of the type indicated, mounted on overhead structures.

936.2 MATERIAL—As shown on the [Standard Drawings](#) and as follows:

- Extruded Channel Signs and Miscellaneous Material—[Section 930.2\(a\)](#)
- Flat Sheet Aluminum Signs with Stiffeners and Miscellaneous Material—[Section 930.2\(b\)](#)
- Flat Sheet Signs—[Section 1103.04](#)
- Other Miscellaneous Material:
 - Angles—[Section 1103.12\(g\)](#)
 - Angles—[Section 1105.02\(a\)2](#), galvanized as specified in [Section 1105.02\(s\)](#).

936.3 CONSTRUCTION—[Section 930.3\(h\)](#), as shown on the [Standard Drawings](#), and as follows:

Remove existing signs only if indicated. Signs that are removed become property of Contractor unless otherwise indicated.

Erect signs level, position correctly on sign brackets, and attach firmly with the necessary mounting hardware as shown in the [Standard Drawings](#).

Erect signs by a method that does not twist, bend, or otherwise deform the signs. Repair or replace damaged signs.

936.4 MEASUREMENT AND PAYMENT—Square Meter (Square Foot) of sign

The unit price includes removal of existing signs and mounting hardware.