

740.1 DESCRIPTION

This work consists of furnishing and stockpiling crushed aggregate.

740.2 MATERIALS

A. Gravel: Crushed gravel shall conform to Section 840.2.A for the type specified.

B. Filler: Filler shall conform to Section 880.2 B.1.

C. Crushed Rock: Crushed rock shall conform to Section 840.2.B.

D. Sand: Sand shall conform to Section 840.2.

740.3 CONSTRUCTION REQUIREMENTS

Filler, sand, crushed rock, or crushed stone shall be proportioned and blended with the crushed gravel by feeding it, in accurately measured quantities, onto a belt leading from the crusher. Spreading filler, sand, crushed rock, or crushed stone over the tops of gravel pits or dumping it into the hoppers at the crushing plants will not be permitted.

Rejection of suitable oversize material will not be permissible. Suitable oversize material is defined as hard pebbles or rock fragments passing a six inch (150 mm) slotted opening.

Scales shall be placed at an approved location at each stockpile site.

The crushed aggregate shall be placed in neatly shaped storage piles on suitably prepared sites.

740.4 METHOD OF MEASUREMENT

Crushed aggregate will be measured to the nearest 0.1 ton (0.1 metric ton), furnished, delivered, and neatly stockpiled.

740.5 BASIS OF PAYMENT

Crushed aggregate will be paid for at the contract unit price per ton (metric ton). Payment will be full compensation for furnishing materials, labor, equipment, and incidentals required.

THIS PAGE INTENTIONALLY LEFT BLANK