

## SECTION 01741

# FINAL CLEANUP

### **PART 1 GENERAL**

#### **1.1 SECTION INCLUDES**

- A. Finish and clean all areas disturbed by construction.

#### **1.2 RELATED SECTIONS**

- A. Section 01455: Materials Quality Requirements.

#### **1.3 PAYMENT PROCEDURES**

- A. All costs associated with Final Cleanup are incidental to other items of work and no separate measurement or payment will be made.
- B. When the Engineer directs clean up work outside the area disturbed by the Contractor, this will be paid as extra work.

#### **1.4 REFERENCES**

- A. AASHTO Roadside Design Guide.

### **PART 2 PRODUCTS Not used**

### **PART 3 EXECUTION**

#### **3.1 CLEANING PROCEDURES**

- A. Do not drag, push, or scrape along or across the final pavement surface.
- B. Only use equipment with pneumatic tires on the final pavement surface.

- C. Determine the Safety Zone using the current AASHTO Roadside Design Guide.
  - 1. No protrusions or depressions greater than 3 inches are allowed within the clear zone (rocks, boulders, ridges, stumps, etc.).
  - 2. Remove trees and provide proper sight distance.
- D. Within drainage ditches: clean all debris and obstructions and dispose of material removed.
- E. On fill slopes: cover large rocks or boulders with fine material from roadway excavation or borrow. On slopes steeper than 3:1 beyond the clear zone, clean up of large rocks and boulders may not be required.
- F. On cut slopes: do not undercut the slope. Remove all overhanging rocks. On slopes steeper than 4:1 beyond the clear zone, solid ledge rock or partially buried boulders 0.33 yd<sup>3</sup> or more may be left in place.
- G. Within borrow and local material source sites: Refer to Section 01455.
- H. Within right-of-way limits:
  - 1. Remove all dead trees and shrubs.
  - 2. Prune trees and shrubs as required.
  - 3. Trim and shape trees to provide horizontal sight distance and 20 ft vertical clearances above the roadway.
  - 4. Remove undesirable live trees, shrubs, and all fruit trees to a depth of 18 inches below natural ground.
  - 5. Dispose of trash and debris.
- I. For staging and office sites:
  - 1. Clean up and finish in accordance with the requirements as described for the finishing of local material source sites under Section 01455, including seeding and mulching.

END OF SECTION