

SECTION 01741

FINAL CLEANUP

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Finish and clean all areas disturbed by construction.

1.2 RELATED SECTIONS

- A. Section 01455: Materials Quality Requirements.

1.3 PAYMENT PROCEDURES

- A. Clean up outside the area disturbed by the Contractor will be paid as extra work.

1.4 REFERENCES

- A. AASHTO Roadside Design Guide.

PART 2 PRODUCTS Not used.

PART 3 EXECUTION

3.1 CLEANING PROCEDURES

- A. Do not drag, push or scrape along or across the final pavement surface.
- B. Only use equipment with pneumatic tires on the final pavement surface.
- C. Determine the Safety Zone using the current AASHTO Roadside Design Guide.
 - 1. No protrusions or depressions greater than 3 inches are allowed within the clear zone (rocks, boulders, ridges, stumps, etc.).
 - 2. Remove trees and provide proper sight distance.
- D. Within drainage ditches: clean all debris and obstructions and dispose of material removed.

- E. On fill slopes: cover large rocks or boulders with fine material from roadway excavation or borrow. On slopes steeper than 3:1 beyond the clear zone, clean up of large rocks and boulders may not be required.
- F. On cut slopes: do not undercut the slope. Remove all overhanging rocks. On slopes steeper than 4:1 beyond the clear zone, solid ledge rock or partially buried boulders 0.33 yd³ or more may be left in place.
- G. Within borrow pits: Refer to Section 01455, article, "Finishing Local Material Source Sites."
- H. Within right-of-way limits:
 - 1. Remove all dead trees and shrubs.
 - 2. Prune trees and shrubs as required.
 - 3. Trim and shape trees to provide horizontal sight distance and 20 feet vertical clearances above the roadway.
 - 4. Remove undesirable live trees, shrubs, and all fruit trees to a depth of 18 inches below natural ground.
 - 5. Dispose of trash and debris.

END OF SECTION