

SECTION 301—CLEARING AND GRUBBING**301.01—Description.**

This work shall consist of clearing, grubbing, removing, and disposing of vegetation, debris, and other objects within the construction limits except for vegetation and objects that are designated to be preserved, protected, or removed in accordance with the requirements of other provisions of these specifications.

301.02—Procedures.

If approved by the Engineer, the Contractor may clear and grub to accommodate construction equipment within the right of way up to 5 feet beyond the construction limits at his own expense. The Contractor shall install erosion and siltation control devices prior to beginning grubbing operations.

The surface area of earth material exposed by grubbing, stripping topsoil, or excavation shall be limited to that necessary to perform the next operation within a given area. Grubbing of root mat and stumps shall be confined to the area which excavation shall be performed within 15-days following grubbing.

Stumps, roots, other perishable material, and nonperishable objects that will be less than 5 feet below the top of earthwork within the area directly beneath the pavement and shoulders shall be removed. However, such material and objects that will be more than 5 feet below the top of earthwork within the area directly beneath the pavement and shoulders and all such material and objects beneath slopes of embankments shall be left in place unless removal is necessary for installation of a structure. The top of stumps left in place shall be not more than 6 inches above the existing ground surface or low water level.

Branches of trees that overhang the roadway or reduce sight distance and that are less than 20 feet above the elevation of the finished grade shall be trimmed using approved tree surgery practices in accordance with the requirements of Section 601.

Vegetation, structures, or other items outside the construction limits shall not be damaged. Trees and shrubs in ungraded areas shall not be cut without the approval of the Engineer.

Combustible cleared and grubbed material shall be disposed of in accordance with the following:

- (a) Trees, limbs, and other timber having a diameter of 3 inches and greater shall be disposed of as saw logs, pulpwood, firewood, or other usable material; however, treated timber shall not be disposed of as firewood. Not more than 2 feet of trunk shall be left attached to grubbed stumps.

When specified that trees or other timber is to be reserved for the property owner, such material shall be cut in the lengths specified and piled

where designated, either within the limits of the right of way or not more than 100 feet from the right-of-way line. When not reserved for the property owner, such material shall become the property of the Contractor.

- (b) When specified on the plans or where directed by the Engineer, material less than 3 inches in diameter shall be used to form brush silt barriers when located within 500 feet of the source of such material. Material shall be placed approximately 5 feet beyond the toe of fill in a strip approximately 10 feet wide to form a continuous barrier on the downhill side of fills. Where selective clearing has been done, material shall be piled, for stability, against trees in the proper location. On the uphill side of fills, brush shall be stacked against fills at approximately 100-foot intervals in piles approximately 5 feet high and 10 feet wide. Any such material not needed to form silt barriers shall be processed into chips having a thickness of not more than 3/8 inch and an area of not more than 6 square inches and may be stockpiled out of sight of any public highway for use as mulch.
- (c) Stumps and material less than 3 inches in diameter that are not needed to form silt barriers and that are not processed into wood chips shall be handled in accordance with the requirements of Sections 106 and 107.

301.03—Measurement and Payment.

Clearing and grubbing will be measured and paid for in accordance with one of the following methods, as specified:

- (a) **Lump Sum Basis:** No measurement of the area to be cleared and grubbed will be made.
- (b) **Acre basis:** The work to be paid for will be the number of acres, computed to the nearest 1/10 of an acre, actually cleared and grubbed. Areas within the limits of any existing roadway or local material pit will not be measured.
- (c) **Unit basis:** The work to be paid for will be determined by the actual count of trees, stumps, structures, or other obstructions removed.

These prices shall include disposing of cleared and grubbed material.

When clearing and grubbing is not a pay item, the cost thereof shall be included in the price for other appropriate pay items. Allowance will not be made for clearing and grubbing borrow pits or other local material pits.

Payment will be made under:

Pay Item	Pay Unit
Clearing and grubbing	Lump sum, acre, or unit