

## SECTION 302—DRAINAGE STRUCTURES

### 302.01—Description.

This work shall consist of installing pipe culverts, endwalls, box culverts, precast concrete and metal arches, storm drains, drop inlets, manholes, spring boxes, junction boxes, and intake boxes and removing and replacing existing structures in accordance with the requirements of these specifications and in reasonably close conformity with the lines and grades shown on the plans or as established by the Engineer.

### 302.02—Materials.

- (a) **Pipe** shall conform to the requirements of Section 232 and shall be furnished in accordance with the diameter, wall thickness, class, and strength or corrugation specified for the maximum height of fill to be encountered along the length of the pipe culvert, storm drain, or sewer.
- (b) **End sections** shall conform to the applicable requirements of Section 232. End sections used with rigid pipe shall be concrete. End sections used with asphalt-coated or paved pipe shall not be asphalt coated or paved.
- (c) **Pipe fittings**, such as tees, elbows, wyes, and bends, shall conform to the applicable requirements of Section 232. Fittings shall be of the same type, class, thickness, gage, and strength as the line in which they are used.
- (d) **Steel grates, steel frames and structural steel** shall conform to the requirements of Section 226 and shall be galvanized in accordance with the requirements of Section 233.
- (e) **Concrete blocks** shall conform to the requirements of Section 222 for masonry blocks.
- (f) **Brick** shall conform to the requirements of Section 222.
- (g) **Hydraulic cement mortar** shall conform to the requirements of Section 218.
- (h) **Cast-in-place concrete** shall conform to the requirements of Section 217 for Class A3.
- (i) **Bedding material** shall conform to the requirements of Section 205.
- (j) **Joint material and gaskets** shall conform to the requirements of Section 212.

- (k) **Gray-iron castings** shall conform to the requirements of Section 224.
- (l) **Reinforcing steel** shall conform to the requirements of Section 223, Grade 40 or 60.
- (m) **Curing materials** shall conform to the requirements of Section 220.

### 302.03—Procedures.

Excavation and backfill operations shall be performed in accordance with the requirements of Section 303. Foundation exploration shall be performed in accordance with the requirements of Section 401 unless otherwise provided herein. Concrete construction shall conform to the requirements of Section 404. Reinforcing steel placement shall conform to the requirements of Section 406. Bearing pile operations shall be performed in accordance with the requirements of Section 403. When specified on the plans or directed by the Engineer, a temporary diversion channel shall be constructed to facilitate installation of a pipe or box culvert.

When lift holes are provided in concrete pipe or precast box culverts, the Contractor shall install a lift hole plug furnished by the manufacturer in accordance with the requirements of Section 232.02 (a) 1. After pipe installation and prior to backfilling, plugs shall be installed from the exterior of the pipe or box culvert and snugly seated.

- (a) **Pipe Culverts:** Not more than one type of pipe shall be used in any one pipeline.

When field cutting corrugated metal pipe is permitted by the Engineer, damaged areas of the protective coating shall be repaired in accordance with the requirements of Section 233.

1. **Jacked method:** The Contractor shall submit to the Engineer a complete plan and schedule for jacked pipe installation prior to beginning such work. The submission shall include complete details of sheeting, shoring, and bracing for protecting the roadbed and materials and equipment. The Contractor shall not proceed with pipe installation until the plan has been reviewed by the Engineer.

When work is stopped, the heading shall be bulkheaded.

The jacked method shall be by means of tunneling or boring. The jacked tunneling method shall be applicable for installing concrete pipe 30 through 108 inches in diameter and smooth-wall steel pipe 30 through 48 inches in diameter. The jacked boring method shall be applicable for installing concrete pipe 12 through 108 inches in diameter and smooth-wall steel pipe 12 3/4 through 48 inches in diameter.

Pipe shall have a design strength and wall thickness so as to withstand the jacking operation.

Construction shall be performed in such a manner that the ground surface above the pipe line will not settle. Installation of the pipeline shall immediately follow heading or tunneling excavation. Voids occurring behind the pipe during installation shall be filled with hydraulic cement grout, placed under pressure, upon completion of the jacking operation.

Joint sealant material on concrete pipe shall be placed ahead of the jacking frame. At his own expense, the Contractor shall replace or repair, as directed by the Engineer, pipe that is damaged during jacking operations. Joints of steel pipe shall be butt welded, watertight, as installation progresses.

2. **Open trench method:**

- a. **Foundation:** The foundation shall be explored below the bottom of the excavation to determine the type and condition of the foundation. However, explorations need not be made for routine entrance or crossover pipe 12 through 30 inches in diameter that is to be installed under fills 15 feet or less in height. Foundation exploration shall extend to a depth equal to 1/2 inch per foot of fill height or 8 inches, whichever is greater. The Contractor shall report findings of foundation exploration to the Engineer for approval prior to placing pipe.

Where unsuitable foundation is encountered at the established grade, as determined by the Engineer, such material shall be removed and replaced.

Backfill for areas where unsuitable material has been removed shall be placed and compacted in accordance with the requirements of Section 303.04(g).

- b. **Bedding:** Bedding material for culvert foundations, including foundations in soft, yielding or otherwise unsuitable material, shall be aggregate No. 25 or 26 conforming to the requirements of Section 205 except where standing or running water is present in the pipe foundation excavation, then pipe bedding material shall be aggregate No. 57 for the depth specified on the plans or as directed by the Engineer, capped with 4 inches of aggregate No. 25 or 26. Where such conditions are discovered in the field and the Contractor is directed by the Engineer to use No. 57 stone, No. 57 stone will be paid for at the existing contract unit price, or if not in the contract, in accordance with Section 109.05.

Pipe bedding shall be lightly and uniformly compacted and shall be carefully shaped so that the lower section of the pipe exterior is in contact with the bedding material for at least ten percent of the overall height of the pipe. Bedding material shall be shaped to accommodate the bell when bell and spigot pipe is used. The depth of bedding material shall be at least 4 inches.

- c. **Placing pipe:** Pipe shall be placed beginning at the downstream end of the pipeline. The lower segment of pipe shall be in contact with the shaped bedding for its entire length. Bell or groove ends of rigid pipe shall be placed facing upstream.

Paved or partially lined pipe shall be placed so that the longitudinal centerline of the paved segment coincides with the flow line.

Pipe will be inspected before backfill is placed. Pipe found to be out of alignment, unduly settled, or damaged shall be taken up and reinstalled or replaced.

- d. **Joining pipe:**

- (1) **Rigid pipe:** The method of joining pipe sections shall be such that ends are fully entered and inner surfaces are reasonably flush and even.

Joints shall be sealed with any one or combination of the following to form a leak-resistant joint: rubber, preformed plastic, or mastic gaskets from the Department's approved list; oakum and mortar; oakum and joint compound; or cold-applied pipe joint sealer.

Rubber ring gaskets shall be installed to form a flexible, leak-resistant seal. Where oakum is used, the joint shall be caulked with this material and then sealed with mortar or joint compound.

- (2) **Flexible pipe:** Flexible pipe sections shall be aligned and firmly joined by approved coupling bands to form a leak-resistant joint.

- e. **Structural plate pipe, pipe arches, and arches:** Erection shall be in accordance with the manufacturer's assembly diagrams and instruction sheets. Splices in the haunch areas of structural plate pipe arches shall be constructed using the reverse shingle method or the side plates shall be provided without longitudinal

seams in the haunch areas. The complete line shall be assembled before backfill is placed. Bolts shall be tightened to a torque of 150 to 250 foot-pounds. Elongated pipe shall be erected with the long diameter in a vertical position. If spiraling occurs during erection, bolts shall be loosened and the pipe assembly adjusted to the correct position.

- f. **Arch substructures, end walls, and pipe spillouts:** Each side of an arch shall rest in a groove formed into the masonry or on a galvanized angle or channel securely anchored to or embedded in the substructure. Where the span of the arch is more than 15 feet or the skew angle is more than 20 degrees, a metal bearing surface having a width at least equal to the depth of the corrugation shall be provided.

Metal bearings for arches shall be cold-formed galvanized channel conforming to the requirements of ASTM A569 at least 3/16 inch in thickness, with the horizontal leg securely anchored to the substructure at points spaced on centers of not more than 24 inches. When the metal bearing is not embedded in a groove in the substructure, one vertical leg shall be punched to allow bolting to the bottom row of plates.

- g. **Backfilling:** Backfill material shall be placed alongside the pipe culvert in uniform layers not more than 6 inches, before compaction, and each layer shall be thoroughly compacted as specified in Section 303.04(g). Material shall be compacted thoroughly under haunches of pipe culverts. Each layer shall be compacted by rolling, tamping with mechanical rammers, or hand tamping with heavy metal tampers with a face of at least 25 square inches. If vibratory rollers are used in the backfill operation, vibratory motors shall not be activated until at least 3 feet of backfill has been placed and compacted over the pipe.

Puddling will not be permitted. Rock more than 2 inches in its greatest dimension shall not be placed within 12 inches of pipe.

Backfill and compaction shall be advanced simultaneously on both sides of the pipe. The fill above the top of the pipe shall be completed as specified for embankment construction unless the induced trench method of installation is used.

Culvert backfill material shall conform to the Standard Drawings for Method A Bedding for the type of culvert and soil conditions. Class I Backfill material shall be crusher run aggregate size no. 25 or 26, flowable backfill or compacted soils conforming to AASHTO M145, Group A-1, A-2-4, A-2-5, A-2-6,

or A-3 (GW, GP, SW, GM and SM) only. Class II backfill material shall have a minimum CBR of 20 and may be material excavated from within the project limits or may be obtained outside of the project limits when not present onsite. Where trench excavation meets the requirements of Class I or Class II backfill material the Contractor will be required to use trench excavation prior to using borrow material.

Regular backfill material outside of the neatlines of the Class I or Class II backfill areas shown on the Standard Drawings shall be regular excavation conforming to Section 303. Regular and classified backfill shall be placed in uniform layers not more than 6 inches before compaction and each layer shall be thoroughly compacted as specified in Section 303.04(g). Class I backfill material shall be thoroughly compacted under the haunches of pipe culverts. Each layer shall be compacted by rolling, tamping with mechanical rammers, or hand tamping with heavy metal tampers with a face of at least 25 square inches. If vibratory rollers are used in the backfill operations, vibratory motors shall not be activated until at least 3 feet of backfill has been placed and compacted over the pipe. Backfill and compaction shall be advanced simultaneously on both sides of the pipe. The fill above the top of the pipe shall be completed as specified for embankment construction.

Where borrow material is used for backfill operations, the volume of Class I and Class II backfill material shall be deducted from the volume of borrow material prior to payment.

Concrete pipe with a height of cover greater than that shown in the Standard PC-1 table for Class V pipe shall be Special Design pipe with Method A bedding and Class I and II backfill material.

- (b) **Precast Drainage Structures:** Submittal of designs for precast items included in the standard drawings will not be required provided fabrication is in accordance with the standard details. Submittal of designs for precast box culverts on the Department's approved list will not be required provided the Contractor submits a certification that the item will be fabricated in accordance with the preapproved design drawings.

Requests for approval of a precast design shall include detailed plans and supporting computations that have been reviewed and approved by a registered Professional Engineer having at least 5 years experience in structural design of the type of precast structures or components proposed. Concrete shall conform to Section 217 unless otherwise specified and have a design strength at 28 days of at least 4,000 pounds per square inch and an air content of  $6 \pm 2$  percent. The design of the concrete mixture and the

method of casting, curing, handling, and erecting shall be subject to review by the Engineer. Precast units may be shipped after reaching 85 percent of the design strength as determined by control cylinders tested in accordance with the requirements of Section 404. However, units shall retain their structural integrity during shipment and shall be subject to inspection at the job site. Approval to use precast units shall not be construed as waiving the size and weight hauling limitations of Section 105.14.

1. **Standard precast drainage units** shall conform to the material requirements of AASHTO M199 and the following:
  - a. If the grade on the adjacent gutter is less than 1.5 percent, the grade on the invert of the throat section of the inlet shall be at least 1.5 percent. Precast throats having flat inverts will be permitted in sag locations provided the total length of the required throat opening does not exceed 6 feet.
  - b. Pipe openings in precast drainage units shall not exceed 4 inches at any given point between the outside wall of the pipe and the opening in the precast unit regardless of their angle of intersection or the shape of the pipe. Pipe openings shall be formed, drilled, or neatly cut.
  - c. The Contractor shall use concrete or brick, masonry block, concrete pipe cutoffs, or native stone in conjunction with mortar to fill the void between pipe culverts and precast structures. With the exception of concrete, such materials shall be thoroughly wetted, bonded with mortar and the remaining exterior and interior voids filled with mortar to the contour of the precast structure.
  - d. When precast units are to be located adjacent to the subbase or base course, units with chambers shall be provided with weep holes 3 inches in diameter and hardware cloth and shall be located to drain the subbase or base.
  - e. Precast units located adjacent to cast-in-place concrete items, such as flumes, ditches, and gutters, shall be connected to the adjacent unit by means of No. 4 smooth steel dowels spaced on approximately 12-inch centers throughout the contact length and extending at least 4 inches into both the precast unit and the cast-in-place item. If holes to receive the dowels are provided in the precast unit, they shall be not more than 5/8 inch in diameter. Other methods of providing the connection, such as keyed joints, shall be approved by the Department prior to fabrication.
  - f. The chamber section shall be installed in the plumb position. The throat and top sections shall have positive restraints, such as adjacent concrete, pavement, or soil on all sides to prevent displace-

ment and shall have a positive interlock, such as dowels, with the chamber section. The throat and top sections shall be installed to conform with the normal slope of the finished grade, and may be canted up to a maximum grade of 10 percent. The chamber may be built up a maximum of 12 inches at any point to provide for complete and uniform bearing of the throat and top sections on the chamber flat slab top or other approved top section. The built up section shall be constructed using whole concrete spacer units where feasible, and partial and whole sections of concrete block or brick with high strength grout and mortar. High strength grout shall be used to provide the final grade adjustment and uniform bearing. The width of the built up section shall match the wall thickness of the chamber section. The concrete block and brick shall be thoroughly bonded with mortar and the inside and outside of the built-up section shall be plastered with mortar except that the concrete spacer unit shall not be plastered.

2. **Precast arches** shall conform to the applicable requirements of AASHTO's *Standard Specifications for Highway Bridges* with the following modifications:

- a. **Combination of loads:** For service load design: E: vertical loads: 1.00; lateral loads: 1.00 and 0.5 (check both loadings).

For load factor design: E: vertical loads: 1.00; lateral loads: 1.30 and 0.5 (check both loadings).

- b. **Protection against corrosion:** The concrete cover of reinforcement shall be at least 1 1/2 inches.

In corrosive or marine environments or other severe exposure conditions, reinforcement shall be epoxy coated in accordance with the requirements of Section 223.

Exposed reinforcing bars, inserts, and plates intended for bonding with future extensions shall be protected from corrosion as directed by the Engineer.

Reinforcement shall be designed and detailed in consideration of fabrication and construction tolerances so that the minimum required cover and proper positioning of reinforcement shall be maintained.

- c. **Anchorage:** Sufficient anchorage shall be provided at the terminus of lines of precast units. Anchorage may consist of a cast-in-place end section at least 3 feet in length with a headwall or collar around the precast unit(s) provided adequate connection can be made between the collar and units.

- d. **Joints:** Joints between units shall be sealed by preformed plastic or mastic gaskets or grout. When preformed gaskets are used, they shall be of a type listed on the Department's approved products list.
  - e. **Pipe openings:** Pipe openings will not be allowed in the precast arch but may be provided through the wingwalls. When required, openings shall conform to the requirements of (b)1.b. herein.
3. **Precast box culverts** shall conform to the applicable requirements of AASHTO M259 or M273 and AASHTO's *Standard Specifications for Highway Bridges* with the following modifications:
- a. **Combination of loads:** For service load design or load factor design: E: new reinforced concrete boxes: vertical loads: 1.00; lateral loads: 1.00 and 0.5 (check both loadings).
  - b. **Protection against corrosion:** The following minimum concrete cover shall be provided for reinforcement: For boxes with more than 2 feet of fill over the top slab: 1 1/2 inches. For boxes with less than 2 feet of fill over the top slab: top reinforcement of top slab: 2 1/2 inches; bottom reinforcement of top slab: 2 inches; all other reinforcement: 1 1/2 inches.

The minimum cover for reinforcement may be reduced by not more than 1/2 inch, provided the reinforcement having reduced cover is epoxy coated or the concrete surfaces adjacent to the reinforcement are coated in accordance with the requirements of Section 416.

Reinforcing steel for box culverts used in 0 to 2 foot fills, used in corrosive or marine environments or used in other severe exposure conditions shall be epoxy coated. When epoxy coated reinforcing steel is required due to these conditions, the minimum cover specified shall not be reduced.

- c. The type of sealant used in joints between units shall be from the Department's approved list of preformed plastic or mastic gaskets.

Where double or greater lines of precast units are used, a buffer zone of 3 to 6 inches between lines shall be provided. This buffer zone shall be backfilled with porous backfill conforming to the requirements of Section 204. The porous backfill shall be drained by a 3-inch diameter weep hole, formed by non-rigid tubing, located at the top of the bottom haunch, centered in the outlet end section and at approximately fifty foot intervals along the length of the box. Weep holes shall be covered with a

3-foot square section of filter barrier cloth firmly attached to the outside of the box. A 3-foot width of filter barrier cloth shall also be centered over the buffer zone for the entire length of the structure after placement of the porous backfill material. Filter barrier cloth shall conform to the requirements of Section 245.

Forming weep holes and furnishing and placing of the filter barrier cloth shall be included in the price bid per linear foot for the Precast Box Culvert.

- d. At the terminus of precast units, sufficient anchorage shall be provided. This anchorage may consist of a cast-in-place end section at least 3 feet in length with a headwall and curtain wall or a collar cast-in-place around the units provided adequate connection can be made between the collar and units.

When the ends of precast units are skewed, the end section shall be cast monolithically. The skew may be provided by forming, saw cutting, or other methods approved by the Engineer. Regardless of the method used, the variation in the precast unit from the exact skew shall be not greater than 1 1/2 inches at any point.

- e. Pipe openings shall conform to the requirements of 1.b. herein.
- f. Bedding shall be at least 6 inches in thickness.

- (c) **Drop Inlets, Manholes, Spring Boxes, Intake Boxes, and End Walls:** Masonry construction shall not be initiated when the air temperature is below 40 degrees F in the shade.

Brick and concrete block masonry shall be placed so that each unit will be thoroughly bonded with mortar. Joints shall be full-mortar joints not more than 1/2 inch in width. Where brick masonry is used, headers and stretchers shall be arranged to bond the mass fully. Every seventh course shall be placed entirely with headers. Inside joints shall be neatly pointed, and the outside of such walls shall be plastered with mortar as they are placed.

Iron fittings entering the masonry shall be placed as the work is built up, thoroughly bonded, and accurately spaced and aligned.

Inlet and outlet pipe connections shall conform to the same requirements as the pipe to which they connect and shall be of the same size and kind. Pipe sections shall be flush on the inside of the structure wall and shall project outside sufficiently for proper connection with the next pipe section. Masonry shall fit neatly and tightly around the pipe.

Immediately following finishing operations, hydraulic cement concrete shall be cured and protected in accordance with the requirements of Section 316.04(j).

Backfilling shall be performed in accordance with the requirements of Section 303.04(g). Surplus material shall be removed, and the site shall be left in a neat and orderly condition.

When grade adjustment of existing structures is specified, frames, covers, and gratings shall be removed and the walls shall be reconstructed as required. Cleaned frames shall be reset at the required elevation. Upon completion, each structure shall be cleaned of silt, debris, and foreign matter and shall be kept clear of such accumulation until final acceptance.

### **302.04—Measurement and Payment.**

**Pipe culverts** will be measured in linear feet. The quantity will be determined by counting the number of sections and multiplying by the length of the section used. When a partial section is required, the actual length of the partial section will be measured in place.

**Structural plate pipe and pipe arches** will be measured in linear feet along the invert line.

**Pipe tees and elbows** will be measured in linear feet of pipe.

**Pipe reducers** will be measured in linear feet of pipe for payment at the larger pipe size.

**Pipe** shall be paid for at the contract unit price per linear foot. This price shall include excavating, when not a pay item, sheeting, shoring, dewatering, disposing of surplus and unsuitable material, backfill material, except Class I and II material, and restoring existing surfaces. When unit prices for extended pipelines are not specified, the unit price for new pipe of the same size shall apply. When not a pay item, the cost of the temporary relocation of a stream to facilitate the installation of a drainage facility shall be included in the price for the related pipe or box culvert. The cost of fittings, anti-seepage collars and anchor blocks shall be included in the price for the applicable type of culvert.

**Jacked pipe** will be measured in linear feet to the nearest 1/10 of a foot and will be paid for at the contract unit price per linear foot.

**Reinstalled pipe** will be measured in linear feet along a line parallel to the flow line and will be paid for at the contract unit price per linear foot of pipe and per cubic yard of minor structure excavation. This price shall include excavation involved in removing pipe, hauling, cleaning, relaying, backfilling, necessary cutting for joining to other sections of pipe, furnishing new coupling bands, disposing of surplus excavation, and replacing any otherwise usable sections damaged or broken because of the negligence of the Contractor.

**End sections and pipe spillouts** will be measured in units of each, complete-in-place, and will be paid for at the contract unit price per each.

**End walls and arch substructures** will be measured in cubic yards of concrete and pounds of reinforcing steel, except that EW-12 endwalls will be measured in units of each complete-in-place. Endwalls and arch substructures will be paid for at the contract unit price per cubic yard of miscellaneous concrete and per pound of reinforcing steel, except that crack control bars shall be included in the price bid for miscellaneous concrete and standard EW-12 endwalls will be paid for at the contract unit price per each.

**Minor structure excavation** will be measured and paid for in accordance with the requirements of Section 303.06.

**Bedding material** shall be measured and paid for at the contract unit price per ton for the type(s) specified, which price shall be full compensation for furnishing, placing, compacting, and shaping the material. Section 104.02 that pertains to adjusting contract unit prices because of alterations of contract quantities will not apply to this pay item.

**Class I backfill material** shall be measured and paid for at the contract unit price per cubic yard or ton, which price will be full compensation for furnishing, placing, compacting and shaping the material in accordance with PB-1 Standards. Section 104.02 that pertains to adjusting contract unit prices because of alterations of contract quantities will not apply to this pay item.

**Class II backfill material** shall be measured and paid for at the contract unit price per cubic yard or ton, which price will be full compensation for furnishing, placing, compacting and shaping the material in accordance with the PB-1 Standards. Section 104.02 that pertains to adjusting contract unit prices because of alterations of contract quantities will not apply to this pay item.

**Box culverts** will be measured in cubic yards of concrete and pounds of reinforcing steel and will be paid for at the contract unit price per cubic yard of concrete and per pound of reinforcing steel. These prices shall include waterproofing.

**Precast box culverts** will be measured in linear feet along the center line of the barrel from face of curtain wall to face of curtain wall and will be paid for at the contract unit price per linear foot. This price shall include designing, casting, reinforcing, installing, waterproofing, sealing joints, anchoring, and providing buffer zones for multiple lines.

If the Contractor elects to furnish and install precast box culverts or precast arches, payment will be made for the original quantities shown on the plans for cast-in-place units. No additional compensation will be made for casting, prestressing, or shipping precast units or performing additional work, such as waterproofing, epoxy coating, or joint sealing, required as a result of the substitution.

**Grates and frames** will be measured in units of each and will be paid for at the contract unit price per each.

**Pipe grate** will be measured in linear feet and will be paid for at the contract unit price per linear foot. This price shall include fabricating, furnishing, galvanizing, and installing.

**Drop inlets and intake boxes** will be measured as complete units, including the frame and grate or cover, and will be paid for at the contract unit price per each. The contract unit price for drop inlets will be adjusted at the rate of 5 percent per foot for increases or decreases in the depth indicated on the plans except that no adjustment will be made for changes amounting to less than 6 inches in the height of a single drop inlet. Where curb or curb and gutter extend along the drop inlet, the contract unit price for drop inlets shall include that part of the curb or gutter within the limits of the structure.

**Base sections of pipe tee units used as drop inlets and manholes** will be measured in linear feet horizontally and will be paid for at the contract unit price per linear foot of pipe specified. The riser section and additional costs for the tee shall be included in the price for the drop inlet or manhole.

**Manholes** will be measured in linear feet, vertical measure, from top of foundation slab to top of masonry on which the casting frame is placed. However, when manholes are constructed as tee sections, measurement will be made to the pay limits shown on the plans. Manholes will be paid for at the contract unit price per vertical linear foot exclusive of frame and cover.

**Concrete spring boxes** will be measured in cubic yards of concrete, pounds of reinforcing steel, and linear feet of pipe and will be paid for at the contract unit price per cubic yard of concrete, per pound of reinforcing steel, and per linear foot of pipe.

**Junction boxes** will be measured in cubic yards of concrete, pounds of reinforcing steel, pounds of structural steel, and each complete frame and cover assembly and will be paid for at the contract unit price per cubic yard of concrete, per pound of reinforcing steel, per pound of structural steel, and per each frame and cover assembly.

**Casting frames and covers** will be measured in units of one complete frame and cover and will be paid for at the contract unit price per unit.

**Reconstructed manholes** will be measured as a complete unit and will be paid for at the contract unit price per each.

**Precast arches** will be measured in linear feet along the centerline of the invert from face of headwall to face of headwall. When a pay item, precast arches will be paid for at the contract unit price per linear foot. This price shall include designing, forming, casting, reinforcing, excavating, wingwalls, installing, waterproofing, sealing joints, anchoring and bedding, and providing buffer zones for multiple lines. The cost for cast-in-place work other than that specified on the plans shall be included in the price for precast arches.

**Temporary diversion channel lining** will be measured in square yards for the class specified and will be paid for at the contract unit price per square yard. This price shall include installing the channel lining and removal when no longer required.

**Temporary diversion channel excavation** will be measured in cubic yards and will be paid for at the contract unit price per cubic yard. This price shall include excavation, temporary pipe culverts and removal of pipe culverts when no longer required, backfilling, site restoration including regrading and seeding.

Excavation, backfill, and disposal of unsuitable or surplus material for drop inlets, intake boxes, manholes both new and reconstructed, spring boxes, junction boxes, and base sections of pipe tee units used as drop inlets and manholes will not be measured for separate payment, and the cost thereof shall be included in the bid price for such items. In the event steps or invert shaping are required, the cost thereof shall also be included in the price for such items.

**Storm Water Management Drainage Structure** will be measured in linear feet, vertical measure, from top of concrete foundation to the top of the concrete cover. The price bid shall include class A3 concrete, reinforcing steel, concrete cover, debris rack, orifice, steps when required, and class A1 riprap.

**Storm Water Management, Riser Pipe** will be measured in linear feet for the size specified and will be paid for at the contract unit price per linear foot. The bid price shall include the riser pipe, perforated pipe, steel plate, debris rack, orifice, grate and cover when required, and class A1 riprap.

**Temporary Sediment Riser Pipe** will be measured in linear feet for the size specified and will be paid for at the contract unit price per linear foot. The price shall include the riser pipe, steel plate, perforated pipe, debris rack, orifice and class A1 riprap, and vortex device when required.

**Storm Water Management Dam** will be measured and paid for at the contract unit price per cubic yards of concrete and pounds of reinforcing steel.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
Pipe (Size and type)	Linear foot
Structural plate arch (Size)	Linear foot
Jacked pipe (Size)	Linear foot
Reinstalled pipe	Linear foot
End section (Standard and size)	Each
Pipe spillout (Standard)	Each
Concrete (Class)	Cubic yard
Reinforcing steel	Pound
End wall grate and frame (Standard)	Each
Bedding material, aggregate No. ( )	Ton

<u>Pay Item</u>	<u>Pay Unit</u>
Class I backfill material	Cubic yard or Ton
Class II backfill material	Cubic yard or Ton
Precast box culvert (Size)	Linear foot
End wall pipe grate (Type)	Linear foot
Drop inlet (Standard and length)	Each
Intake box (Standard)	Each
Structural steel (Type)	Pound
Manhole (Standard)	Linear foot
Frame and cover (Standard)	Each
Reconstructed manhole	Each
Precast arch (Size)	Linear foot
Temporary diversion channel lining (Class)	Square yard
Temporary diversion channel excavation	Cubic yard
Endwall standard EW-12	Each
Storm water management drainage structure (type)	Linear foot
Storm water management riser pipe (size)	Linear foot
Temporary sediment riser pipe (size)	Linear foot

## SECTION 303—EARTHWORK

### 303.01—Description.

This work shall consist of constructing roadway earthwork in accordance with these specifications and in reasonably close conformity with the specified tolerances for the lines, grades, typical sections, and cross sections shown on the plans or as established by the Engineer. Earthwork shall include regular, borrow, undercut and minor structure excavation; constructing embankments; disposing of surplus and unsuitable material; shaping; compaction; sloping; dressing; and temporary erosion control work.

### 303.02—Materials.

- (a) Borrow excavation shall consist of approved material required for the construction of the roadway and shall be obtained from approved sources outside the project limits. Borrow excavation shall conform to AASHTO M57 and the requirements herein.
- (b) Materials for temporary silt fences, geotextile fabric silt barriers, and filter barriers shall conform to the requirements of Sections 242 and 245.
- (c) Geotextile materials used for embankment stabilization shall conform to the requirements of Section 245.