

**8-13 MONUMENT CASES****8-13.1 Description**

This Work consists of furnishing and placing monument cases and covers, in accordance with the Standard Plans and these Specifications, in conformity with the lines and locations shown in the Plans or as staked.

**8-13.2 Materials**

Materials shall meet the requirements of the following sections:

Concrete	6-02
Monument Cases and Covers	9-22.1

**8-13.3 Construction Requirements**

The concrete base shall be placed on a well compacted foundation. The placing of the monument case and base shall be performed in a manner that will not disturb the monument.

The monument case shall be installed by the Contractor after the final course of surfacing has been placed. After the monument case has been in place for a minimum of 3-days, the Roadway surface shall be patched in a workmanlike manner.

When the monument case and cover are placed in cement concrete pavement, the concrete base will not be required.

The monument will be furnished and set by the Engineer.

**8-13.4 Measurement**

Measurement of monument case and cover will be by the unit for each monument case and cover furnished and set.

**8-13.5 Payment**

Payment will be made in accordance with Section 1-04.1, for the following Bid item when included in the Proposal:

“Monument Case and Cover”, per each.