

### 203.3

#### 203.3-CONSTRUCTION METHODS:

The work shall include dismantling and storing, or disposing of designated structures by such methods as are specified on the Plans. If the old structure is to be reerected, it shall be carefully dismantled without unnecessary damage, the parts matchmarked, and carefully stored as required by the Plans or as directed by the Engineer. Disposal, if required, shall be accomplished in accordance with the provisions of 201. The bridge may contain lead base paint and the Contractor shall provide protection for their Workers as per the requirements of 29 CFR 1926.62.

#### 203.4-METHOD OF MEASUREMENT:

"Dismantling Structures" will be measured as a complete unit and shall include the complete execution of the work of dismantling, handling, storing, or removing all of the structures so designated.

#### 203.5-BASIS OF PAYMENT:

The quantity, determined as provided above, will be paid for at the contract lump sum price bid for this item, which price and payment shall be full compensation for completing the item, including removal and disposition of all falsework, debris and refuse resulting from the work, leaving the premises in good condition.

The cost of preparation and transmittal of the demolition/dismantling plan shall be included in the lump sum bid for Item 203001-.\*.

#### 203.6-PAY ITEM:

ITEM	DESCRIPTION	UNIT
203001-*	DISMANTLING STRUCTURE	LUMP SUM

\* Sequence number

## SECTION 204 MOBILIZATION

#### 204.1-DESCRIPTION:

This work shall consist of the performance of construction preparatory operations, including the movement of personnel and equipment to the project site and for the establishment of the Contractor's offices, buildings and other facilities necessary to begin work on a substantial phase of the contract. The bid for mobilization shall be a lump sum. When Item 204001-\*, "Mobilization", is not included as a separate bid item it is specifically understood that the cost of mobilization will be included in the unit bid price for each individual item.

#### 204.2-MATERIALS:

Not specified.

**204.3-CONSTRUCTION METHODS:**

Not Specified.

**204.4-METHOD OF MEASUREMENT:**

The method of measurement will be a lump sum.

<b>TOTAL ORIGINAL CONTRACT AMOUNT, INCLUDING MOBILIZATION</b>		<b>TOTAL LIMITS FOR PARTIAL PAYMENTS</b>
More Than	To and Including	
0	\$100,000	10 percent of total contract amount
\$100,000	\$500,000	\$10,000, plus three percent times (total contract minus \$100,000)
\$500,000	\$1,500,000	\$22,000, plus two percent times (total contract minus \$500,000)
\$1,500,00	More	\$42,000, plus one percent times (total contract minus \$1,500,000)

**204.5-BASIS OF PAYMENT:**

Partial payments will be made as the work progresses in accordance with the following schedule.

- i. 1.5% of the original contract amount or 50% of the amount bid for mobilization, whichever is less, will be released to the Contractor as the first estimate payable, not less than 15 days after the start of work at the project site.
- ii. 1.5% of the original contract amount or the remaining 50% of the amount bid for mobilization, whichever is less, shall be released with the estimate payable 30 days after the first estimate.

Upon completion of all work on the project, payment of any amount bid for mobilization in excess of 3% of the original contract amount will be released.

Nothing herein shall be construed to limit or preclude partial payments otherwise provided for by the contract.

No deduction will be made, nor will any increase be made, in the lump sum mobilization item amount regardless of decreases or increases in the final total contract amount or for any other cause.

**204.6-PAY ITEM:**

<b>ITEM</b>	<b>DESCRIPTION</b>	<b>UNIT</b>
204001-*	MOBILIZATION	LUMP SUM

\* Sequence number

**205 THROUGH 206-BLANK**